

SLF-3/30/92

FINAL DRAFT
ENVIRONMENTAL PRIORITIES INITIATIVE
PRELIMINARY ASSESSMENT REPORT
E L BETH LTD
PREPARED UNDER


WORK ASSIGNMENT NO. 019-2JZZ
CONTRACT NO. 68-W9-0051


MARCH 30, 1992

SUBMITTED BY:


CLAIRE BARUXIS
SITE MANAGER


GARY ROJEK
PROJECT MANAGER


DENNIS STAINKEN, Ph.D.
WORK ASSIGNMENT MANAGER


RONALD M. NAMAN
SUBCONTRACT OFFICE MANAGER

198549



**This Report was conducted
under the following
USEPA Documentation Procedure**

**Guidance for Performing Preliminary
Assessments Under CERCLA
Publication 9345.0-01A**

SITE SUMMARY AND RECOMMENDATION

The E L Beth Ltd Site (E L Beth) is located off of High Street in a light industrial and residential area of Perth Amboy, Middlesex County, New Jersey. The property is bordered to the east by the Arthur Kill, and to the south, west, and north by industrial properties. The adjacent property to the south is also a CERCLIS site. The EL Beth property consists of a 0.66-acre area of land and a pier, approximately 0.41 acre in size, that extends into the Arthur Kill (Ref. Nos. 2; 4, pp. 4, 5; 27; 32). A factory was located on the pier; the factory and pier, as well as company records, were destroyed in a May 1981 fire. The site has been inactive since the time of that fire (Ref. Nos. 3; 4, pp. 3, 4; 6; 7, pp. 8, 15). Figures 1 and 2 present a Site Location Map and a Site Map, respectively.

E L Beth was a foundry and secondary smelting operation that produced solder, casting metals, and lead alloys. Specifically, lead and tin scrap materials were melted and alloyed and cast into ingots. In addition, gold was recovered from electronic scrap (Ref. Nos. 2; 4, p. 5; 7, p. 15; 8, p. 5). The facility reportedly was established in October 1975 under the ownership of M.C. Canfield Sons; in late 1977 the present owners purchased the facility, and operated it as a subsidiary of M.C. Canfield Sons from 1978 until 1981. From 1981 to the present, the property has been in the names of the individual owners. The owners submitted a RCRA Part A permit application in November 1980 indicating that the facility would treat, store, or dispose of hazardous waste (Ref. Nos. 2; 4, p. 1; 8, p. 5).

In May 1981 an on-site fire caused by an overheated kiln destroyed the facility. An earlier fire had occurred on the same tax block in July 1980. The 1980 fire began at a property located southeast of both the E L Beth site and the adjacent CERCLIS site, and spread through much of the block. The 1980 fire spread to the CERCLIS site adjacent to E L Beth; it is not certain, however, whether this fire reached the E L Beth property (Ref. Nos. 28, 32). In March 1983 the owner requested that the facility be delisted as a treatment, storage, or disposal facility; the facility was delisted by the New Jersey Department of Environmental Protection (NJDEP) in February 1985 (Ref. Nos. 3; 5; 6; 7, p. 15). NJDEP inspectors noted in January 1985 and June 1990 that hazardous materials were not being stored on site at the times of those inspections (Ref. Nos. 4, 5, 7). No wastes in containers are presently stored at the E L Beth site. However, much rubble, including a few burned or rusted drums, is now present at the fire-damaged factory and pier (Ref. No. 8, p. 4; see also photographs in Attachment 1).

According to the facility's Hazardous Waste Permit Application, the wastes that were generated were corrosive materials and emission control dust/sludge from secondary lead smelting. "D000" waste was also reported. (It is not known what the applicant intended by the use of the designation "D000".) Wastes were reportedly contained in drums on concrete, outdoors and indoors (Ref. Nos. 2; 8, pp. 4, 5, 7; 29). During an on-site reconnaissance conducted by HALLIBURTON NUS Environmental Corporation on March 4, 1992, imprints of approximately 10 drums were noted in blacktop at the site, near the shoreline along the south property boundary (Ref. No. 8, pp. 4, 7; see also photograph No. 1P-12 in Attachment 1). In the November 1980 permit application, the owner reported an estimated annual quantity of 50,000 pounds of hazardous wastes in drums, and a process design capacity of 2,500 gallons (Ref. Nos. 2, 9). Available information indicates that no hazardous waste transportation manifests were generated by the facility after 1980. The owner informed an NJDEP inspector that wastes may have been transported to his new industrial facility in Edison, New Jersey prior to the 1981 fire. The NJDEP inspector noted that this action would have represented a violation of hazardous waste transportation regulations, but recommended no enforcement action. It is not known whether any hazardous wastes were present on site at the time of the May 1981 fire (Ref. Nos. 4, pp. 3, 4; 5; 28).

The former drum storage areas, and the large amount of debris now present at the fire-damaged factory and pier, represent a potential for contaminant migration to the Arthur Kill, which is considered to be a sensitive environment and in which limited fishing may be conducted (Ref. Nos. 21, 23 through 26). Contaminant migration to the Arthur Kill is favored by overland migration across the paved surface of the site, storm sewer discharge, and the proximity of the pier to the water surface. Particulates and other air contaminants potentially present could reach nearby worker and residential

SITE SUMMARY AND RECOMMENDATION (CONTD)



populations, and sensitive environments. It is not likely that contaminants would reach an aquifer that supplies potable water, as the site reportedly was paved prior to E L Beth activities. The nearest known potable water supply wells are located more than 2 miles from the site and are separated from the site by the Raritan River. During a HALLIBURTON NUS Environmental Corporation on-site reconnaissance that was conducted on March 4, 1992, it was noted that the site is not entirely fenced; the presence of graffiti indicates that outsiders have access to the property.

The E L Beth Site is recommended for a **SCREENING SITE INSPECTION** based upon the following: the possibility that wastes formerly stored in drums on site may have been released to the Arthur Kill; contaminants may be present in debris at the fire-damaged pier, and could readily migrate to the Arthur Kill; and the potential for air migration of contaminants that may be present in debris to affect nearby workers and residents. The Arthur Kill represents a concern with respect to both sensitive environments and human food chain considerations. Surface water and/or sediment sampling is recommended, as well as removal of the debris that is now present at the pier.

**FIGURE 1**

SCALE: 1" = 2000'

← HIGH STREET
APPROXIMATELY
640' WEST



LEGEND:

- ▲ RUSTED OR BURNED DRUM
- LOCATION OF OPEN CONTAINER OF ROOFING TAR WITH ASBESTOS, AND SMALL, OPEN SOLVENT CAN

— X — FENCE

SITE MAP
E L BETH LTD
PERTH AMBOY, N.J.

(NOT TO SCALE)

FIGURE 2

SITE ASSESSMENT REPORT: SITE INSPECTION

PART I: SITE INFORMATION

1. Site Name/Alias E L Beth Ltd
Street 500 High Street
City Perth Amboy State New Jersey Zip 08861
2. County Middlesex County Code 023 Cong. Dist. 06
3. CERCLIS ID No. NJD067484923
4. Block No. 238 Lot No. 4 and 4.18
5. Latitude 40° 30' 46" N Longitude 74° 15' 34" W
USGS Quad. Perth Amboy
6. Approximate size of site 1.07 acres
7. Owner Robert Silverman and Jack Silverman Tel. No. (201) 379-9447
Street 23 Audubon Court
City Short Hills State New Jersey Zip 07078
8. Operator (Same) Tel. No. _____
Street _____
City _____ State _____ Zip _____
9. Type of Ownership
☒ Private ☐ Federal ☐ State
☐ County ☐ Municipal ☐ Unknown ☐ Other _____
10. Owner/Operator Notification on File
☒ RCRA 3001 Date 10/9/80 ☐ CERCLA 103c Date _____
☐ None ☐ Unknown
11. Permit Information

Permit	Permit No.	Date Issued	Expiration Date	Comments
RCRA Part A	N/A	1980	N/A	Site delisted in 1985
"Other"	46339	Unknown	Unknown	Reportedly issued by NJDEP
"Other"	41104	Unknown	Unknown	Reportedly issued by NJDEP

12. Site Status

☐ Active ☒ Inactive ☐ Unknown

13. Years of Operation 1975 to 1981

14. Identify the types of waste sources (e.g., landfill, surface impoundment, piles, stained soil, above- or below-ground tanks or containers, land treatment, etc.) on site. Initiate as many waste unit numbers as needed to identify all waste sources on site.

(a) Waste Sources

Waste Unit No.	Waste Source Type	Facility Name for Unit
1	<u>Containers</u>	<u>Drums</u>
2	<u>Scrap Metal or Junk Pile</u>	<u>Pier</u>

(b) Other Areas of Concern

Identify any miscellaneous spills, dumping, etc. on site; describe the materials and identify their locations on site.

All areas of concern are discussed in Part II, Waste Source Information.

Ref. Nos. 1, 2, 6, 27, 29, 32, 33

15. Information available from

Contact Sandy Foose Agency U.S. EPA Tel. No. (908) 906-6808

Preparer Claire Baruxis Agency HALLIBURTON NUS Environmental Corporation

Date March 30, 1992

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following items.

Waste Unit 1 - Containers (Drums)

Source Type

<input type="checkbox"/> Landfill	<input type="checkbox"/> Land Treatment
<input type="checkbox"/> Surface Impoundment	<input type="checkbox"/> Chemical Waste Pile
<input checked="" type="checkbox"/> Drums	<input type="checkbox"/> Scrap Metal or Junk Pile
<input type="checkbox"/> Tanks/Containers	<input type="checkbox"/> Tailings Pile
<input type="checkbox"/> Contaminated Soil	<input type="checkbox"/> Trash Pile
<input type="checkbox"/> Pile	<input type="checkbox"/> Other

Description:

Waste material was reportedly stored in drums on concrete, indoors and outdoors. The facility's RCRA Part A submittal indicated drum storage near the western part of the site and also to the north, near the Arthur Kill. During the HALLIBURTON NUS on-site reconnaissance on March 4, 1992, the owner indicated that on-site drum storage was along the western boundary of the property, to the south of the garage. During the reconnaissance, drum imprints were noted in blacktop paving, along the south property boundary, next to the Arthur Kill; a storm sewer grating is located next to the drum imprints. According to the Hazardous Waste Permit Application that was filed by the facility owner, corrosive material and emission control dust/sludge from secondary lead smelting were generated as wastes at the facility. "D000" waste was also reported. (It is not known what the owner intended by the use of the designation "D000".) Releases of unknown hazardous materials may have occurred during the 1981 on-site fire.

Hazardous Waste Quantity

The owner reported 20,000 pounds of emission control dust/secondary lead smelting sludge, 10,000 pounds of corrosive waste, and 20,000 pounds of "D000" waste as an estimated annual quantity of waste stored in drums.

Hazardous Substances/Physical State

Metallic constituents would be present in the emission control dusts. Chromium, lead, and cadmium may have been constituents of the secondary lead smelting sludge. Corrosive material that reportedly included ammonium chloride may have been present as solidified material or sludge.

SWMU - Specific Conclusion

It is possible that waste materials may have been deposited on the ground surface and migrated to the Arthur Kill; additional information, such as surface water and/or sediment sample data, is needed before a determination can be made regarding any possible release of hazardous substances from this unit.

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following items.

Waste Unit 2 - Pier

Source Type

<input type="checkbox"/> Landfill	<input type="checkbox"/> Land Treatment
<input type="checkbox"/> Surface Impoundment	<input type="checkbox"/> Chemical Waste Pile
<input type="checkbox"/> Drums	<input checked="" type="checkbox"/> Scrap Metal or Junk Pile
<input type="checkbox"/> Tanks/Containers	<input type="checkbox"/> Tailings Pile
<input type="checkbox"/> Contaminated Soil	<input type="checkbox"/> Trash Pile
<input type="checkbox"/> Pile	<input type="checkbox"/> Other

Description:

The former manufacturing plant at the E L Beth facility was located on pilings (referred to herein as a pier) in the Arthur Kill. The pier location is designated as lot 4.18, in Block 238; this lot is approximately 0.41 acre in size. The manufacturing plant and pier were destroyed in a fire that originated in one of the facility's kilns in May 1981. Much rubble is now present at the pier. A few burned or rusted drums were noted among the rubble during the HALLIBURTON NUS on-site reconnaissance that was conducted on March 4, 1992. It appears that contaminants that may be associated with debris on the pier could migrate to the Arthur Kill as a result of surface water runoff, air migration, or possible collapse of the badly damaged structure.

Hazardous Waste Quantity

The quantity of waste that may currently be (or may have once been) present in debris at the pier is not known.

Hazardous Substances/Physical State

Hazardous substances that may be present include lead, chromium, and cadmium, which were once generated as wastes on site, and unknown substances that may have been generated during the 1981 fire. Such substances, if present, would be associated with particulate debris or other solids.

SWMU - Specific Conclusion

Based upon knowledge of wastes formerly generated at the facility, and the proximity of the plant and exposed debris to the Arthur Kill, it is possible that a release of contaminants such as lead, cadmium, or chromium, or of unknown fire-generated materials, may have occurred. Additional information, such as surface water and/or sediment sample data, is needed before a determination can be made regarding any possible release of hazardous substances from this unit.

Ref. Nos. 2; 4, p. 3; 8, pp. 4, 5; 27; 28; 29; 30

PART III. SAMPLING RESULTS

EXISTING ANALYTICAL DATA

No analytical data exist for the site.

PART IV. HAZARD ASSESSMENT

GROUNDWATER ROUTE

- 1. Describe the likelihood of a release of contaminant(s) to the groundwater as follows: observed release, suspected release, or none. Identify contaminants detected or suspected and provide a rationale for attributing them to the site. For observed release, define the supporting analytical evidence.**

It is not likely that site contaminants would reach the aquifer of concern. Paving that is present would favor overland contaminant migration to the Arthur Kill. Moreover, a confining unit of clay overlies the aquifer of concern.

Ref. Nos. 8, pp. 4, 5; 10, pp. 15, 17, 18

- 2. Describe the aquifer of concern; include information such as depth, thickness, geologic composition, areas of karst terrain, permeability, overlying strata, confining layers, interconnections, discontinuities, depth to water table, groundwater flow direction.**

The site is located within the northern part of the New Jersey Coastal Plain physiographic province. The aquifer of concern is the Farrington Sand member of the Raritan Formation, the upper surface of which occurs at a depth of approximately 90 feet below sea level in the area of the site. Geologic units that overlie the Farrington Sand near the site include the Wisconsin Drift terminal moraine, which mantles the area, and the Woodbridge Clay. The Wisconsin Drift has a thickness of approximately 50 feet near the site, and consists of a mixture of red clay, sand, and gravel, and a few boulders. It is reported that in most areas this material is fairly impermeable (Ref. No. 10, pp. 3, 12, 15; Ref. No. 11, pp. 9, 10, 11, 15, 16, 17, 18; Ref. No. 12, p. 3; Ref. No. 13). It is likely that shallow groundwater flow in this material is influenced by tidal water. The Woodbridge Clay, an extensive, impervious confining layer that is approximately 40 feet thick in the area of the site, lies between the drift material and the Farrington Sand. The Woodbridge Clay consists of micaceous silts and clays; its permeability is estimated to be 10^{-7} cm/sec or less (Ref. No. 10, pp. 15, 17, Ref. No. 11, p. 17; Ref. No. 12, p. 3; Ref. No. 18).

In Middlesex County the Farrington Sand consists of coarse- to fine-grained sand with lignite and pyrite, and locally it contains clay beds. The permeability of the Farrington Sand is 10^{-3} to 10^{-6} cm/sec. Its thickness and depth increase to the southeast. From its outcrop north of the site, to areas south of the Raritan River, it thickens from a feather edge to approximately 130 feet, and has a reported dip to the southeast of 45 to 60 feet per mile (Ref. No. 10, pp. 3, 10, 11, 13, 15; Ref. No. 11, pp. 6, 18, 19; Ref. No. 12, p. 3; Ref. No. 13; Ref. No. 18;). The direction of groundwater flow in the Farrington Sand is to the south; however, the hydraulic connection across the Raritan River is restricted to some extent by discontinuities in the formation and the presence of relatively impermeable mud (Ref. No. 10, p. 10; Ref. No. 11, pp. 10, 18, 19; Ref. No. 12, p. 7).

- 3. What is the depth from the lowest point of waste disposal/storage to the highest seasonal level of the saturated zone of the aquifer of concern?**

The lowest known point of waste storage is the paved surface on which drums were located; the estimated depth from this point of waste storage to the estimated potentiometric surface of the Farrington Sand Aquifer is approximately 50 to 60 feet.

Ref. Nos. 8; 10, p. 19; 14

4. Identify and determine the distance to and depth of the nearest well that is currently used for drinking purposes?

Public water supply wells in the Borough of South Amboy are located between 2 and 3 miles south of the site and are separated from the site by the Raritan River. These wells draw from the Old Bridge Sand Aquifer at a depth of approximately 48 feet, and are currently reserved for emergency use only. Five of the Borough of Sayreville's public water supply wells, also located across the Raritan River and approximately 3.5 miles south of the site, are the nearest known wells that are currently used for drinking purposes. Two of the wells are screened at a depth of approximately 250 feet, and draw from the Farrington Sand Aquifer; three of the wells, screened at a depth of approximately 80 to 90 feet, draw from the Old Bridge Sand Aquifer. The Old Bridge Sand has not been identified in outcrop anywhere north of the Raritan River, and thus is not included in the description of the aquifer of concern. Hydraulic continuity across the Raritan River is restricted to some extent by aquifer discontinuities and relatively impermeable mud beneath the river bed.

Ref Nos. 10, p. 10; 14; 15; 16; 19

5. If a release to groundwater is observed or suspected, determine the number of people that obtain drinking water from wells that are documented or suspected to be located within the contamination boundary of the release.

It is not suspected that site contaminants would have reached the Farrington Sand, as the site is paved, and a confining geologic unit overlies the aquifer. Moreover, the distance to the nearest potable wells and hydraulic interference of the Raritan River further reduce the likelihood of contaminant migration to supplies obtained from the Farrington Sand Aquifer.

Ref. Nos. 8, pp. 4, 5; 10, pp. 17, 18; 11 through 13

6. Identify the population served by wells that are not expected to be contaminated located within 4 miles of the site that draw from the aquifer of concern.

<u>Distance</u>	<u>Population</u>
0 - ¼ mi	0
> ¼ - ½ mi	0
> ½ - 1 mi	0
> 1 - 2 mi	0
> 2 - 3 mi	8,500
> 3 - 4 mi	12,000

State whether groundwater is blended with surface water, groundwater, or both before distribution.

The well field located at a distance of 3 to 4 miles from the site consists of two wells that draw from the aquifer of concern and three that draw from the more shallow Old Bridge Sand Aquifer. The water from the deep and shallow wells is mixed. Recharge water from the South River is also mixed with the well water.

Ref. No. 16

7. Is there a wellhead protection area within 4 miles of the site?

No; wellhead protection areas have not yet been delineated in the state of New Jersey, and there are no known wells used for potable purposes on Staten Island, New York, which is also located within 4 miles of the site.

Ref. Nos. 17, 19, 20

8. Does a waste source overlie a designated or proposed wellhead protection area? If a release to groundwater is observed or suspected, does a designated or proposed wellhead protection area lie within the contaminant boundary of the release?

Not applicable.

Ref. Nos. 17, 20

9. Identify uses of groundwater within 4 miles of the site (i.e. private drinking source, municipal source, commercial, irrigation, unusable).

Groundwater obtained within 4 miles of the site is used for industrial, commercial, and potable water supply purposes. The potable water wells are located across the Raritan River, a large water body.

Ref. No. 14, 15, 16

SURFACE WATER ROUTE

10. Describe the likelihood of a release of contaminant(s) to surface water as follows: observed release, suspected release, or none. Identify contaminants detected or suspected and provide a rationale for attributing them to the site. For observed release, define the supporting analytical evidence.

A release of contaminants to the Arthur Kill, located adjacent to the site, is suspected. Contaminants that may be associated with the wastes generated at the site include lead, chromium, and cadmium. Unknown contaminants may have also been generated or released during a 1981 on-site fire, which destroyed the facility. Much rubble remains at the fire-damaged pier, where the facility's manufacturing plant was located. A few rusted or burned drums were noted among the rubble during the HALLIBURTON NUS on-site reconnaissance that was conducted on March 4, 1992.

Ref. Nos. 2; 8, p. 4; 28; 29; 30

11. Identify the nearest downslope surface water. If possible, include a description of possible surface drainage patterns from the site.

The Arthur Kill adjoins the land portion of the site and is located beneath the pier on which the manufacturing plant was located. The site is very level, but surface drainage would be expected to flow to the Arthur Kill as a result of flow over the paved surface and discharge through the storm sewer that is present. During the HALLIBURTON NUS on-site reconnaissance that was conducted on March 4, 1992, drum imprints were noted in an area of blocktop paving located next to the Arthur Kill; a storm sewer grating is also located next to the drum imprints. Drainage also flows through the pier, where much rubble is present, directly to the Arthur Kill.

Ref. Nos. 2; 8, pp. 4, 7, 11; 28

12. What is the distance in feet to the nearest downslope surface water? Measure the distance along a course that runoff can be expected to follow.

The Arthur Kill adjoins the land portion of the site and is located beneath the pier on which the manufacturing plant was located.

Ref. Nos. 2; 8, p. 4; 28

13. Determine the type of floodplain that the site is located within.

The site is primarily located within the 100-year flood boundary; a portion of the property is located within the 100-year to 500-year flood boundaries.

Ref. No. 22

14. Identify drinking water intakes in surface waters within 15 miles downstream of the point of surface water entry. For each intake identify: the name of the surface water body in which the intake is located, the distance in miles from the point of surface water entry, population served, and stream flow at the intake location.

<u>Intake</u>	<u>Distance</u>	<u>Population Served</u>	<u>Flow (cfs)</u>
---------------	-----------------	--------------------------	-------------------

There are no drinking water intakes along surface water within 15 miles downstream of the site.

Ref. Nos. 16, 21, 23

15. Identify fisheries that exist within 15 miles downstream of the point of surface water entry. For each fishery specify the following information:

<u>Fishery Name</u>	<u>Water Body Type</u>	<u>Flow (cfs)</u>	<u>Saline/Fresh/Brackish</u>
Arthur Kill	Coastal Tidal Water	Not Applicable	Saline
Raritan Bay	Coastal Tidal Water	Not Applicable	Saline
Raritan River	Coastal Tidal Water	Not Applicable	Brackish
Lower NY Bay	Coastal Tidal Water	Not Applicable	Saline
Sandy Hook Bay	Coastal Tidal Water	Not Applicable	Saline

Ref. Nos. 23, 25, 26

16. Identify surface water sensitive environments that exist within 15 miles of the point of surface water entry. For each sensitive environment specify the following:

<u>Sensitive Environment</u>	<u>Water Body Type</u>	<u>Flow (cfs)</u>	<u>Wetland Frontage (miles)</u>
Federally-listed endangered bird species (Arthur Kill, Raritan River)	Coastal Tidal Water	Not Applicable	
State-listed endangered fish species (Arthur Kill, Raritan River, Low New York Bay, Sandy Hook Bay)	Coastal Tidal Water	Not Applicable	
State-listed threatened or endangered breeding bird population. (Sandy Hook Bay)	Coastal Tidal Water	Not Applicable	
Wetland	Coastal Tidal Water	Not Applicable	6.3
Wetland (Federally Protected; Raritan River)	Coastal Tidal Water	Not Applicable	

Ref. Nos. 23, 24

17. If a release to surface water is observed or suspected, identify any intakes, fisheries, and sensitive environments from question Nos. 12-14 that are or may be located within the contamination boundary of the release.

Intake: Not Applicable

Fishery: Arthur Kill

Sensitive Environment: • Federally-listed endangered bird species at Arthur Kill
• State-listed endangered fish species at Arthur Kill

Ref. Nos. 23 through 26

SOIL EXPOSURE PATHWAY

18. Determine the number of people that occupy residences or attend school or day care on or within 200 feet of the site property.

There are no residences, schools, or day care facilities on or within 200 feet of the site property.

Ref. No. 8, pp. 14, 15

19. Determine the number of people that regularly work on or within 200 feet of the site property.

It is estimated that no more than 100 people may work within 200 feet of the site property; a large warehouse is located within 200 feet of the site, and work is ongoing outdoors, next to the site.

Ref. No. 8

20. Identify terrestrial sensitive environments on or within 200 feet of the site property.

There are no known terrestrial sensitive environments on or within 200 feet of the site property.

Ref. Nos. 8, 23

AIR ROUTE

21. Describe the likelihood of release of contaminants to air as follows: observed release, suspected release, or none. Identify contaminants detected or suspected and provide a rationale for attributing them to the site. For observed release define the supporting analytical evidence.

It is suspected that a potential exists for release to air of particulates and other contaminants that may be present in debris at the fire-damaged factory. Unknown contaminants may have been generated during the on-site fire that occurred in 1981. Contaminants that may be associated with the wastes formerly generated include lead, chromium, and cadmium. During the HALLIBURTON NUS on-site reconnaissance that was conducted on March 4, 1992, ambient readings that were obtained during continuous air monitoring with an OVA and HNu did not significantly exceed background. Locations of above background readings include the following: at an opening in the concrete at the interface of the land-based portion of the site and the pier; from an open container labeled "roofing tar with asbestos" (apparently not associated with former site operations); and at an open container labeled "another pentanone

product", approximately 1 gallon in size.

Ref. No. 8, pp. 4, 9, 12, 13

22. Determine populations that reside within 4 miles of the site.

<u>Distance</u>	<u>Population</u>
0 - ¼ mi	279
> ¼ - ½ mi	4,567
> ½ - 1 mi	19,400
> 1 - 2 mi	19,821
> 2 - 3 mi	25,530
> 3 - 4 mi	43,847

Ref. No. 31

23. Identify sensitive environments, including wetlands and associated wetlands acreage, within ½ mile of site.

<u>0 - ¼ mile</u>	<u>¼ - ½ mile</u>
<u>Sensitive Environments/Wetland Acreage</u>	<u>Sensitive Environments/Wetland Acreage</u>
<ul style="list-style-type: none">• Possible presence of federally-listed endangered bird species and state-listed endangered fish species.	<ul style="list-style-type: none">• Possible presence of federally-listed endangered bird species and state-listed endangered fish species.• Approximately 2.3 acres of wetland

Ref. Nos. 23, 24

24. If a release to air is observed or suspected, determine the number of people that reside or are suspected to reside within the area of air contamination from the release.

Approximately 280 people live within 0.25 mile of the site.

Ref. No. 31

25. If a release to air is observed or suspected, identify any sensitive environments, listed in question No. 23, that are or may be located within the area of air contamination from the release.

The potential exists for the presence of a federally-listed endangered bird species and a state-listed endangered fish species within 0.5 mile of the site, and approximately 2.3 acres of wetland are present within 0.5 mile of the site. The potential distance of the migration of particulates that might remain from site operations is not known.

Ref. Nos. 8; 23; 24

ATTACHMENT 1

EXHIBIT A

PHOTOGRAPH LOG

**E L BETH LTD
PERTH AMBOY, NEW JERSEY**

ON-SITE RECONNAISSANCE: MARCH 4, 1992

PHOTOGRAPH INDEX

**E L BETH LTD
PERTH AMBOY, NEW JERSEY
MARCH 4, 1992**

ALL PHOTOGRAPHS TAKEN BY CLAIRE BARUXIS

<u>PHOTO NUMBER</u>	<u>DESCRIPTION</u>	<u>TIME</u>
1P-1, 1P-3	Photograph taken from the southeastern corner of the land portion of the site, facing west to northeast.	1045
1P-4, 1P-5	Photograph taken from the southeastern corner of the land portion of the site facing north.	1045
1P-6, 1P-7, 1P-8	View of the fire damaged factory and pier along the Arthur Kill, at the E L Beth site.	1048
1P-9	Closer view of the fire-damaged pier.	1050
1P-10	Closer view of another part of the fire-damaged pier, taken from the land portion of the site.	1051
1P-11	Photograph of the location of OVA reading, at the interface of the pier and the land portion of the site.	1055
1P-12	Photograph of a storm sewer grating, blacktop area with drum imprints, and broken fencing, taken facing the southeastern corner of the land portion of the site.	1058
1P-13	Photograph of the on-site conduit that contains soil and debris, and the adjacent property along the northern border of the E L Beth site, taken facing northeast.	1105
1P-15	Photograph of debris and the former garage at the site, taken facing west.	1112
1P-16	Photograph facing southeast, of the blacktop paving along the southern border of the site. A CERCLIS site borders the E L Beth property to the south.	1115
1P-17	Photograph of debris and the former drum staging ramp at the site, taken facing west.	1117
1P-18	A former on-site drum storage location along the western border of the property, next to the garage.	1119
1P-19	Photograph of debris and an overturned can at the former drum staging ramp. The label on the can describes the contents as "roofing tar with asbestos", and "check-a-leak plastic roof cement". An OVA reading and an HNu reading were obtained at the overturned can.	1120

**E L BETH LTD
PERTH AMBOY, NEW JERSEY
MARCH 4, 1992**

ALL PHOTOGRAPHS TAKEN BY CLAIRE BARUXIS

<u>PHOTO NUMBER</u>	<u>DESCRIPTION</u>	<u>TIME</u>
1P-22	Photograph of the entrance to the properties at 500 High Street, taken from the street.	1150

PHOTOGRAPH LOG

J030-RP
Rev. No. 0

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-1, 1P-3

March 4, 1992

1045

Photograph taken from the southeastern corner of the land portion of the site, facing west to northeast.

PHOTOGRAPH LOG

J030-RP
Rev. No. 0

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-4, 1P-5

March 4, 1992

Photograph taken from the southeastern corner of the land portion of the site facing north.

1045

PHOTOGRAPH LOG

J030-RP
Rev. No. 0

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-6, 1P-7, 1P-8 March 4, 1992
View of the fire damaged factory and pier along the Arthur Kill, at the E L Beth site.

1048

PHOTOGRAPH LOG

J030-RP
Rev. No. 0

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-9

March 4, 1992
Closer view of the fire-damaged pier.

1050



1P-10

March 4, 1992
Closer view of another part of the fire-damaged pier, taken
from the land portion of the site.

1051

PHOTOGRAPH LOG

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-11

March 4, 1992

Photograph of the location OVA reading, at the interface of the pier and the land portion of the site.

1055



1P-12

March 4, 1992

Photograph of a storm sewer grating, blacktop area with drum imprints, and broken fencing, taken facing the southeastern corner of the land portion of the site.

1058

PHOTOGRAPH LOG

J030-RP
Rev. No. 0

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-13

March 4, 1992

Photograph of the on-site conduit that contains soil and debris, and the adjacent property along the northern border of the E L Beth site, taken facing northeast.

1105



1P-15

March 4, 1992

Photograph of debris and the former garage at the site, taken facing west.

1112

PHOTOGRAPH LOG

J030-RP
Rev. No. 0

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-16

March 4, 1992

Photograph facing southeast, of the blacktop paving along the southern border of the site. A CERCLIS site borders the E L Beth property to the south.

1115



1P-17

March 4, 1992

Photograph of debris and the former drum staging ramp at the site, taken facing west.

1117

PHOTOGRAPH LOG

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-18

March 4, 1992

1119

A former on-site drum storage location along the western border of the property, next to the garage.



1P-19

March 4, 1992

1120

Photographs of debris and an overturned can at the former drum staging ramp. The label on the can describes the contents as "roofing tar with asbestos", and "check-a-leak plastic roof cement". An OVA reading and an HNu reading were obtained at the overturned can.

PHOTOGRAPH LOG

J030-RP
Rev. No. 0

E L BETH LTD
PERTH AMBOY, NEW JERSEY



1P-22

March 4, 1992

Photograph of the entrance to the properties at 500 High Street,
taken from the street.

1150

ATTACHMENT 2

REFERENCES

1. Acknowledgement of Notification of Hazardous Waste Activity (Verification). E L Beth. October 9, 1980.
2. U.S. EPA General Information Form 3510-1 Consolidated Permits Program, postmarked December 13, 1980, and Hazardous Waste Permit Application 3510-3, dated November 18, 1980. E L Beth Ltd.
3. Letter from Robert M. Silverman, E.L. Beth Limited, to Frank Coolick, NJDEP Bureau of Hazardous Waste Engineering. March 14, 1983.
4. NJDEP Generator and TSD facility Inspection Form. E.L. Beth Ltd., EPA ID No. NJD067484923. January 16, 1985.
5. Memorandum from Linda Zaninelli to file through Fred Sickels (both of NJDEP), Subject: Phone Conversations. January 17, 1985.
6. Letter from Frank Coolick, NJDEP, Bureau of Hazardous Waste Engineering, to Robert Silverman, E.L. Beth. February 14, 1985.
7. NJDEP Hazardous Waste Management Facility Inspection Report. E.L. Beth Ltd., EPA ID No. NJD067484923. June 4, 1990.
8. Field Notebook Number HNUS005, E L Beth Ltd Site, NOMAD No. J030, On-site Reconnaissance, HALLIBURTON NUS Environmental Corporation, Iselin, N.J., March 4, 1992.
9. Project Note: Waste Quantity Reported for the E L Beth Site. By Claire Baruxis, HALLIBURTON NUS Environmental Corporation, March 27, 1992.
10. Geohydrology and Digital-Simulation Model of the Farrington Aquifer in the Northern Coastal Plain of New Jersey. U.S. Geological Survey Water-Resources Investigations 79-106, August 1979.
11. Barksdale, H.C. et al. The Ground-Water Supplies of Middlesex County, New Jersey. Special Report 8. State of New Jersey Water Policy Commission in cooperation with the U.S. Department of the Interior, Geological Survey, 1943.
12. Middlesex County 208 Area-Wide Waste Treatment Management Planning, Task 8 - Ground-Water Analysis. Geraghty and Miller, Inc., November 1976.
13. Geological Investigations of the Coastal Plain of Southern New Jersey. Part 2: A. Hydrogeology and the Coastal Plain. Edited by Claude M. Epstein. 2nd Annual Meeting of the Geological Association of New Jersey, sponsored by Geology Program, Stockton State College, Pomona, New Jersey.
14. NJDEP, Division of Water Resources, Well Record, Permit No. 26-7714, Stolt Terminals Inc., August 20, 1985.
15. U.S. Geological Survey Groundwater Site Inventory of wells in Middlesex County. U.S.G.S., Trenton, New Jersey, January 9, 1989.
16. Project Note: Potable water supply wells located within 4 miles of the E L Beth Site. By Claire Baruxis, HALLIBURTON NUS Environmental Corporation, March 26, 1992.

REFERENCES (CONTD)

17. Telecon Note: Conversation between Dan Van Abs, NJDEPE, and Kathy Campbell, HALLIBURTON NUS Environmental Corporation, February 14, 1992.
18. Hazard Ranking System; Final Rule, 40 CFR, Part 300, Federal Register, Vol. 55, No. 241, p. 51601, December 14, 1990.
19. Four Mile Vicinity Map based on U.S. Department of the Interior Geological Survey Topographic Maps, 7.5 minute series, "Perth Amboy Quadrangle, N.J.-N.Y.", 1956, photorevised 1981; "Aurthur Kill Quadrangle, N.Y.-N.J.", 1966, photorevised 1981; "Keyport Quadrangle, N.J.-N.Y.", 1954, photorevised 1970; "South Amboy Quadrangle, N.J.-N.Y.", 1954, photorevised 1981.
20. Geologic and Geohydrologic Reconnaissance of Staten Island, New York. U.S. Geological Survey Water-Resources Investigations Report 87-4048. 1988.
21. Surface Water Quality Standards, New Jersey Administrative Code 7:9-4.1 et seq., NJDEP, Division of Water Resources, August 1989.
22. Federal Emergency Management Agency, National Flood Insurance Program, Flood Insurance Rate Map, City of Perth Amboy, Middlesex County, New Jersey, Community Panel Number 340272 0001 C, May 1, 1984.
23. Fifteen Mile Surface Water Route Map, E.L. Beth Site. Based on U.S. Department of the Interior Fish and Wildlife Service National Wetlands Inventory Maps: "Perth Amboy, N.J.-N.Y.", 1976; "South Amboy, N.J.-N.Y.-N.J.", 1976; "Aurthur Kill, N.Y.-N.Y.", 1976; "Keyport, N.J.-N.Y.", 1976; "The Narrows, N.Y.", "Sandy Hook, N.J.-N.Y.". 1976
24. Project Note: Sensitive environments located along the 15-mile surface water route downstream of the E L Beth Site, Perth Amboy, New Jersey. By Claire Baruxis, March 24, 1992.
25. Telecon Note: Conversation between Mr. Robert Soldwedel, NJDEPE, and Claire Baruxis, HALLIBURTON NUS Environmental Corporation, November 18, 1991.
26. News Paper Article, "State circulates warnings on consuming certain fish", The Record, February 9, 1992.
27. Project Note: Lot and block number, and property acreage, E L Beth Site, Perth Amboy, New Jersey. By Claire Baruxis, March 27, 1992.
28. Telecon Notes:
 - Conversation between Perth Amboy Fire Department representatives, and Claire Baruxis, HALLIBURTON NUS Environmental Corporation, March 24, 1992.
 - Conversation between Investigator Ritz, Middlesex County Prosecutor's Office, and Claire Baruxis, HALLIBURTON NUS Environmental Corporation, March 25, 1992.
29. Telecon Note: Conversation between Carol Surgens, Jones and Day, and Claire Baruxis, HALLIBURTON NUS Environmental Corporation, February 24, 1992.
30. 40 CFR, Part 261. Revised as of July 1, 1988.

REFERENCES (CONTD)

31. General Sciences Corporation, Graphical Exposure Modeling Systems (GEMS), Landover, Maryland, 1986.
32. U.S. EPA Superfund Program, Comprehensive Environmental Response, Compensation, and Liability Information System (CERCLIS). Site/Event Listing, pp. 63, 65, and Site Alias Location Listing, pp. 80, 82. March 2, 1992.
33. Election Division, New Jersey Department of State, CN304, Trenton, N.J. Congressional Districts, January 1987.

REFERENCE NO. 1



**ACKNOWLEDGEMENT OF NOTIFICATION
OF HAZARDOUS WASTE ACTIVITY
(VERIFICATION)**

This is to acknowledge that you have filed a Notification of Hazardous Waste Activity for the installation located at the address shown in the box below to comply with Section 3010 of the Resource Conservation and Recovery Act (RCRA). Your EPA Identification Number for that installation appears in the box below. The EPA Identification Number must be included on all shipping manifests for transporting hazardous wastes; on all Annual Reports that generators of hazardous waste, and owners and operators of hazardous waste treatment, storage and disposal facilities must file with EPA; on all applications for a Federal Hazardous Waste Permit; and other hazardous waste management reports and documents required under Subtitle C of RCRA.

EPA I.D. NUMBER

•NJ0067484923

INSTALLATION ADDRESS

**E L BETH
500 HIGH ST
PERTH AMBOY**

NJ 08861

**500 HIGH ST
PERTH AMBOY**

NJ 08861

REFERENCE NO. 2

FORM 1 EPA GENERAL INFORMATION (Read the "General Instructions" before starting.)		ENVIRONMENTAL PROTECTION AGENCY GENERAL INFORMATION Consolidated Permits Program (Read the "General Instructions" before starting.)		I. EPA I.D. NUMBER	
<p>II. FACILITY NAME</p> <p>III. FACILITY ADDRESS</p> <p>VI. FACILITY LOCATION</p>		<p>PLEASE PLACE LABEL IN THIS SPACE</p> <p><i>State Post</i></p>		<p>II. EPA I.D. NUMBER</p> <p>III. FACILITY NAME</p> <p>IV. FACILITY ADDRESS</p> <p>VI. FACILITY LOCATION</p>	
<p>III. FACILITY CHARACTERISTICS</p> <p>INSTRUCTIONS: Complete A through I to determine whether you need to submit any permit application. If you answer "yes" to any question, you must submit the permit application and the supplemental form listed in the parenthesis following the question. If the supplemental form is attached, if you answer "no" to each question, you need not submit any of these forms. You may answer "no" if your activity is excluded from permit requirements; see Section C of the instructions. See also, Section D of the instructions for definitions of bold-faced terms.</p>					
SPECIFIC QUESTIONS		MARK 'X'		SPECIFIC QUESTIONS	
		YES NO FORM ATTACHED			
A. Is this facility a stationary source of air pollution under the U.S. Clean Air Act? (FORM 2)		X		B. Is this a proposed facility for the production or storage of a liquid or gaseous substance which results in a discharge to waters of the U.S.? (FORM 2B)	
C. Is this facility a source which currently results in a discharge of a liquid or gaseous substance to waters of the U.S.? (FORM 2B)		X		D. Is this a proposed facility for the production or storage of a liquid or gaseous substance which results in a discharge to waters of the U.S.? (FORM 2B)	
E. Does or will this facility treat, store, or dispose of hazardous wastes? (FORM 3)		X		F. Do you or will you inject at this facility industrial or municipal effluent below the lowermost stratum containing, within one quarter mile of the well bore, underground sources of drinking water? (FORM 4)	
G. Do you or will you inject at this facility any produced water or other fluids which are brought to the surface in the production of oil or natural gas production or which are used for enhanced recovery of oil or natural gas? (FORM 4)		X		H. Do you or will you inject at this facility fluids for special processes such as mining of sulfur by the Frasch process, solution mining of minerals, or the combustion of fossil fuel of recovered energy? (FORM 4)	
I. Is this facility a proposed stationary source which is not one of the 25 industrial categories listed in the instructions and which will potentially emit 100 tons per year of any air pollutant regulated under the Clean Air Act and may affect or be located in an attainment area? (FORM 5)		X		J. Is this facility a proposed stationary source which is NOT one of the 25 industrial categories listed in the instructions and which will potentially emit 100 tons per year of any air pollutant regulated under the Clean Air Act and may affect or be located in an attainment area? (FORM 5)	
<p>IV. NAME OF FACILITY</p> <p>1. SKIP E L BETH LTD</p>					
<p>V. FACILITY CONTACT</p> <p>A. NAME & TITLE THOMAS A. PROJECT ENGR PHONE (area code & no.) 201 826 0800</p>					
<p>VI. FACILITY MAILING ADDRESS</p> <p>A. STREET OR P.O. BOX 500 HIGH STREET</p> <p>B. CITY OR TOWN PERTH AMBOY C. STATE NJ D. ZIP CODE 08861</p>					
<p>VI. FACILITY LOCATION</p> <p>A. STREET, ROUTE NO. OR OTHER SPECIFIC IDENTIFIER 500 HIGH STREET</p> <p>B. COUNTY NAME MIDDLESEX</p> <p>C. CITY OR TOWN PERTH AMBOY D. STATE NJ E. ZIP CODE 08861 F. COUNTY CODE (if known)</p>					

II. SIC CODES (4-digit, in order of priority)

A. FIRST				B. SECOND			
3341 (specify) SECONDARY SMELTING & REFINING NON FERROUS				7 (specify)			
(specify)				(specify)			

III. FIRM IDENTIFICATION

A. NAME		B. IS THE NAME LISTED IN THE 1987-88 YEARBOOK?	
E L BETH LTD		<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	

C. STATE OF OPERATOR (Enter the appropriate letter into the answer box; if "Other", specify.)		D. COUNTY (Enter code if not "Other")	
P (specify) PUBLIC (other than federal or state)		A 2018260800	

E. STREET OR TOWN		F. STATE		G. ZIP CODE		H. INDIAN LAND	
500 HIGH STREET		NJ		08861		<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	

I. CITY OR TOWN		J. STATE		K. ZIP CODE		L. INDIAN LAND	
PERTH AMBOY		NJ		08861		<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	

X. EXISTING ENVIRONMENTAL PERMITS

1. PERMIT TYPE		2. PERMIT NUMBER		3. PERMIT DATE		4. OTHER (specify)	
9 U		46339		N.J. DEP.		(specify)	
5. RCRA (Hazardous Waste)		6. OTHER (specify)		7. OTHER (specify)		8. OTHER (specify)	
9 R		41194		N.J. DEP.		(specify)	

XI. MAP

Attach a map showing the location of the site, including the site boundaries, the location of the facility, the location of each of its existing and proposed intake and discharge structures, each of its hazardous waste treatment, storage, or disposal facilities, and each well where it injects fluids underground. Include all springs, rivers and other surface water bodies in the area, and show the location of the site relative to the nearest town or city.

XII. NATURE OF BUSINESS (Provide a brief description)

TIN & LEAD SCRAP ARE MELTED AND ALLOYED AND CAST INTO INGOTS.
ELECTRONIC SCRAP IS PROCESSED TO RECOVER GOLD CONTENT.

F9: A
SI

DEC 3 11 31 AM '80
NEW YORK, NY 10047

XIII. CERTIFICATION (See Instructions)

I, the undersigned, being a duly authorized officer or representative of the firm, hereby certify that the information furnished on this form is true and complete, and that I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

A. NAME & OFFICIAL TITLE (Type or print)	B. SIGNATURE	C. DATE SIGNED
RICHARD STEINBERG PRESIDENT	<i>[Signature]</i>	

COMMENTS FOR OFFICIAL USE ONLY

C. COMMENTS FOR OFFICIAL USE ONLY	

FORM 3 RCRA **EPA** **ENVIRONMENTAL PROTECTION AGENCY**
HAZARDOUS WASTE PERMIT APPLICATION
Consolidated Permit Program
(This information is required under Section 3005 of RCRA.)

EPA I.D. NUMBER
F N J 0 0 6 7 4 8 9 9 2 3 3

FOR OFFICIAL USE ONLY

APPLICATION APPROVED	DATE RECEIVED (yr., mo., & day)	COMMENTS

II. FIRST OR REVISED APPLICATION

Place an "X" in the appropriate box in A or B below (mark one box only) to indicate whether this is the first application you are submitting for your facility or a revised application. If this is your first application and you already know your facility's EPA I.D. Number, or if this is a revised application, enter your facility's EPA I.D. Number in Item I above.

A. FIRST APPLICATION (Place an "X" below and provide the appropriate date.)

1. EXISTING FACILITY (See instructions for definition of "existing" facility. Complete item below.)			2. NEW FACILITY (Complete item below.)						
<input checked="" type="checkbox"/>	VR.	MO.	DAY	FOR EXISTING FACILITIES, PROVIDE THE DATE (yr., mo., & day) OPERATION BEGAN OR THE DATE CONSTRUCTION COMMENCED (use the boxes to the left)	<input type="checkbox"/>	VR.	MO.	DAY	FOR NEW FACILITIES, PROVIDE THE DATE (yr., mo., & day) OPERATION BEGAN OR IS EXPECTED TO BEGIN
	75	10	30						

B. REVISED APPLICATION (Place an "X" below and complete item 1 above.)

1. FACILITY HAS BEEN RE-STATUTED	2. FACILITY HAS BEEN RE-DESIGNED
<input type="checkbox"/>	<input type="checkbox"/>

III. PROCESSES - CODES AND DESIGN CAPACITIES

A. PROCESS CODE - Enter the code from the list of process codes below that best describes the process occurring at the facility. If more lines are needed, enter the code(s) in the space provided. If a process will be performed that is not included in the list of codes below, then describe the process (including its design capacity) in the space provided on the form (Item III-C).

B. PROCESS DESIGN CAPACITY

1. AMOUNT - Enter the amount of material handled, stored, or treated at the facility.
2. UNIT OF MEASURE - For each amount entered in column B(1), enter the code from the list of unit measure codes below that describes the unit of measure used. Only the units of measure that are listed below should be used.

PROCESS CODE	APPROPRIATE UNITS OF MEASURE FOR PROCESS DESIGN CAPACITY	PROCESS CODE	APPROPRIATE UNITS OF MEASURE FOR PROCESS DESIGN CAPACITY
Storage:		Treatment:	
CONTAINER (barrel, drum, etc.)	S01 GALLONS OR LITERS	TANK	T01 GALLONS OR LITERS
TANK	S02 GALLONS OR LITERS	SURFACE IMPOUNDMENT	T02 GALLONS OR LITERS
WASTE PILE	S03 CUBIC YARDS OR CUBIC METERS	INCINERATOR	T03 GALLONS OR LITERS
SURFACE IMPOUNDMENT	S04 GALLONS OR LITERS		
Disposal:			
INJECTION WELL	D10 GALLONS OR LITERS		
LANDFILL	D00 ACRE-FOOT (the volume that would cover one acre to a depth of one foot) OR HECTARE-METER		
LAND APPLICATION	D01 ACRES OR HECTARES		
OCEAN DISPOSAL	D02 GALLONS PER DAY OR LITERS PER DAY		
SURFACE IMPOUNDMENT	D03 GALLONS OR LITERS		
UNIT OF MEASURE		UNIT OF MEASURE	
GALLONS OR LITERS	L	GALLONS OR LITERS	L
CUBIC YARDS	Y	TONS PER HOUR	T
CUBIC METERS	C	METRIC TONS PER HOUR	M
GALLONS PER DAY	U	GALLONS PER HOUR	H
		LITERS PER HOUR	LH

EXAMPLE FOR COMPLETING ITEM III (shown in line number X-1 and X-2 below). A facility has two storage tanks, one tank can hold 2000 gallons and the other can hold 400 gallons. The facility also has an incinerator that can burn 10 to 20 gallons per hour.

LINE NUMBER	A. PROCESS CODE (from list above)	B. PROCESS DESIGN CAPACITY	C. UNIT OF MEASURE
X-1	S02	600	G
X-2	T01	2500000	G
2	S01	400	G

III. PROCESSES (continued)

C. SPACE FOR ADDITIONAL PROCESS CODES OR FOR DESCRIBING OTHER PROCESSES (code "T04"). FOR EACH PROCESS ENTERED HERE INCLUDE DESIGN CAPACITY.

DEC 3 11 58 AM '80

ENVIRONMENTAL PROTECTION
AGENCY
NEW YORK, N.Y. 10007

IV. DESCRIPTION OF HAZARDOUS WASTES

A. EPA HAZARDOUS WASTE NUMBER - Enter the four-digit number from 40 CFR, Subpart D for each listed hazardous waste you will handle or store at the facility. For hazardous wastes which are not listed in 40 CFR, Subpart D, enter the four-digit number(s) from 40 CFR, Subpart C that describes the characteristics and/or the toxic contaminants of those hazardous wastes.

B. ESTIMATED ANNUAL QUANTITY - For each listed waste entered in column A estimate the quantity of that waste that will be handled on an annual basis. For each characteristic or toxic contaminant entered in column A estimate the total annual quantity of all the non-listed hazardous wastes handled which possess that characteristic or contaminant.

C. UNIT OF MEASURE - For each quantity entered in column B enter the unit of measure code. The units of measure which must be used are: pounds, kilograms, or metric tons.

ENGLISH UNIT OF MEASURE
POUNDS
TONS

CODE

METRIC UNIT OF MEASURE
KILOGRAMS
METRIC TONS

If facility records use any other unit of measure for quantity, the units of measure must be converted into one of the required units of measure taking into account the appropriate density or specific gravity of the waste.

D. PROCESSES**1. PROCESS CODES:**

For listed hazardous waste: For each listed hazardous waste entered in column A select the code(s) from the list of process codes contained in Item III to indicate how the waste will be managed, stored, or disposed of at the facility.

For non-listed hazardous waste: For each characteristic or toxic contaminant entered in column A, select the code(s) from the list of process codes contained in Item III to indicate all the processes that will be used to store, treat, or dispose of all the waste that possesses that characteristic or contaminant.

Note: Four spaces are provided for entering process codes. If more are needed: (1) Enter the first three in the first three boxes of the extreme right box of Item IV-D(1); and (3) Enter in the space provided on page 4, the line number and the additional code(s).

2. PROCESS DESCRIPTION: If a code is not listed for a process that will be used, describe the process in the space provided on the form.

NOTE: HAZARDOUS WASTES DESCRIBED BY MORE THAN ONE EPA HAZARDOUS WASTE NUMBER - Hazardous wastes that can be described by more than one EPA Hazardous Waste Number shall be described on the form as follows:

1. Select one of the EPA Hazardous Waste Numbers and enter it in column A. On the same line complete columns B, C, and D.
2. In column A of the next line enter the other EPA Hazardous Waste Number that can be used to describe the waste. Enter "included with above" and make no other entries on that line.
3. Repeat step 2 for each other EPA Hazardous Waste Number that can be used to describe the waste.

EXAMPLES FOR COMPLETING ITEM IV shown in line numbers

per year of chrome shavings from leather tanning and finishing operations. The facility will store and dispose of these wastes. The wastes are corrosive only and there will be an estimated 200 pounds per year of that waste. Treatment will be in an incinerator and the waste will be disposed of in a landfill.

LINE NO.	A. EPA HAZARDOUS WASTE NO. (enter code)	B. ESTIMATED ANNUAL QUANTITY OF WASTE	C. UNIT OF MEASURE (enter code)	D. PROCESS CODES
X-1	D 0 0 1	900	P	T 0 1 1 1
X-2	D 0 0 2	400	P	T 0 1 1 1
X-3	D 0 0 1	100	P	T 0 1 1 1
X-4	D 0 0 2			

Included with above

Continued from page 2.

NOTE: Photocopy this page before completing if you have more than 26 wastes to list.

Form Approved OMB No. 158-SB0004

EPA I.D. NUMBER (enter from page 1)										FOR OFFICIAL USE ONLY															
W	N	J	0	0	6	7	4	8	4	9	2	3	2	1	W	DUP				3	2	D	1	1	
IV. DESCRIPTION OF HAZARDOUS WASTES (continued)																									
NO.	HAZARD. WASTE NO. (enter code)				ESTIMATED ANNUAL QUANTITY OF WASTE				CODE (enter code)	1. PROCESS CODES (enter)								2. PROCESS DESCRIPTION (if a code is not entered in D(1))							
	K	O	6	9	20,000,000	P	S	0		1															
2	D	0	0	2	10,000,000	P	S	0	1																
3	D	0	0	0	20,000,000	P	S	0	1																
4																									
5																									
6																									
7																									
8																									
9																									
10																									
11																									
12																									
13																									
14																									
15																									
16																									
17																									
18																									
19																									
20																									
21																									
22																									
23																									
24																									
25																									
26																									

IV. DESCRIPTION OF HAZARDOUS WASTE

(continued)

E. USE THIS SPACE TO LIST ADDITIONAL PROCESS CODES FROM ITEM D(1) ON PAGE 3.

PA3
FACILITY
NEW YORK, NY 10007

F6: $\frac{A}{55}$ F6: $\frac{A}{56}$

EPA I.D. NO. (enter from page 1)

F	N	J	D	0	6	7	4	8	4	9	2	3	3	6
---	---	---	---	---	---	---	---	---	---	---	---	---	---	---

V. FACILITY DRAWING

All existing facilities must include in the space provided on page 5 a scale drawing of the facility (see instructions for more detail).

VI. PHOTOGRAPHS

All existing facilities must include photographs (aerial or ground-level) that clearly delineate all existing structures; existing storage, treatment and disposal areas; and sites of future storage, treatment or disposal areas (see instructions for more detail).

VII. FACILITY GEOGRAPHIC LOCATION

LATITUDE (degrees, minutes, & seconds)

LONGITUDE (degrees, minutes, & seconds)

4	0	3	0	4	6	0
---	---	---	---	---	---	---

0	7	4	1	5	3	4	0
---	---	---	---	---	---	---	---

VIII. FACILITY OWNER

☐ A. If the facility owner is also the facility operator as listed in Section VIII on Form 1, "Ownership Information", place an "X" in the box to the left and skip to Section IX below.

☐ B. If the facility owner is not the facility operator as listed in Section VIII on Form 1, "Ownership Information", place an "X" in the box to the right and skip to Section IX below.

1. NAME OF FACILITY'S LEGAL OWNER

2. PHONE NO. (area code & no.)

E	M	C	C	A	N	F	I	E	L	D	S	O	N	S
---	---	---	---	---	---	---	---	---	---	---	---	---	---	---

2	0	1	6	8	8	5	0	5	0
---	---	---	---	---	---	---	---	---	---

3. STREET OR P.O. BOX

4. CITY OR TOWN

5. ST.

6. ZIP CODE

F	1	0	0	0	B	R	I	G	H	T	O	N
---	---	---	---	---	---	---	---	---	---	---	---	---

G	U	N	I	O	N
---	---	---	---	---	---

N	J
---	---

--	--	--	--	--	--	--	--

IX. OWNER CERTIFICATION


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this report and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

A. NAME (print or type)

B. SIGNATURE

C. DATE SIGNED

ROBERT M. SILVERMAN



11/18/80

X. OPERATOR CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this report and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

A. NAME (print or type)


B. SIGNATURE

C. DATE SIGNED


RICHARD STEINBERG



11/18/80



V. FACILITY DRAWING (see page 4)



REFERENCE NO. 3

RECEIVED 1-11-85
From: A. Silverman

E. L. BETH LIMITED

P.O. Box 1769
Union, NJ 07083
201-688-9011

500 HIGH STREET
PERTH AMBOY, NJ 08861
(201) 688-9000

CABLE ADDRESS: BETHMETAL, PERTH AMBOY
TELEX No. 844535

March 14, 1983

Mr. Frank Coolick, Chief
Bureau of Hazardous Waste
Engineering
32 E. Hanover Street
Trenton, NJ 08625

SUBJECT: Annual Report

REF: NJD067484923
500 High Street, Perth Amboy, NJ 08861


Dear Mr. Coolick:

Please delist the above facility.

This plant has been closed since May 1981. There has been no activity since then and there is no storage of hazardous waste at this location.

Sincerely,

E. L. BETH LIMITED


Robert M. Silverman
Vice President

RMS/fh

REFERENCE NO. 4

NJDEP INSPECTION FORM

Report Prepared for:

Generator ☒ }
Transporter ☐ } see comments
HWM (TSD) facility ☒ }

Facility Information

Name: E.L. Beth Ltd

Address: 500 High Street
Perth Amboy, N.J. 08861

Lot: _____ Block: _____

County: Middlesex

Phone: 201-688-5050 (Silverman's Office)

EPA ID#: NJDD067484923

Date of Inspection: 1-16-85

Participating Personnel

State or EPA personnel: L. Zannelli - N.J. D.E.P.

Facility personnel: Robert Silverman - Vice President
Robert McIntyre - Plant Manager
of Edison site

Report Prepared by Name: L. Zannelli

Region: Central

Telephone #: 609-292-5560

Reviewed by: [Signature]

Date of Review: 1/17/85

FACILITY NAME: E.L. Beth Ltd.

ADDRESS: 500 High St.

Perth Amboy, N.J. - 08861

COUNTY: Middlesex

EPA ID #: NJDO67484923

DATE OF INSPECTION: 1-16-85

TIME IN: 0930hrs

TIME OUT: 0955hrs

PHOTOS TAKEN



YES



NO

If yes, how many? 5

SAMPLES TAKEN



YES



NO

NUMBER OF SAMPLES _____

NUDEP ID # _____

MANIFESTS REVIEWED



YES



NO

Number of manifests in compliance _____

Number of manifests not in compliance _____

List manifest document numbers of those manifests not in compliance.

Summary of Findings

Facility Description and Operations

E.L. Beth Ltd. has not been in operation since 5/81. According to Mr. Robert Silverman, Vice President, a fire occurred on 5/15/81 collapsing the building, and destroying the site. At that time, they were just starting up operations at another E.L. Beth Ltd. site located at 321 Meadow Road in Edison which is registered with the State as a generator and TSD with an EPA ID# NJD980594022. All salvagable items from the Perth Amboy site were taken to the Edison site.

The E.L. Beth site located in Perth Amboy was purchased by Mr. Silverman in 1978. According to same, the only waste generated was baghouse dust from processes, and TSD status pertained to 90 day drum storage. I questioned him as to any waste stored on-site at the time of the fire, and its disposition. He stated that he was unsure if any waste (baghouse dust) was on-site at

Summary of Findings

Facility Description and Operations

that two per se, but if there was, it would have been taken to the Edison site. I informed him ^{that} if any waste had been taken to the Edison site, he would be in violation of N.J.A.C. 7:26-7.5(c)1 - transporting waste without being permitted to do so. He also indicated that DEP-Dum representative, Edman View ^{of the} Hazardous Site Mitigation Administration, had been on-site on various occasions and site approval was given in regard to cleaning up the area after the fire. It must be noted that the site is located adjacent to the Dum Marine site, which is located due south of the EL Beth Ltd property. I questioned Mr. Silverman on any manifests generated by EL Beth, and he indicated that the trailer which housed all of this information was destroyed by the fire. I was also informed that the State was informed of closure and request to delist as a generator and TSD facility. (See attached letter sent to Dum Engineering

Summary of Findings

Facility Description and Operations

representative Frank Corlick dated 2/14/83).
A tour of the site was then conducted.
(see attached map).


The entire site is situated on concrete.
Located on the north side of the property
near the fence is what appears to be
some ^{remaining} process equipment (dust collector), and to
the south of the main entrance, the remains
of a shed (partial brick) and a sloping
concrete platform. Due East located by
the Arthur Kill River, is a smoke-stack,
and the remains of a process building
(structure) with some cardboard refuse (board) rubble
deposited. No apparent waste could be observed,
and the site basically looked barren.

While operating, E.L. Roth Ltd. conducted a
foundry operation ^{for secondary metals} consisting of the manufacturing
of solder and casting metals, as well as
tin-lead alloys. Metals are received in
various forms from brokers and companies.

Summary of Findings

Facility Description and Operations

Raw materials are then placed into Kettles. The Kettles are hooded and all particulates are accumulated and tied into a baghouse system (3) baghouses. The sootier and emission control dust are then stored in bags and put into drums. From the Kettles melted material is alloyed and assayed and cast into various ^{solid} forms as per customer specifications (bars, ingots, pigs, saws, and hogs). Product was then sold to various customers such as General Motors, V.S. Motors, and Delco.



Arthur K. H. River

stack

burned at site.
rubble

Concrete

concrete platform

EL Beth Ltd.

burned at
shed

Dune

Marine

oooo
oooo
oooo
oooo
oooo

drum

ooo
ooo

Fence

burned
out
trailer

Gregson
metal
Fabrication Inc.

zib Int'l Ltd.
Christian Custom

Joe K's Inc.
500

old Foundation
- Notarized Cable

rubble

N

High Street

REFERENCE NO. 5

TO: File thru Fred Sickels

FROM: Walter Zambelli

DATE: 1-17-85

SUBJECT: Phone Conversations -

1-11-85 - Contacted Dum-Hurst M section and spoke with Ferd Sczarcetti to see if any manifest records could be found on EL Beth. Nothing could be found after 11/9/80, and prior to that time, the manifest # is needed to get information from micro-film.

1-11-85 - Contacted Edwin Lieu - HSMA. He stated that he had been on the EL Beth site on several occasions due to his interest in the Duane Marine site. EL Beth site had been cleaned up satisfactorily after the fire (scrap metal, etc.) and he does not recall seeing any warren-site.

1-16-85 Contacted Bill Shaples - Dum-Engineering. He requested that my report be sent to him in order to delete the company.

REFERENCE NO. 6



State of New Jersey
DEPARTMENT OF ENVIRONMENTAL PROTECTION

DIVISION OF WASTE MANAGEMENT
32 E. Hanover St., CN 028, Trenton, N.J. 08625

DR. MARWAN M. SADAT, P.E.
DIRECTOR

LINO F. PEREIRA, P.E.
DEPUTY DIRECTOR

Mr. Robert Silverman
E.L. Beth Limited
P.O. Box 1769
Union, New Jersey 07083

14 FEB 1985

RE: E.L. Beth
500 High Street
Perth Amboy
NJD 067 484 923

Dear Mr. Silverman:

The Department has completed a file review of the above referenced facility. The Bureau has found adequate information to determine the facility's operating status under N.J.A.C. 7:26-1 et seq., The New Jersey Hazardous Waste Management Regulations.

The facility filed with the USEPA in August of 1980 for on-site generated hazardous waste storage in containers/drums (S01) at 2,500 gallons capacity. According to your March 14, 1983 letter, the facility closed in May of 1981. A facility site visit conducted by inspector L. Zaninelli, NJDEP, Central Field Office on January 16, 1985, revealed the site destroyed due to a fire.

Based upon the aforementioned events, the Department has reached the following conclusions regarding hazardous waste activity at the site:

- (1) Hazardous waste site operations terminated on 5/18/81 due to a fire which destroyed the facility.
- (2) No present or future hazardous waste activity occurs or will occur at this site.

Assuming the aforementioned conclusions are correct and complete, E.L. Beth's TSD facility as identified by the following USEPA identification number:

NJD 067 484 923

is excluded from applicable TSD facility regulations under N.J.A.C. 7:26-1 et seq.

FEB 14 1985

This written acknowledgement of the exclusion of E.L. Beth from the New Jersey Department of Environmental Protection's list of existing hazardous waste TSD facilities is based expressly on the review of the aforementioned correspondence. This letter makes no claim as to the extent and physical conditions of the actual hazardous waste activities occurring at the site mentioned above.

The issuance of this delisting letter by the Department does not indicate, or imply, and should not be construed as a waiver of any requirements pursuant to the New Jersey Water Pollution Control Act, N.J.S.A. 58:10A-1 et seq., and regulations promulgated thereunder concerning the New Jersey Pollutant Discharge Elimination System, N.J.A.C. 7:14-1 et seq. If your facility is in any of the regulated categories identified in the above cited regulations, you are hereby directed to apply for any and all permits necessary within ninety (90) days to the Bureau of Ground Water Discharge Permits, CN 029, Trenton, New Jersey 08625. Applications may be obtained by calling (609) 292-0424.

E.L. Beth's hazardous waste facility above is no longer included in DEP's list of "existing facilities" (see N.J.A.C. 7:26-1.4 and 12.3) and therefore does not need to conform with the interim operating requirements of N.J.A.C. 7:26-9 et seq., for "existing facilities". To operate a hazardous waste facility without prior approval from the DEP is a violation of the Solid Waste Management Act N.J.S.A. 13:1E-1 et seq.

If you have any questions on these matters, please contact Mr. William Sharples of my staff at (609) 984-4062.

Very truly yours,



Frank Coolick, Chief
Bureau of Hazardous Waste Engineering

EP6:lk

cc: A. Chang, USEPA, Region II
L. Zaninelli, CFO, Yardville

FEB 15 12 54 PM '85
RECEIVED

REFERENCE NO. 7

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF HAZARDOUS WASTE MANAGEMENT
HAZARDOUS WASTE INSPECTION REPORT

DWM-029

HAZARDOUS WASTE MANAGEMENT FACILITY INSPECTION REPORT

FACILITY INFORMATION

FACILITY NAME: E.L. BETH LTD.
FILE NUMBER: 12-16-28
VHT FACILITY FILE NUMBER: _____
PERMIT #: _____
REGION: C
INSPECTION DATE: 6/4/90
INCIDENT/CASE NUMBER: _____
INSPECTION TYPE: ISD / NCRA
RESPONSIBLE AGENCY CODE: _____
INSPECTOR'S NAME: Pete Taylor
INSPECTOR'S AGENCY: NJDEP
INSPECTOR'S BUREAU: DHWM / BCE
EPA ID NUMBER: (NJID 067484923)
ADDRESS: 500 High Street
Perth Amboy
LOT: _____ BLOCK: _____
COUNTY: Middlesex
FACILITY PERSONNEL: _____
TELEPHONE #: 201-688-5050
OTHER STATE/EPA PERSONNEL: 2
REPORT PREPARED BY: Pete Taylor
REVIEWED BY: Y
DATE OF REVIEW: 6/9/90

TIME IN: _____

TIME OUT: _____

PHOTOS TAKEN () YES (☒) NO

IF YES, HOW MANY? _____

SAMPLE TAKEN () YES (☒) NO

NO. OF SAMPLES _____

NJDEP SAMPLE ID#: _____

MANIFESTS REVIEWED () YES (☒) NO

Number of manifests in compliance _____

Number of manifests not in compliance _____

List manifest document numbers of those manifests not in compliance.

*This Facility has been
closed since 1985*

GENERAL

GENERAL CHECKLIST

YES NO N/A

7:26-7.4(a)1

Does the Generator have an EPA ID number?

☒ YES ☐ NO ☐ N/A

HAZARDOUS WASTE DETERMINATION

7:26-8.5(a)

Did the generator test its waste to determine whether it is hazardous?

☒ YES ☒ NO ☐ N/A

7:26-8.5(b)

Did the generator determine the hazardous characteristics based upon knowledge of process?

☒ YES ☐ NO ☐ N/A

Is the waste hazardous?

☒ YES ☐ NO ☐ N/A

7:26-8.5(d)

Were test results, waste analysis, or other determinations made in accordance with this section kept for three years from the date that the waste was last sent to an on-site or off-site TSF?

☒ YES ☐ NO ☐ N/A

MANIFESTS

7:26-7.4(a)4

Does each manifest have the following information? Please circle the elements missing and obtain a copy of the incomplete manifests. (List those manifests that are deficient on G-1).

7:26-7.4(a)4i

The generator's name, address and phone number.

7:26-7.4(a)4ii

The generator's EPA ID number.

7:26-7.4(a)4iii

The hauler(s) name, address phone number and NJ registration.

7:26-7.4(a)4iv

The hauler(s) EPA ID number.

7:26-7.4(a)4v

The name, address and phone number of the designated TSD facility.

7:26-7.4(a)4vi

The TSF's EPA ID number.

7:26-7.4(a)4v

The name, address and phone number of the designated TSD facility.

7:26-7.4(a)4vii

The name, type and quantity of hazardous waste being shipped, including such particulars as may be required regarding same?

7:26-7.4(a)4viii

Special handling instructions and any other information required on the form to be shipped by generator

		YES	NO	N/A
7:26-7.4(3)	Did the generator describe all N.O.S. wastes in Section J?	—	—	—
7:26-7.4(a)1x	When shipping hazardous waste to a waste reuse facility does the generator enter the waste reuse facility I.D. # in the section G of the Uniform Manifest?	—	—	—
7:26-7.4(a)5	Before allowing the manifested waste to leave the generator's property, did the generator:	—	—	—
7:26-7.4(a)5i	Sign the manifest certification by hand?	—	—	—
7:26-7.4(a)5ii	Obtain the handwritten signature of the initial transporter and date of acceptance on the manifest?	—	—	—
7:26-7.4(a)5iii	Retain one copy and forward one copy to the state of origin and one copy to the state of destination?	—	—	—
7:26-7.4(a)5iv	Provide the required numbers of copies for: generator, each hauler, owner/operator of the designated facility, as well as one copy returned to the generator by the facility owner/operator?	—	—	—
7:26-7.4(a)5v	Give the remaining copies of the manifest form to the hauler?	—	—	—
7.26-7.4(f)	Has the generator maintained facility records for three (3) years? (Manifest(s), exception report(s) and waste analysis)	—	—	—
7:26-7.4(h)1	Has the generator received signed copies of portion B (from the TSD facility) of all manifests for waste shipped off site more than 35 days ago?	—	—	—
7:26-7.4(h)1	If not: Did the generator contact the hauler and/or the owner or operator of the TSDF and the NJDEP at (609) 292-8341 to inform the NJDEP of the situation?	—	—	—
7:26-7.4(h)2	Have exception reports been submitted to the Department covering any of these shipments made more than 45 days ago?	—	—	—

7:26-9.3

Accumulation Time

How is waste accumulated on site?

- ☒ Containers
☐ Tanks (greater than 90 days)
 (complete HWMF (TSD) Facility Checklist)
☐ Tanks (less than 90 days)
☐ Above ground
☐ Below ground
☐ Surface impoundments
 (complete HWMF (TSD) Facility Checklist)
☐ Piles (complete HWMF checklist)

7:26-9.3(a)1

YES NO N/A

Is waste accumulated for more than 90 days?

when stored

STOP HERE IF THE HAZARDOUS WASTE MANAGEMENT FACILITY (TSF) CHECKLIST IS FILLED OUT.

*No waste on site**since 1980*

HAZARDOUS WASTE FACILITY STANDARDSYES NO N/A

MANIFESTS

7:26-7.4(a)4

Does each manifest have the following information? Please circle the elements missing and obtain a copy of the incomplete manifests. (List those manifests that are deficient on G-1).

7:26-7.4(a)4i

The generator's name, address and phone number.

7:26-7.4(a)4ii

The generator's EPA ID number.

7:26-7.4(a)4iii

The hauler(s) name, address phone number and NJ registration.

7:26-7.4(a)4iv

The hauler(s) EPA ID number.

7:26-7.4(a)4v

The name, address and phone number of the designated TSD facility.

7:26-7.4(a)4vi

The TSF's EPA ID number.

7:26-7.4(a)4vii

The name, address and phone number of the designated TSD facility.

7:26-7.4(a)4viii

The name, type and quantity of hazardous waste being shipped, including such particulars as may be required regarding same?

7:26-7.4(a)4viii

Special handling instructions and any other information required on the form to be shipped by generator?

YES NO N/A

7:26-7.4(3)	Did the generator describe all N.O.S. wastes in Section J?			
7:26-7.4(a)1x	When shipping hazardous waste to a waste reuse facility does the generator enter the waste reuse facility I.D. # in the section G of the Uniform Manifest?			
7:26-7.4(a)5	Before allowing the manifested waste to leave the generator's property, did the generator:			
7:26-7.4(a)5i	Sign the manifest certification by hand?			
7:26-7.4(a)5ii	Obtain the handwritten signature of the initial transporter and date of acceptance on the manifest?			
7:26-7.4(a)5iii	Retain one copy and forward one copy to the state of origin and one copy to the state of destination?			
7:26-7.4(a)5iv	Provide the required numbers of copies for: generator, each hauler, owner/operator of the designated facility, as well as one copy returned to the generator by the facility owner/operator?			
7:26-7.4(a)5v	Give the remaining copies of the manifest form to the hauler?			
7:26-7.4(f)	Has the generator maintained facility records for three (3) years? (Manifest(s), exception report(s) and waste analysis)			
7:26-7.4(h)1	Has the generator received signed copies of portion B (from the TSD facility) of all manifests for waste shipped off site more than 35 days ago?			
7:26-7.4(h)1	If not: Did the generator contact the hauler and/or the owner or operator of the TSDF and the NJDEP at (609) 292-8341 to inform the NJDEP of the situation?			
7:26-7.4(h)2	Have exception reports been submitted to the Department covering any of these shipments made more than 45 days ago?			

2/14/85

YES NO N/A

Records Booked

7:26-9.4(b)

Waste Analysis

7:26-9.4(b)11

Is there a detailed chemical and physical analysis of a representative sample of the waste(s) or each waste? (At a minimum, this analysis must contain all the information necessary for proper treatment storage or disposal of the waste).

7:26-9.4(b)1111

Does the character of the waste handled at the facility change from day to day, week to week, etc., thus requiring frequent testing? Check only one:

Waste characteristics vary: _____

All waste(s) are basically the same: _____

Company treats all waste(s) as hazardous: _____

7:26-9.4(b)2

Is there a written waste analysis plan at the facility?

Does it contain:

7:26-9.4(2)1

Parameters for which each hazardous waste stream will be analyzed including constituents listed in NJAC 7:26-8.16 and the rationale for the selection of these parameters?

7:26-9.4(b)211

The test methods which will be used to test for these parameters?

7:26-9.4(b)2111

The sampling method which will be used to obtain a representative sample of the waste to be analyzed?

7:26-9.4(b)21v

The frequency with which the initial analysis of the waste will be reviewed or repeated to ensure that the analysis is accurate and up-to-date?

7:26-9.4(b)2v

For off-site facilities, the waste analysis that hazardous waste generators have agreed to supply?

7:26-9.4(b)2v11

Procedures which will be used to identify changes in waste stream characteristics?

Does hazardous waste come to this facility from an outside source? (e.g., another generator).

If yes, list the name(s) of generators.

YES NO N/A

- 7:26-9.4(b)4 If waste comes from an outside source, are there procedures in the waste analysis plan to insure that waste received conforms to the accompanying manifest?
- Does the plan describe:
- 7:26-9.4(b)41 The procedures which will be used to determine the identity of each shipment of waste managed at the facility?
- 7:26-9.4(b)411 The sampling method which will be used to obtain a representative sample of the waste to be identified, if the identification method includes sampling?
- 7:26-9.4(c)1 Did the facility accept hazardous waste which it is not authorized to handle?
- 7:26-9.4(1) Are all records and results of waste analysis performed pursuant to NJAC 7:26-9.4(b) and 9.4(e) as applicable written in the operating log?
- 7:26-9.4(h) Security *Facility Closed*
- Does the facility have: *7:26-9.4(h)11*
- 7:26-9.4(h)11 A 24 hour surveillance system which continuously monitors and controls entry onto the active portion of the facility?
- 7:26-9.4(h)111 An artificial or natural barrier, which completely surrounds the active portion of the facility; and a means to control entry, at all times, through the gates or other entrances to the active portion of the facility?
- 7:26-9.4(h)3 Are there "Danger-Unauthorized Personnel Keep Out" signs posted at each entrance to the facility?
- If no, explain what measures are taken for security.

YES NO N/A

7:26-9.4(f)

General Inspection Requirements

7:26-9.4(f)1

Does the owner or operator inspect the facility for malfunctions and deterioration, operator errors and discharges which may be causing, or may lead to:

7:26-9.4(f)11

Discharge of hazardous waste constituents to the environment?

7:26-9.4(f)111

A threat to human health?

7:26-9.4(f)3

Has the owner or operator developed, and does the owner or operator follow a written schedule for inspecting monitoring equipment, safety and emergency equipment, security devices, and operating and structural equipment that are utilized for the prevention, detection or response to environmental or human health?

7:26-9.4(f)31

Did the owner or operator submit the written inspection schedule to the department?

If yes, when was it submitted?

7:26-9.4(f)3111

Is the written inspection schedule kept at the facility?

7:26-9.4(f)31v

Does the schedule identify the types of problems to be looked for during the inspection?

7:26-9.4(f)3v

Does the schedule include the frequency of inspection, based upon the rate of possible deterioration of the equipment and the probability of an environmental, or human health incident if the deterioration or malfunctions or any operator error goes undetected between inspections?

7:26-9.4(f)5

Is there evidence that problems reported in the inspection log have not been remedied?

7:26-9.4(f)6

Does the owner/operator record inspections in a log?

YES NO N/A

7:26-9.4(f)6

Are these records kept for at least three (3) years from the date of inspection?

7:26-9.4(f)6

Does the records include the date, and time of the inspection, the name of the inspector, a notation of the observations made, and the date and nature of any repairs or other remedial action?

7:26-9.4(g)

Personnel Training*Facility closed over*

Have facility personnel successfully ~~not~~ *3 yrs* completed a program of classroom instruction or on-the-job training *Records* within six months of having been *burned* employed?

7:26-9.4(g)2

Is the program directed by a person trained in hazardous waste management procedures and does it include instruction which teaches facility personnel hazardous waste management procedures (including contingency plan implementation) relevant to the positions in which they are employed?

7:26-9.4(g)5

If yes, have facility personnel taken part in an annual review of training?

Is there written documentation of the following:

7:26-9.4(g)61

Job title for each position at the facility related to hazardous waste management, and the name of the employee filling each job?

7:26-9.4(g)611

A written job description for each position related to hazardous waste management?

7:26-9.4(g)6111

A written description of the type and amount of both introductory and continuing training given to personnel in jobs related to hazardous waste management?

7:26-9.4(g)61v

Documentation of actual training or experience received by personnel?

YES NO N/A

7:26-9.8(e)11

A description of how and when the facility will be partially closed (if applicable) and ultimately closed?

7:26-9.8(e)111

The maximum extent of the operation which will be open during the life of the facility?

7:26-9.8(e)2

An estimate of the maximum inventory of wastes in storage or in treatment at any given time during the life of the facility?

7:26-9.8(e)3

A description of the steps needed to decontamination facility equipment during closure?

7:26-9.8(e)4

A schedule for final closure including the anticipated date when the wastes will no longer be received, the date when completion of final closure is anticipated, and intervening milestone dates which will allow tracking of the progress of closure?

Post Closure Plan

Not needed

7:26-9.9(g)

Does the facility have a written post-closure plan kept at the facility?

If yes, does the plan:

7:26-9.9(1)

Identify the activities which will be carried on after closure and the frequency of these activities?

7:26-9.9(1)1

Include a description of the planned ground water monitoring activities and frequencies at which they will be performed?

7:26-9.9(1)2

Include a description of the planned maintenance activities, and frequency at which they will be performed, to insure the following:

7:26-9.9(1)21

The integrity of the cap and final cover or other containment structures where applicable?

7:26-9.9(1)211

Describe the function of the facility monitoring equipment?

YES NO N/A

7:26-9.9(1)3

Include the name, address and phone number of a person or office to contact about the disposal facility during the post-closure period?

Does the owner/operator have a written estimate of the cost of post-closure for the facility?

If yes, what is it?

Please circle all appropriate activities and answer questions in appropriate sections all activities circled.

Storage	Treatment	Disposal
<u>Container</u>	Tank	Landfill
Tank, Above Ground	Surface Impoundments	
Tank, Below Ground	Incineration	Surface Impoundments
Surface Impoundments	Thermal Treatment	Other _____
Waste Piles		
Other _____	Chemical, Physical and Biological Treatment	
Other _____		

7:26-9.4(d)

Containers

What type of containers are used for storage? Describe the size, type, quantity and nature of wastes (e.g., 12 fifty-five gallon drums of waste acetone).

None on site since 1980

7:26-9.4(d)11

Do the containers appear to be of sturdy leakproof construction of adequate wall thickness, weld, hinge and seam strength, and of sufficient material strength to withstand side and bottom shock, while filled, without impairment of the container's ability to contain hazardous waste?

If no, explain.

Inspector: Taylor
Address: Two Rivers P.O. Bldg
East Windsor NJ
Telephone No: 609-426-0700

RCRA LAND DISPOSAL RESTRICTION
GENERATOR CHECKLIST

I. HANDLER IDENTIFICATION

A. Handler Name E.L. BETH LTD. B. Street (or other Identifier) 500 STATE ST
C. City Penthampton D. State N.J. E. Zip Code 08851 F. County Name Middlesex
G. Nature of Business; Identification of Operations: SIC Code(s) FOUNDRY
H. EPA ID # NJD 067484923
I. Handler Contact (Name and Phone Number) Robert Silverman 201-688-5050

II. GENERATOR COMPLIANCE

A. Waste Identification

1. F-Solvents

a. Does the handler generate the following wastes?

(1) P001, P002, P004, or P005 Yes No

(11) P003 Yes No

If an P003 wastestream (listed solely for ignitability) has been mixed with a non-restricted solid or hazardous waste, does the resultant mixture exhibit the ignitability characteristic? Yes No

b. Source of the above: Form 8700-12 Part A; Part B Biennial/Annual Reports other (specify)

Appendix A is intended to assist the inspector and enforcement official in determining whether the facility is generating F-solvent wastes, if such wastes were not identified by the facility previously. If you are concerned that F-solvent wastes may be misclassified or mislabeled, turn to Appendix A-1. To assist in identifying potentially

Comments

This Facility has been closed and delisted since 2/14/85.

Prior to 1980 they have not produced any wastes since 1980.

Prior to 1980 they produced a bag house waste which was classified as hazardous.

SUMMARY OF FINDINGS

FACILITY DESCRIPTION AND OPERATIONS

EL Beth was a foundry operation which manufactured solder, casting metals, and lead alloys.

This site is situated at 500 State Street, Perth Amboy. The site borders the Arthur Kill.

This facility has not been in operation since 1981, at which time it was completely destroyed by fire. This fire destroyed all hazardous waste manifests as well as other company records.

On 1/16/85 Linda Zaninelli, NJDEP-DHWM/BCE, conducted a RCRA inspection at this facility. At that time the company had applied for closure. This closure was granted, and the company was delisted by the NJDEP - DHWM, Bureau of Hazardous Waste Engineering on 2/14/85.

DESCRIBE THE ACTIVITIES THAT RESULT IN THE GENERATION OF HAZARDOUS WASTE.

No waste has been generated by this facility since 11/19/80. Prior to that time baghouse dust was the only waste generated at this site.

IDENTIFY THE HAZARDOUS WASTE LOCATED ON SITE, AND ESTIMATE THE APPROXIMATE QUANTITIES OF EACH (IDENTIFY WASTE CODES).

None.

CHEL FORM

COMPANY DATA

EPA ID NUMBER: NJ0067484923
 FACILITY NAME: EL BETH LTD
 FACILITY PHONE: (201) 688-5050 FACILITY STREET: 500 E STATE
 COUNTY/MUNIC. CODE: 12-16
 FACILITY CITY: PORT HARBOR FACILITY STATE: NJ FACILITY ZIP:
 CORPORATE NAME: CANT Field Metal group
 CORPORATE STREET: PO Box 3100 CORPORATE CITY: UNION
 CORPORATE STATE: NJ CORPORATE ZIP: 07083 CORPORATE PHONE: (201) 688-5050
 CORPORATE CONTACT: R SILVERMAN FILE NUMBER: 12-16-28 REGION CODE: C

INITIAL INSPECTION (4)

INITIAL INSPECTION DATE: 6/14/90 MANDATORY: (Y/N) DATE NOV ISSUED:
 DATE VIOLATIONS REFERRED: AGENCY REFERRED TO: LAND BAN (Y/N)
 INCIDENT CASE NUMBER: SCHEDULED COMPLIANCE DATE:
 SITE VISIT? (Y/N) (Y) FEE: (Y/N) (Y) DATE COMPLIANCE ATTAINED:
 INSPECTOR/REVIEWER: TAYLOR DATE ASSIGNED: 4/1/90 DATE REVIEWED: 6/12/90
 REGULATORY STATUS: 03
 EVALUATION TYPE CODE: 01
 GRANT CODE: 03

FOLLOWUP INSPECTION ()

FOLLOWUP INSPECTION DATE: SITE VISIT: (Y/N)
 INSPECTOR/REVIEWER: DATE REPORT REVIEWED:
 EVALUATION TYPE CODE:
 GRANT CODE:

CHEL GRID FOR
 (1) INITIAL () FOLLOWUP

		GW	CLO	\$\$\$	PTB	SCH	MNF	LDB	OTH	
CLASS OF VIOLATION	I*						<u>O</u>		<u>O</u>	Z=UNDETERMINED OR UNDER INVESTIGATION
	I						<u>O</u>		<u>O</u>	X=VIOLATION
	II						<u>O</u>		<u>O</u>	O=NO VIOLATION
										H=HIGH PRIORITY VIOLATOR

(ENTER Z, X, O, H OR C IN THE APPROPRIATE BOX.)

AREAS OF EVALUATION:

GW=GROUND WATER
 CLO=CLOSURE
 \$\$\$=FINANCIAL RESPONSIBILITY
 PTB=PART B

SCH=COMPLIANCE SCHEDULE
 MNF=MANIFEST
 LDB=LAND BAN
 OTH=OTHER

C=FACILITY NOT IN COMPLIANCE WITH CORRECTIVE ACTION COMPLIANCE SCHEDULE IN AN ORDER OR PERMIT

COMMENTS:

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION
CENTRAL BUREAU OF FIELD OPERATIONS
DAILY ACTIVITY/MILEAGE LOG

NAME: Taylor ID #: 2572

DATE: 6/4/90

DEPARTED: 7:20 ARRIVED: 8:30
ODOM. IN: 28857 ODOM. OUT: 28903
DEPARTED: 950

SITE NAME: Berlin Township
MUNICIPALITY: Berlin Township
COUNTY: Berlin
INCIDENT# / PAC #: 90-05-31-1022

HAZARDOUS WASTE INSPECTIONS

SPILL/HW INVESTIGATIONS

RCRA GRANT ACTIVITIES

- ☐ GENERATOR
- ☐ LDF-CEI
- ☐ TSF'S (TSD'S)
- ☐ PERMITTED FACILITY
- ☐ COMMERCIAL FACILITY
- ☐ SAMPLING
- ☐ COMPLIANCE INSPECTION
- ☐ TRANSPORTER AUDIT
- ☐ FIELD NOV ISSUED
- ☐ WITH LAND BAN

FEE BASED INSPECTIONS

- ☐ MAJOR FACILITY (WEEKLY)
- ☐ NON-MAJOR FACILITY
- ☐ GENERATOR
- ☐ TRANSPORTER
- ☐ TSD
- ☐ FIELD NOV ISSUED
- ☐ COMPLIANCE INSPECTION
- ☐ SAMPLING EPISODE

SUMMONS PROGRAM

- ☐ SUMMONS ISSUED
- ☐ COURT APPEARANCE

- ☒ INITIAL INVEST.
- ☐ FOLLOWUP INVEST.
- ☐ SAMPLING
- ☐ CLEANUP MONITORING
- ☐ CRIM. JUSTICE INV.
- ☐ ABANDONED DRUMS
- ☐ POTABLE WATER
- ☐ GROUND WATER
- ☐ SURFACE WATER
- ☐ RP KNOWN
- ☐ RP UNKNOWN
- ☐ LUST
- ☐ LAST
- CHECK APPLICABLE
- ☐ PETRO.PROD
- ☐ HOMEOWNER
- ☐ MEETING
- ☐ OTHER
- ☐ FIELD NOV ISSUED
- ☐ CLEANUP RP FUND
- ☐ SPILL FUND

RP COST \$ 12

FINDINGS:

No Further

Action

Required

REFERENCE NO. 8

MP



Field Book

748212

Projects (continued)

Ne

Ac

Pr

TI
SP
a

EL Beth Ltd

JO30

(1)

Table of Contents

Page No.	Contents
2-13	ON-Site Reconnaissance March 4, 1992
14, 15	OFF-Site Reconnaissance March 4, 1992
16, 17	Photo Log - On-Site Reconnaissance March 4, 1992
17	Photo Log - Off-Site Reconnaissance March 4, 1992

Clare Baruk March 4, 1992 ~~Full~~ 7/1/92

J030
(2) EL Beth Ltd March 4, 1992

OVA serial# (EPA #) 729633. Background reading: 60.2 ^{ppm}
HNU: EPA Serial # 729622. Background reading: 0 ppm
Monitor-4; EPA Serial # 734665. Background: <1 cph.

Camera for prints: EPA# 734745
Camera for slides: EPA# 734743

Clair/Banks March 4, 1992
K. Campbell 03/04/92

J030
EL Beth Ltd March 4, 1992 (3)
Perth Amboy, New Jersey
Wednesday, March 4, 1992
ON-Site Reconnaissance

HNUS Personnel:

Clair Banks - Site Manager
Nick Kides - Surveillance Support ^{3/4/92}
Barry Vroeginday - Site safety officer ^{3/4/92}
(The above personnel have read and understand the site work plan and safety plan). 08 3/4/92

Arrive at property at 0930. Met Mr. Jack Silbourn, Robert Silbourn and Carol Siggins. We looked over top map, clarifying where on block property lines. Now we're entering site.

Weather: Sunny, haze, cool, about 40°F, calm breeze from the east-northeast
0937 Holding tailgate meeting.

Barry's reviewing site legends, potential contaminants and ppe.


1000 Instrument setup, background readings, sorting up completed. I'm briefly going over recon with Barry, Nick.

Clair/Banks March 4, 1992
K. Campbell 03/04/92

K. Company

0 (base sketches from application for Hazardous Waste Permit)

EL BETH



ARTHUR KILL

 $\frac{1}{8}'' - 4'-0''$

Chas. P.

EL Beth Ltd

J030
March 4, 1992 (5)

1014 hrs Mr. Bob & Jack S. (their company
purchased existing facility late 1977/6 at
about late 1977). (They are relating site history
to me). In operation 1978-1981 as subsidiary
of parent company M.C. Garfield.

Property is in the names of individuals
now.

Company ^{then} owned by M.C. Garfield & Mr. Silverman
(Dick & Bob Silverman) remains as property owners.

Co. made solder, casting metals.
Used Virgin metals, repair & factory secondary
metals.

Some of their raw material was
by-product from their material suppliers.
They recycled, reused here.

This reused material was ammon-
ium chloride, that came with scrap
solder, he said.

Mr. Silverman said:

Property has been paved as long as
they've been owners. ^{ie - he hasn't paved before he bought it.} Open storage ~~area~~
at W edge of property next to garage
for raw materials.

Mr. Bob Silverman paid the
wayhouse dirt was recycled.
Claim Brought March 4, 1992 ^{03/04/92}

JO30

(6)

EL Beth Ltd March 4, 1992

owner said that drums of
waste were very heavy - could
be about 2000 lb each.

Clair Bump March 4, 1992
H. Campbell 03/09/92

JO30

March 4, 1992 (7)

EL Beth Ltd

posts of the drum storage area by the
former garage can be seen (do not see all four)
Much waste volume - "there may not be
removal documentation because ~~waste~~ ^{was} ~~planned~~ ^{used}"
Ms. Sargens said there was no O&P
cleaning requirement after the fire -
"back then less requirements," she said.

(according to on-site talk with owner's attorney)

SE part of site, storm sewer grating;
small (6' x 12') asphalt area
with ten drum marks. (blacktop)
fence in this area is broken, open, by pier.
1038 ft
Barry & Nick are checking storm
sewer, with iron grating
Barry detected 0.6 ppm with OVA,
after stone dropped into storm sewer.

Graffiti present on burned building,
Mr. Jack Silberman noted kids
did the graffiti.

1043 we're at edge of concrete
looking at burned remains of
building - an above-ground tank had
heating oil, Ms. Sargens said.
Clair Bump March 4, 1992
H. Campbell 03/09/92

JO30
(8) EL Beth Ltd

JO30
EL Beth Ltd March 4, 1992 (9)
1045 Photos P1 through P5, and
S1 through S5 - panoramic view
of property taken from SE corner of
paved end of property (land portion of site)

Barry has OVA reading of 0.6 ppm
at edge of concrete (next soil there)
by ~~digging~~ glow of cast iron conduits (perhaps
sewer) (possibly storm sewer line)
There is no response on HNV

1048 Photos P6 through P8 - Panoramic
view facing pier
of burned building at pier.

1050 Closer view South edge of
burned pier (Photos P9, S9)

1051 Photo P10, S10, of burned plant
at pier facing S-SE.

Barry has spike reading on OVA
up to 0.8 ppm at hole at
concrete - soil (pier) interface
Camp March 4, 1992

El Beth 03/04/92

El Beth 03/04/92

(10) J030

EL Beth Ltd

March 4, 1992

0.8 to 1 ppm on OVA at 1100 hrs
at NE corner of land area of site.
(wind from NE also) by
crescent logs.

Claire Bump March 4, 1992 K. G. Bell 03/04/92

J030

March 4, 1992 (11)

EL Beth Ltd

1055 photo P11-S11 of location where
Bing had 0.8 ppm OVA reading.
Photo facing E-SE 3/27/92

1058 photo P12, S12 photograph
of location of stormsewer asphalt
where drum marks noted, facing SE.

1100 walking along N^W site border
at NE corner of land area, storm sewer
(crescent); there are crescents covered
large logs right at adjacent property,
about 20 feet away.

1105 photo of condiment & adjacent
lot, facing NE-SE. P13, S13
3/27/92

1110 Photo # - P14, S14,
remains baghouse equipment.

1112 Photo # - P15, S15
facing West, debris (tree) and,
site border, ramp & garage.

1115 Photo # P16, S16 facing S-SE

Claire Bump March 4, 1992

K. G. Bell 03/04/92

(12) J030

EL Beth Ltd March 4, 1992

1120 hrs - by debris at ramp (former drum shipping area) is an overturned bucket; nickel label - roopy, tar with asbestos. Also, is can, about 1 gallon size - label reads (partly) "another penton one product". I'm not approaching it to read further, as it seems uncapped. Owner is holding the can now. (Indicated should have a glove on).

Big big house area (its a large metal structure) seems compass isn't working properly. Not to check compass readings against map.

Clair Bump March 4, 1992

K. G. Hall 03/04/92

J030

EL Beth Ltd March 4, 1992 (13)
 old border, 1 blacktop area (120' in from fence)

1117 hrs.

P17, S17 ramp formerly for drum storage.

1119 P18, S18 former drum storage area, and, garage, pump W.

small bucket, tar and asbestos = roopy tar with asbestos (Nick read & related to me).
 photo of bucket 1120 hrs P19, S19.

They believe there were no trans wires. Electricity came from street, they said.

1125 Photo P20, S20 ^{is 4/19/92}
 photo of bag house & some electrical equipment ^{is 3/11/92}


note: brick shed ("garage") by entrance seems to have debris. I did not inquire if anything is now stored in it. No readings were taken at shed.

1135 Leaving site.

Clair Bump March 4, 1992

K. G. Hall 03/04/92

(14) JO30
EL Beth Ltd
offset recon. March 4, 1992



Claire Bampf March 4, 1992
K. Copbell 03/04/92

JO30
EL Beth Ltd
offset recon. March 4, 1992 (15)

Drive along area near site, ^{if there are} note houses, and if schools, etc present.

1149: Photo of ^{Block 44/2} Lot 238, lots (industrial) adjacent to site. Taken from High Street.

1150: Photo of property entrance, 500 High Street

1151 Photo at property entrance with sign, "500 High Street"

Claire Bampf March 4, 1992
K. Copbell 03/04/92

J030
(16) ELBeth Ltd March 4, 1992

Photograph Log - ON-SITE Reconnaissance

Time	Description	Photo#
1045	Panoramic view of site taken from SE corner of land portion of property; facing W to NE.	P1-P5 S1-S5
1048	Panoramic view of burned building, pier.	P6-P8 S6-S8
1050	Closer view, south edge of burned pier	P9, S9
1051	Burned manufacturing plant, facing S-SE.	P10, S10
1055	Location of 10.8 ppm OVA reading, facing E-SE	P11, S11
1058	Location of storm sewer and, blacktop with drum marks, facing SE	P12, S12
1105	Conduit and adjacent lot	P13, S13
1110	Remaining baghouse equipment	P14, S14
1112	facing west; pile of tree debris; former drum ramp; "garage"	P15, S15
1115	facing S-SE	P16, S16

Claire Bampf March 5, 1992
K. Campbell 04/01/92

J030
ELBeth Ltd entered March 5, 1992 (17)
Photograph Log - ON-SITE Reconnaissance, continued:

Time	Description	Photo#
1117	former ramp for drum handling	P17, S17
1119	facing west, former drum storage area, and, -garage.	P18, S18
1120	Photo of overturned bucket of roofing tar with asbestos	P19, S19
1125	Photo of part of baghouse, and, some electrical equipment	P20, S20

Photos taken off-site 3/4/92

Time	Description	Photo#
1149	Photo of Block 238, with lots adjacent to site; taken from High Street.	P21, S21
1150	Property entrance	P22, S22
1151	Property entrance, showing sign.	P23, S23

Claire Bampf March 5, 1992
K. Campbell 04/01/92

REFERENCE NO. 9

TO: EL Beth Ltd file
 FROM: Claire Barajas
 SUBJECT: Waste Quantity Reported for the EL Beth site.
 REFERENCE: noted below

Through discussion with Hanna Majczyk of U.S. EPA, Permits Administration Branch, the correct waste quantity figures for the EL Beth Ltd. Hazardous Waste Permit Application dated November 18, 1980 have been determined. The figures that appear in the file copy are 1000 times greater than the values entered by the applicant; this is because in the past, EPA added the additional zeros to the form for the purpose of filling in a field, in data entry. The correct values are:

Part III, process design capacity, SOI = 2500 G

Part IV, estimated annual quantity of waste:

K069, 20,000 P

D002, 10,000 P

"D000", 20,000 P

REFERENCE NO. 10

GEOHYDROLOGY AND DIGITAL-SIMULATION MODEL OF THE FARRINGTON AQUIFER IN THE NORTHERN COASTAL PLAIN OF NEW JERSEY

By George M. Farlekas

U.S. GEOLOGICAL SURVEY

Water-Resources Investigations 79-106

**Prepared in cooperation with
New Jersey Department of Environmental
Protection, Division of Water Resources**

August 1979



CONTENTS

	Page
Abstract.....	1
Introduction.....	3
Purpose and scope.....	3
Location and extent.....	3
Previous investigations.....	3
Acknowledgments.....	5
Geohydrology.....	5
Potomac-Raritan-Magothy aquifer system.....	5
Lower confining unit.....	7
Farrington aquifer.....	8
Geohydrology.....	8
Hydrology.....	12
Hydraulic characteristics.....	12
Flow before development.....	13
Potentiometric surfaces for 1959 and 1973.....	13
Withdrawals.....	16
Upper confining unit.....	16
Old Bridge aquifer.....	22
Simulation of the Farrington aquifer.....	25
Simulation theory.....	25
Model application.....	26
Boundary conditions.....	27
Initial conditions.....	29
Aquifer characteristics.....	29
Recharge and withdrawal.....	32
Confining unit characteristics.....	33
Vertical leakage.....	33
Model calibration.....	35
Transient simulation.....	35
Steady-state simulation.....	36
Accuracy of data.....	40
Potentiometric surfaces simulated due to future stresses.....	40
Water budget.....	48
Summary and conclusions.....	50
Selected references.....	53

ABSTRACT

A two-dimensional digital-computer flow model was developed to simulate the Farrington aquifer in the northern part of the Coastal Plain of New Jersey. The area of detailed study includes approximately 500 square miles in Middlesex and Monmouth Counties where the aquifer provides a large part of the municipal and industrial water supply. The area modeled is much larger, extending seaward as well as northeastward into Long Island.

The aquifer consists chiefly of the Farrington Sand Member of the Raritan Formation and is composed of sand and some gravel. It thickens from a featheredge in outcrop to more than 170 feet, 11 miles to the southeast. The confining unit between the Farrington and the overlying Old Bridge Sand Member of the Magothy Formation consists primarily of the Woodbridge Clay Member of the Raritan Formation and has a maximum thickness of 244 feet.

The model simulates both water-table and artesian conditions. The confining unit overlying the Farrington aquifer is simulated as having a variable thickness and vertical hydraulic conductivity. The effect of a declining water level in the overlying Old Bridge aquifer on the Farrington aquifer is also simulated by the model.

Values used to describe the hydraulic properties of the Farrington aquifer are: a hydraulic conductivity of 105 feet per day, a storage coefficient of 1.6×10^{-4} for artesian conditions, and a specific yield of 0.25 for water-table conditions. Values for the overlying confining unit are: a vertical hydraulic conductivity ranging from 4.2×10^{-7} to 1.0×10^{-10} feet per second and a specific storage of 4×10^{-5} feet⁻¹.

Aquifer simulation for the 15-year period, 1959-73, was used to calibrate the model. The model was calibrated by comparing the observed potentiometric surface of November 1973 with the simulated potentiometric surface. In addition, hydrographs for selected wells were compared with model results. Ground-water withdrawals for 1959 and 1973 were 12.1 and 28.5 million gallons per day, respectively.

Potentiometric surfaces for 1985 and 2000 were computed based on a linear projection of ground-water withdrawals (39.5 and 56.9 million gallons per day in 1985 and 2000, respectively) of the period 1959 through 1973. These surfaces are deeper than that of November, 1973, and the cone of depression is wider. The potentiometric head projected by the model in the vicinity of Sayreville will be more than 150 feet below mean sea level by 2000; the head in this area was 70 feet below sea level in 1973.

The model calculated ground-water budgets for steady-state and transient conditions for the entire modeled area and for several rectangular subareas. Ground-water flow into the modeled Farrington aquifer under steady-state conditions before

ground-water development was 16 cubic feet per second for the entire area. Recharge in the outcrop area and vertical leakage from the Old Bridge was 8 cubic feet per second each. Approximately 75 percent of the discharge occurred as seepage into surface-water bodies in and near the outcrop and as lateral flow southwestward into Burlington County near the outcrop area. The remaining 25 percent occurred southeast of the outcrop as vertical leakage into the overlying Old Bridge aquifer and as lateral flow to the south into Ocean and Burlington Counties.

A transient water budget for 1973 was calculated for a subarea consisting mainly of Middlesex County. The model indicates that 48 percent (14.3 cubic feet per second) of the total inflow to the subarea was through its boundaries. Other sources of water include direct recharge within the subarea (5.4 cubic feet per second), vertical leakage (mainly from the Old Bridge) within the subarea (2.6 cubic feet per second), and water released from storage (3.4 cubic feet per second). Discharge from the subarea consisted mainly of withdrawals (26.5 cubic feet per second). It also included vertical leakage to the Old Bridge and discharge to surface-water bodies simulated by constant-head nodes (3.2 cubic feet per second).

INTRODUCTION

Purpose and Scope

The purpose of this study is to simulate the hydrology of the Farrington aquifer using a computer-simulation model so that the effects of alternative withdrawal schemes can be evaluated quantitatively. The primary study area consists of the northern part of the New Jersey Coastal Plain. The area modeled is much larger, extending seaward and also to the northeast into Long Island. This report discusses the geohydrology of the Farrington aquifer, the simulation model, and the effects of projected withdrawals from the Farrington aquifer. Saltwater intrusion, one of the limiting factors of future development of the aquifer, had not been investigated during this study. This study by the U.S. Geological Survey was done in cooperation with the Division of Water Resources of the New Jersey Department of Environmental Protection.

Location and Extent

The primary area of study consists of approximately 500 mi², including parts of Middlesex, Monmouth, and Mercer Counties (fig. 1). The modeled area is much larger, incorporating additional areas of New York and New Jersey. To the northeast, the model extends into Long Island. The southeastern boundary of the model is approximately 60 mi offshore. The southwestern boundary extends to the southwestern limit of Monmouth County. The total area simulated by the model is approximately 7,500 mi².

Previous Investigations

The geology and ground-water resources of the Farrington aquifer in the northern part of the Coastal Plain of New Jersey have been studied for many years. Barksdale (1937) discussed the geology and hydrology of the Farrington Sand in Middlesex County. Barksdale and others (1943) completed an investigation of the ground-water resources of Middlesex County, with special emphasis on the coastal plain. Appel (1962) reported on saltwater encroachment into the Farrington and Old Bridge aquifers in the Sayreville area, Middlesex County. Hasan, Kasabach, and Malone (1969) discussed the Old Bridge aquifer in the Sayreville area of Middlesex County. Reports on the ground-water resources of several counties in the northern part of the New Jersey Coastal Plain include: Jablonski (1968) on Monmouth County, Anderson and Appel (1969) on Ocean County, and Vecchioli and Palmer (1962) and Widmer (1965) on Mercer County. Wilson and others (1972) reported on the water resources of the Upper Millstone River basin, with emphasis on the water-table aquifer. The Potomac-Raritan-Magothy aquifer system in the New Jersey Coastal Plain was described by Gill and Farlekas (1976).




Figure 1.--Map showing area of investigation.

Recent investigations of the geology of the northern part of the Coastal Plain of New Jersey include a report by Owens, Minard, and Sohl (1968) on the Cretaceous deltas and a report by Owens and Sohl (1969) on the Cretaceous-Tertiary shelf and deltaic paleoenvironments. A recent paper by Perry and others (1975) presents a survey of the stratigraphy of the Atlantic Coastal Margin and includes detailed stratigraphic sections of the northern part of the New Jersey Coastal Plain.

Acknowledgments

The assistance of state government officials and private individuals is gratefully acknowledged for furnishing well information and permitting access to wells. Special thanks are extended to the Duhernal Water System officials for providing hydrologic data from their files. Gerard P. Lennon and Flavian Stellerine, both formerly of the U.S. Geological Survey, provided valuable assistance with computer programming.

GEOHYDROLOGY

Potomac-Raritan-Magothy Aquifer System

The northern part of the Atlantic Coastal Plain of New Jersey is underlain by unconsolidated silt, clay, sand, and gravel deposited under fluvial, fluvial-deltaic, and marine conditions. The sediments range in age from Early Cretaceous to Holocene and lie unconformably on a pre-Cretaceous bedrock consisting mainly of sedimentary and igneous rocks of Triassic age and older crystalline rocks. The unconsolidated sediments crop out in northeast-southwest directions and thicken downdip to the southeast. Their thickness ranges from a featheredge in Middlesex County to about 1,700 ft in Monmouth County (Gill and Farlekas, 1976). The present study is concerned with the lower part of this sedimentary sequence.

The most productive source of ground water in the northern part of the New Jersey Coastal Plain is the Potomac-Raritan-Magothy aquifer system, which is made up of the Potomac Group and the Raritan and Magothy Formations of Cretaceous age. This wedge-shaped aquifer system, consisting of quartz sand with some gravel, silt, and clay, thickens from a featheredge at its outcrop in Middlesex County to a maximum of about 600 ft in Monmouth County (Gill and Farlekas, 1976). Overlying the Potomac-Raritan-Magothy aquifer system is a confining unit consisting of the Cretaceous Merchantville Formation and the Woodbury Clay. It is the most extensive confining unit in the New Jersey Coastal Plain and ranges in thickness from a featheredge in Middlesex County to a maximum of approximately 300 ft in Monmouth County. Structure contour maps of the top of the Merchantville Formation, the Magothy Formation, and the pre-Cretaceous bedrock in New Jersey appear in Gill and Farlekas (1976).

The Potomac-Raritan-Magothy aquifer system in the northern part of the New Jersey Coastal Plain contains two major aquifers; the Farrington aquifer, consisting mainly of the Farrington Sand Member of the Raritan Formation, and the Old Bridge aquifer, consisting mainly of the Old Bridge Sand Member of the Magothy Formation. The Old Bridge Sand Member was originally placed in the upper part of the Raritan Formation. However, Wolfe and Pakiser (1971, p. 41) designated the unit as the basal member of the younger Magothy Formation. An analysis of geophysical and water-level data indicate that the Farrington and the Old Bridge function as separate aquifers in Middlesex County, and each can be traced downdip into Monmouth County.

The Woodbridge Clay Member of the Raritan Formation, an extensive confining unit that separates the Farrington Sand Member from the overlying Old Bridge Sand Member, can also be traced downdip from the outcrop area in Raritan Bay to the shore area in Monmouth County. This interpretation is supported by a recently published cross section along the Atlantic Coast (Perry and others, 1975, p. 1542). The stratigraphic section shown in Table 1 is modified from Perry and others (1975, p. 1539) and shows the correlation of part of the Cretaceous section in the northern part of the Coastal Plain of New Jersey (Middlesex and Monmouth Counties) with sediments on Long Island.

SERIES	STAGE	MIDDLESEX COUNTY NEW JERSEY	MONMOUTH COUNTY NEW JERSEY	LONG ISLAND NEW YORK
UPPER CRETACEOUS	LOWER CAMPANIAN	WOODBURY CLAY	WOODBURY CLAY	MATAWAN GROUP (UNDIVIDED)
		MERCHANTVILLE FORMATION	MERCHANTVILLE FORMATION	
		CLIFFWOOD BEDS	CLIFFWOOD BEDS	MAGOTHY FORMATION
	SANTONIAN	MORGAN BEDS	MORGAN BEDS	
		AMBOY STONEWARE CLAY MEMBER	AMBOY STONEWARE CLAY MEMBER	
		OLD BRIDGE SAND MEMBER	OLD BRIDGE SAND MEMBER	
	CONIACIAN	?	?	
	TURONIAN	?	?	
	CENOMANIAN	SOUTH AMBOY FIRE CLAY	SOUTH AMBOY FIRE CLAY	RARITAN FORMATION
		SAYREVILLE SAND MBR.	SAYREVILLE SAND MEMBER	
		WOODBIDGE CLAY MBR.	WOODBIDGE CLAY MEMBER	
		FARRINGTON SAND MBR.	FARRINGTON SAND MBR.	
		RARITAN FIRE CLAY	RARITAN FIRE CLAY	
		POTOMAC GROUP	POTOMAC GROUP	

Table 1.--Correlation of stratigraphic units in Middlesex and Monmouth Counties, New Jersey and Long Island, New York (Modified from Perry and others, 1975).

Lower Confining Unit

The lower confining unit in Middlesex County, as defined in this report, consists mainly of a layer of clay and the underlying consolidated rocks. Southeast of the Monmouth-Middlesex County line, the lower confining unit is defined as the first layer of clay thicker than 20 ft beneath the Farrington aquifer.

In Middlesex County, the upper part of the lower confining unit is the Raritan fire clay (Barksdale and others, 1943). This clay lies between the Farrington Sand Member and bedrock in much of Middlesex County. Near the Farrington outcrop, the Raritan fire clay ranges in thickness from 0 to 35 ft, and the thickness increases downdip (Barksdale and others, 1943, p. 140). Well data near Spotswood, Old Bridge, Runyon, Parlin, and South Amboy indicate a thickness of up to 86 ft for the Raritan fire clay.

The lower part of the confining unit in Middlesex County consists of rocks of Triassic age and pre-Triassic crystalline rocks. An analysis of drillers' logs indicates that Triassic rocks extend beneath the northwestern edge of the coastal plain southward for approximately 5 mi. Farther southeast, the bedrock is composed of pre-Triassic crystalline rocks. The thickness of the Triassic and crystalline rocks is not known.

Within the Triassic sequence is a thick diabase sill, which is exposed north of the study area along the Hudson River, where it forms the Palisades. The same diabase sill occurs on Staten Island, N.Y., in Middlesex County, N.J., and farther west. The sill is a continuous unit within the study area and is overlain by post-Triassic sediments (Barksdale and others, 1943, p. 15). The hydrologic significance of this sill will be discussed in the section on aquifer characteristics.

The lower confining unit southeast of the Middlesex-Monmouth County line is defined as the first confining layer of clay below the Farrington aquifer thicker than 20 ft. Only a few wells or test holes completely penetrate the Farrington in this area. Consequently, data on the sediments between the Farrington and bedrock are scant. Geophysical logs of a test hole just north of Freehold Borough suggest the presence of at least 60 ft of silt and clay below the principal aquifer. Southeast of the Middlesex-Monmouth County line, geophysical logs indicate a thickness of up to 200 ft for the lower confining unit.

Farrington Aquifer

Geohydrology

The Farrington aquifer in the northern Coastal Plain of New Jersey consists primarily of the Farrington Sand Member of the Raritan Formation. At or near its outcrop, the aquifer includes the Farrington Sand Member and overlying sand and gravel beds. In Middlesex County southeast of the outcrop, the aquifer consists solely of the Farrington Sand Member. Southeast of the Middlesex-Monmouth County line, the aquifer, as defined in this report, consists of the Farrington Sand and the underlying uppermost sand layers of the Potomac Group, which are hydraulically connected to the Farrington.

In Middlesex County, the Farrington Sand Member has been described as coarse to fine sand with lignite and pyrite. Locally, it contains clay beds (Barksdale and others, 1943, p. 104-105). In Middlesex County, its thickness ranges from 0 to 129 ft. Near South River, Sayreville, and Old Bridge the thickness of the Farrington ranges from 44 to 104 ft. It is either thin or missing above the Triassic diabase sill between the Borough of South River and Perth Amboy City due to erosion or a lack of deposition during Cretaceous time (Barksdale and others, 1943, p. 106). The sand was deposited in a subaerial deltaic environment near the outcrop area and in a marine environment downdip along the coast (Perry and others, 1975, p. 1543). North of the Raritan River, the northwesterly part of the Farrington Sand Member in Middlesex County is overlain by a unit consisting of sand and, in places, clayey sediments (Barksdale and others, 1943, p. 19 and p. 58). Farther north in Middlesex County, the northwesterly part of the Farrington is overlain by glacial deposits of considerable thickness (Barksdale, 1937, p. 6). Information on the Farrington at the New Jersey-New York State line beneath Arthur Kill is not available. On Staten Island, the northwesterly part of the Farrington is overlain by glacial deposits consisting of ground moraine and terminal moraine and some glacial outwash (Perlmutter and Arrow, 1953, plate 2).

Near the Raritan River, the Farrington Sand Member is overlain by Pleistocene or Holocene deposits consisting of highly permeable sand and gravel. In some places, the overlying deposits are dense and nearly impermeable. In places, the ancestral Raritan River eroded through the Farrington, disrupting its continuity. The Farrington has been replaced with relatively impermeable river mud. This mud, where present, restricts the hydraulic connection between the part of the Farrington north of the Raritan River with the part south of the river (Barksdale, 1937, p. 3-6).

Along the Washington Canal, the overlying confining unit (Woodbridge Clay Member), together with all or part of the Farrington Sand Member, has been eroded. Here, Holocene sand and

gravel were deposited directly on the Farrington and the Triassic bedrock, thus increasing the thickness of the aquifer (Barksdale, 1937, p. 6-9).

South of the Raritan River, the northwesterly part of the Raritan and Magothy Formations are covered by surficial deposits of fine to very coarse sand and local basal beds of gravel (Owens and Minard, 1975). Near Hightstown, the surficial deposits reach a thickness of 94 ft. Where the surficial deposits are in direct contact with the underlying Farrington Sand Member, the thickness and effective recharge area of the Farrington is increased. Wilson and others (1972, p. 27) state that west of the New Jersey Turnpike in the Upper Millstone River basin, where the surficial deposits overlie Cretaceous sediments, the entire section acts essentially as a single water-table aquifer.

Southeast of the Middlesex-Monmouth County line, few wells penetrate the Farrington Sand Member and, consequently, data are sparse. However, geophysical data at Lakewood, Freehold, Toms River, and Sandy Hook, and palynological analyses of cores from wells at Fort Dix, Matawan, Sandy Hook, and Toms River (Perry and others, 1975, p. 1542; Sirkin, written commun., 1971) indicate that the Farrington is separated from the underlying sands of the Potomac Group by a relatively thin confining unit. The unit may be equivalent to the Raritan fire clay. At Sandy Hook and Toms River, this confining unit is only 10 to 20 ft thick (Perry and others, 1975, p. 1542). The thinness of this confining unit strongly suggests that the Farrington and some Potomac sands act as a single aquifer in Monmouth and Ocean Counties in the study area. For this reason, in the area southeast of the Middlesex-Monmouth County line, the Farrington aquifer, as defined in this report, includes the uppermost Potomac sand unit.

The top of the Farrington aquifer strikes in a northeast-southwest direction and dips to the southeast 45 to 60 ft/mi. A structure contour map of the top of the aquifer constructed primarily from geophysical logs is shown in figure 2. The altitude of the top of the aquifer near the Middlesex-Monmouth County line is approximately 400 ft below mean sea level. Near Freehold, the top is approximately 700 ft below mean sea level.

A thickness map of the Farrington aquifer, constructed from geophysical logs and geologists' and drillers' logs, is shown in figure 3. More than 50 geophysical logs were used, most of which were obtained from wells within 6 mi of the outcrop area. The aquifer, is thickest, about 170 ft, in Marlboro Township, Monmouth County (fig. 3).




Figure 2.--Structure contour of the top of the Farrington aquifer.




Figure 3.--Thickness of the Farrington aquifer.




Figure 5. Generalized potentiometric surface of the Farrington aquifer, 1959.

a discharge to a recharge area prior to 1959. Ground-water flow in 1959 was from the canal to Perth Amboy's Runyon well field (fig. 5).

Water-level measurements made in November 1973 at more than 180 wells were used to construct a 1973 potentiometric surface for the Farrington aquifer. The map (fig. 6) shows a deeper and more extensive cone of depression with the lowest point in excess of 70 ft below mean sea level in the Sayreville area. The gradient from the Washington Canal to Perth Amboy's Runyon well field increased 10 ft/mi between 1959 and November 1973. Water levels in the major recharge area of South Brunswick Township area did not change significantly from 1959 to November 1973.

Withdrawals

Withdrawals from the Farrington aquifer south of the Raritan River began at Perth Amboy's Runyon well field in 1897. By 1914 total withdrawals from the Farrington aquifer in Middlesex County "did not exceed one or two million gallons daily" (Barksdale and others, 1943, p. 107). Annual withdrawal data presented by Barksdale and others (1943, p. 108) for the period 1929-42 are shown in figure 7 together with withdrawals for the period 1959-73. The peak withdrawal of 12 Mgal/d (18 ft³/s) for the period of 1929-42 occurred in 1936. The lowest withdrawal rate of 7 Mgal/d (11 ft³/s) for the period occurred in 1942.

Ground-water withdrawals from the Farrington aquifer for the period 1959-73 are presented in figure 8. The total withdrawal shown includes irrigation, public supply, and industrial use. Irrigation withdrawals did not exceed 0.3 Mgal/d (0.5 ft³/s) and, therefore, are not shown in figure 8. Total withdrawal increased 113 percent, from 12.1 Mgal/d (18.7 ft³/s) in 1959 to 25.8 Mgal/d (1.4 ft³/s) in 1973. Public supply and industrial withdrawals during the period 1959-65 were approximately equal and each increased at an average annual rate of 0.2 Mgal/d (0.3 ft³/s). However, during the period 1966-73, yearly industrial withdrawals were virtually unchanged; while, public-supply withdrawals increased from 9.0 Mgal/d (13.9 ft³/s) to 18.4 Mgal/d (28.5 ft³/s), an average annual rate of increase of 1.2 Mgal/d (1.9 ft³/s). Much of the increase in public-supply withdrawals from 1966 to 1973 occurred southeast of the Old Bridge-Sayreville area.

Upper Confining Unit

The upper confining unit for the Farrington aquifer as defined in this report consists mainly of the Woodbridge Clay Member of the Raritan Formation. The upper confining unit also includes the clayey segment of the overlying Sayreville Sand Member and the South Amboy Fire Clay Member, both of the Raritan Formation, when these units are in direct contact with the Woodbridge. This confining unit is quite extensive and has been traced into Monmouth County on the basis of geophysical logs and palynological data. A thickness map of the confining unit, based




Figure 6. Potentiometric surface of the Farrington aquifer, November 1973.

on geophysical and drillers' logs, is shown in figure 9. Although variable in thickness, the unit is generally greater than 100 ft thick southeast of the outcrop of the Old Bridge Sand Member. The unit has a maximum thickness of 244 ft.

The Woodbridge Clay Member is a thin to thick-bedded sequence of micaceous silts and clays (Owens and Sohl, 1969, p. 239). The basal part of the Woodbridge "contains beds of compact, tough, and highly refractory fire-clay" (Barksdale and others, 1943, p. 103). This fire-clay has been mined in the vicinity of Sayreville. Also, near Sayreville, the Woodbridge contains lignite, pyrite, and nodular masses of impure siderite (Barksdale and others, 1943, p. 103). To the southwest, the clay content in the Woodbridge decreases, while the sand and gravel content increases. The hydrological significance of this change in lithology will be discussed in a later section of this report.

The Woodbridge ranges in thickness from 50 to 90 ft near the outcrop area (Barksdale and others, 1943, p. 103). Farther downdip, the thickness is 190 ft at Fort Hancock and 120 ft at Toms River (Perry and others, 1975, p. 1542). Perry and others (1975, p. 1543) state that the Woodbridge is "probably estuarine to shallow water marine in origin." Siderite nodules found near Sayreville in the upper part of the Woodbridge contained marine fossils suggesting a marine depositional environment for at least part of Raritan time (Barksdale and others, 1943, p. 103). Dinosaur footprints have also been found in the upper part of the Woodbridge (Barksdale and others, 1943, p. 103-104).

The Woodbridge Clay Member is widespread throughout the Raritan Bay area (Owens and Sohl, 1969, p. 239) and has been traced from Long Island to southern New Jersey on the basis of recent palynological studies. Pollen characterizing the Woodbridge has been found in clays cropping out along the North Shore of Long Island (Sirkin, 1974, p. 440) and in clay pits near Sayreville in Middlesex County (Wolfe and Pakiser, 1971, p. B38-39). Core samples obtained from well sites at Matawan, Monmouth County, and at Fort Dix and Medford, Burlington County, have yielded this same pollen zonation (Sirkin, written commun., 1971). These sites are located 10-15 mi downdip from the outcrop area. Farther downdip, the same zonation has been found in cores collected at Fire Island State Park, Long Island; Fort Hancock, Monmouth County; and Toms River, Ocean County (Perry and others, 1975, p. 1540) as well as from cores obtained at New Brooklyn Park, Camden County, and at Milmay, Cumberland County (Sirkin, written commun., 1971).

Overlying the Woodbridge Clay Member at some locations is the Sayreville Sand Member of the Raritan Formation. The sand consists of fine to medium sand with an average thickness of 35-40 ft (Barksdale and others, 1943, p. 101-102). Locally, it is thin and clayey. Because of its irregular occurrence and its clay content, the Sayreville sand is not a significant water-producing unit.




Figure 9.--Thickness of the upper confining unit.




Figure 20. Simulated potentiometric surface of the Farrington aquifer, 1985.

(4.3 ft³/s), infiltration from surface-water bodies (2.6 ft³/s, and water released from storage (3.4 ft³/s). All of these occurred within the subarea.

Discharge from the subarea for the last time step of 1973 was largely by withdrawals through wells. The total withdrawal rate through wells was 26.5 ft³/s. Combined discharge through vertical leakage to the Old Bridge and to surface-water bodies was approximately 3.2 ft³/s. The difference between inflow, water released from storage, and outflow is 0.3 ft³/s, about 1 percent of outflow, which is probably due to calculation errors inherent in the computer.

A budget analysis of the subarea under transient conditions for the year 2000 produced a similar percentage of inflows and discharges. However, the values were greater than those calculated for 1973.

SUMMARY AND CONCLUSIONS

The Potomac-Raritan-Magothy aquifer system consisting of sand, silt, clay, and gravel of Cretaceous age is the most productive source of ground water in the northern part of the New Jersey Coastal Plain. The Farrington and the Old Bridge aquifers are the two major aquifers within the Potomac-Raritan-Magothy system in Middlesex and Monmouth Counties.

The Farrington aquifer consists primarily of the Farrington Sand Member of the Raritan Formation and overlying surficial deposits in Middlesex County. In Monmouth County, the aquifer consists of the underlying sand unit of the Potomac Group. The aquifer ranges in thickness from a featheredge at its outcrop to more than 170 ft in Marlboro Township, Monmouth County. The mean specific capacity of 99 wells, mostly in Middlesex County, is 20.4 (gal/min)/ft of drawdown. The mean specific capacity per ft of well screen is 0.62 (gal/min)/ft per foot of screen.

Overlying the Farrington Sand Member is a confining unit of silt and clay composed mainly of the Woodbridge Clay Member of the Raritan Formation. The confining unit has a maximum thickness of 244 ft and separates the overlying Old Bridge aquifer from the Farrington aquifer.

A major cone of depression existed in the Farrington aquifer near Sayreville in 1959 and 1973. Cones of depression for the Old Bridge aquifer occurred in the Keyport area in 1959 and 1973 and in the Freehold area in 1973. Withdrawals from wells tapping the Farrington aquifer increased from 12.1 Mgal/d (18.7 ft³/s) in 1959 to 25.8 Mgal/d (39.9 ft³/s) in 1973. The major recharge area for both the Farrington aquifer and the Old Bridge aquifer is in South Brunswick Township in Middlesex County.

A finite-difference digital-flow model was developed to simulate water-table and artesian conditions in the Farrington

aquifer. A lateral hydraulic conductivity of 105 ft/d was used for most of the area. A uniform storage coefficient of 1.6×10^{-4} was used for artesian conditions and a uniform specific yield of 0.25 for water-table conditions. Vertical hydraulic conductivity of the upper confining unit ranged from 4.2×10^{-7} to 1.0×10^{-10} ft/s and a specific storage of 4×10^{-5} ft⁻¹ was used. The model includes the effects of declining water levels in the Old Bridge aquifer. For transient conditions, the 1959 Farrington potentiometric surface was used as the starting head and the 1959 Old Bridge potentiometric surface was used as the initial head overlying the confining unit. Old Bridge heads were adjusted at each node and at every time step using the average rate of change in head for each node between 1959 and 1973.

The model was calibrated for the 15-year period, 1959-73. Yearly withdrawal rates were used to stress the aquifer. Calibration of the model was achieved by comparing the calculated potentiometric surface for the end of the 15-year period with the observed November 1973 potentiometric surface. In addition, hydrographs of selected wells were compared with model results. After calibration, steady-state conditions were simulated. The model results compared favorably with available prepumping water levels.

The potentiometric surface of the Farrington aquifer was simulated to the year 2000 by using projected withdrawals. The withdrawals were estimated by a linear projection determined from 1959-73 withdrawals. The simulated potentiometric surface for the Sayreville area is in excess of 100 ft below mean sea level by 1985 and exceeds 150 ft by 2000. The simulated potentiometric surfaces for 1985 and 2000 are somewhat similar to the 1973 surface, but the cone of depression in the vicinity of Sayreville is greater in depth and area.

A ground-water budget analysis for steady-state conditions prior to development indicates that total inflow into the Farrington aquifer was 16 ft³/s. Recharge in the outcrop area and vertical leakage from the Old Bridge each accounted for about 8 ft³/s each. Approximately 75 percent of the discharge occurred in or near the outcrop area. Most of this discharge was into the Raritan River, Washington Canal area, and Arthur Kill. The remaining 25 percent of the discharge occurred southeast of the outcrop as vertical leakage into the overlying Old Bridge aquifer and as lateral flow into Ocean and Burlington Counties.

The budget analysis for transient conditions (1959-2000) indicates the importance of vertical leakage (mainly from the Old Bridge) as a source of water to the Farrington aquifer. Other sources of water include recharge in the outcrop area, water released from storage, and infiltration from the Washington Canal and part of the Raritan River. The original hydraulic gradient toward the two surface-water bodies was reversed prior to 1959, thus causing the Washington Canal and part of the Raritan River to recharge the aquifer. The budget analysis also shows that

recharge into the aquifer from these two surface-water bodies increased with time during the simulation.

A transient budget analysis for the last time step of 1973 was made for a subarea consisting mainly of Middlesex County. About 48 percent ($14.3 \text{ ft}^3/\text{s}$) of the total inflow to the subarea was through its boundaries. Other sources included direct recharge ($5.4 \text{ ft}^3/\text{s}$), vertical leakage, mainly from the Old Bridge, ($2.6 \text{ ft}^3/\text{s}$), and water released from storage ($3.4 \text{ ft}^3/\text{s}$). Withdrawals from wells ($26.5 \text{ ft}^3/\text{s}$) were the major discharge from the subarea of the aquifer. The combined rate of discharge through vertical leakage to the Old Bridge and to surface-water bodies was approximately $3.2 \text{ ft}^3/\text{s}$.

Analysis for the year 2000 showed a similar percentage. However, the values were greater than those calculated for 1973.

REFERENCE NO. 11

Wet Din

Trube

STATE OF NEW JERSEY
STATE WATER POLICY
COMMISSION



SPECIAL REPORT 8

THE GROUND-WATER SUPPLIES OF
MIDDLESEX COUNTY, NEW JERSEY

Prepared in cooperation with the United States Department
of the Interior, Geological Survey

1943

STATE OF NEW JERSEY
STATE WATER POLICY COMMISSION
HOWARD T. CRITCHLOW, ENGINEER IN CHARGE

The Ground-Water Supplies of Middlesex County New Jersey

With Special Reference to the Part of the Coastal Plain
Northeast of Jamesburg

By

HENRY C. BARKSDALE

MEREDITH E. JOHNSON

ROGER C. BAKER

EDWARD J. SCHAEFER

GEORGE D. DEBUCHANANNE

*Prepared in cooperation with the
United States Department of the Interior,
Geological Survey*

NEW JERSEY STATE WATER POLICY COMMISSION

28 WEST STATE STREET, TRENTON, N. J.

GEORGE S. BURGESS, *Chairman*Madison

THURLOW C. NELSONHighland Park

HERBERT K. SALMONStanhope

FORSTER W. FREEMANPaterson

ERNEST J. HOWESouth Orange

JOHN WYACK, *Secretary*

HOWARD T. CRITCHLOW, *Chief Engineer*

CONTENTS

	PAGE
Abstract	ix
Introduction	1
Cooperation and personnel	1
Authorship	3
Acknowledgments	3
Area described	4
Scope of report	7
History of ground-water development	8
Public water supplies	8
Industrial water supplies	10
Need for regulated ground-water development	12
Outline of geology	14
Physical divisions	14
Geologic history	14
Outline of the stratigraphy	16
Stratigraphic table	18
Precipitation and evaporation	22
Well and pumpage inventory	30
Summary and scope	30
Distribution of pumpage	31
Fluctuations of the water table	34
Physical properties of the aquifers	39
Chemical character of the ground water	47
Hydrology and geology of the rock formations	52
Cenozoic sequence	52
Quaternary system	52
Recent series	52
Alluvium	52
Eolian deposits	53
Pleistocene series	54
Wisconsin drift	54
Cape May formation	55
Pensauken formation	57
Mesozoic sequence	60
Cretaceous system	60
Upper Cretaceous series	60
Mount Laurel and Wenonah sands undifferentiated	61
Marshalltown formation	62
Englishtown sand	62
Woodbury clay	64
Merchantville clay	64
Magothy formation	64
Raritan formation	66
Amboy stoneware clay	67
Old Bridge sand member	67
Geology	67
Physical properties	68
Quality of water	69
Development and pumpage	70
Factors affecting safe yield	77

	PAGE
Mesozoic sequence (Continued)	
Cretaceous system (Continued)	
Upper Cretaceous series (Continued)	
Raritan formation (Continued)	
Old Bridge sand (Continued)	
Factors affecting safe yield (Continued)	
Available recharge	79
Intake area	80
Recharge as indicated by water level fluctuations	81
Estimates of natural recharge	84
Artificial recharge	87
Capacity to transmit water	91
Danger of salt-water intrusion	92
Contamination by industrial wastes	100
South Amboy fire-clay	101
Sayreville sand member	101
Woodbridge clay	103
Farrington sand member	104
Geology	104
Physical properties	106
Quality of water	106
Development and pumpage	107
Factors affecting safe yield	109
Available recharge	109
Artificial recharge	110
Capacity to transmit water	110
Salt-water intrusion	115
North of Raritan River	115
South of Raritan River	118
Salinity of surface waters	119
Theory of movement of salt water	120
Description of intrusion	122
Suggested remedial measures	133
Estimate of safe yield	138
North of Raritan River	138
South of Raritan River	138
Effect of proposed New Jersey ship canal	139
Raritan fire-clay	140
Triassic system	140
Newark group	140
Geology	141
Physical properties	143
Quality of water	144
Development and pumpage	145
Factors affecting yield	146
Nature of overlying material	146
Degree of cracking	148
Recharge from surface water	148
Estimate of safe yield	148
Proterozoic sequence (?)	149
Pre-Cambrian (?)	149
Wissahickon formation	149
Possible sources of additional water supplies	150
Index	155

TABLES

	PAGE
Table 1. Precipitation, evaporation from land pan, wind movement, and mean temperature at Runyon, 1923 to 1942	23
Table 2. Source and quantity of water pumped in each political unit in 1941	33
Table 3. Physical properties of water-bearing materials	40
Table 4. Analyses of water from the principal water-bearing formations..	48
Table 5. Quantity of water pumped from the Old Bridge sand member of the Raritan formation, 1917-1942	70
Table 6. Chloride content of monthly samples from tidal streams	93
Table 7. Chloride content of monthly samples from wells tapping the Old Bridge sand member of the Raritan formation	95
Table 8. Quantity of water pumped from the Farrington sand member of the Raritan formation, 1929-1942	108
Table 9. Chloride content of samples of water from wells tapping the Farrington sand member of the Raritan formation	116
Table 10. Chloride content of monthly samples from key wells tapping the Farrington sand member of the Raritan formation	124

ILLUSTRATIONS

	PAGE
Figure 1. Map of New Jersey showing county boundaries and the areas in which ground-water conditions are being studied	2
Figure 2. Map of Middlesex County, showing township and municipal boundaries, the location of important wells or well fields, and places referred to in the text	6
Figure 3. Generalized geologic section from Stelton through Runyon to the county line	17
Figure 4. Map of Middlesex County showing the areal distribution of the rocks of the Quaternary system	19
Figure 5. Map of Middlesex County showing the exposures of the rocks of the Triassic and Cretaceous systems	20

	PAGE
Figure 6. Map of Middlesex County showing the intake areas of the important aquifers	21
Figure 7. Map of Middlesex County showing the quantity and distribution of the ground water pumped in 1941	32
Figure 8. Diagram showing the fluctuations of water levels in a group of water-table wells not affected by pumping, and the actual and normal monthly precipitation for the years 1923-1942	37
Figure 9. Map of well fields tapping the Old Bridge sand member of the Raritan formation near Old Bridge, N. J.	73
Figure 10. Diagram showing relation between pumpage, precipitation and water levels in the Old Bridge sand member of the Raritan formation	82
Figure 11. Diagram showing the relation between water levels and pumpage in the Farrington sand member of the Raritan formation....	112
Figure 12. Map of the area between Perth Amboy and Spotswood showing the location of wells tapping the Farrington sand member of the Raritan formation	113
Figure 13. Diagram showing the fluctuations in the chloride content of samples from wells tapping the Farrington sand member of the Raritan formation	123

LETTER OF TRANSMITTAL

*Mr. George S. Burgess, Chairman
State Water Policy Commission*

DEAR SIR:

I am transmitting herewith a report on ground-water supplies of Middlesex County, N. J., prepared by Henry C. Barksdale, Hydraulic Engineer, U. S. Geological Survey. The report contains the information which has been assembled on ground-water conditions in that portion of Middlesex County adjacent to Raritan Bay and extending up the valleys of Lawrence Brook and South River. It discusses the public water supplies and many of the private supplies which are derived from the ground-water horizons designated in the report as Farrington (No. 1) sand and Old Bridge (No. 3) sand. Special Report No. 7 published in 1937 was a preliminary report on the water supplies from the No. 1 sand in the vicinity of Parlin.

The report points out the danger to the water supplies in this area from salt water intrusion and emphasizes the importance of reducing the draft on the No. 1 sand in order to avoid further pollution. It warns against further development in the No. 3 sand, the safe yield of which has been reached in this area. It is important that the municipalities and other public agencies be acquainted with this situation in order that the valuable ground water resources in this area may not be ruined by overdraft.

I therefore recommend that this report on ground-water supplies of Middlesex County be published as a special report of the Commission in order that the information contained therein may be made available to the people of the State.

Respectfully submitted,

*H. T. CRITCHLOW,
Engineer in Charge.*

June 11, 1943.

ABSTRACT

Ground-water investigations have been carried on in parts of Middlesex County since 1923. This report is based upon detailed observations of ground-water conditions in that part of the coastal plain between Jamesburg and Perth Amboy, and upon a generalized survey of ground-water conditions in the remainder of the county. It deals primarily with the factors affecting the safe yield of the more important aquifers in the county.

Roughly the northwestern third of the county is underlain by rocks of the Newark group of Triassic age and the southeastern two-thirds by sands and clays of the coastal plain, which are of Cretaceous age and are largely unconsolidated. The rocks of the Newark group dip toward the northwest, but they are so badly fractured that the dip is of very little significance from a hydrologic standpoint. Intruded into the rocks of the Newark group is a diabase dike, that is of no importance as a water-bearing formation, but stood as a ridge on the surface upon which the Cretaceous deposits were laid down. Hence the lowest of the Cretaceous sands (the Farrington sand member of the Raritan formation) is almost divided into two parts by it. To a considerable extent this ridge has been effective in retarding the advance of salt water into this sand from the estuary of the Raritan River. The beds of the coastal plain formations dip to the southeast, and alternating layers of permeable sands and relatively impermeable clays provide a setting under which water supplies are frequently encountered under artesian conditions. Both the Cretaceous formations and the older rocks of the Newark group are overlain throughout much of the county by various Quaternary deposits. These latter deposits are relatively unimportant as water-bearing formations. Their principal importance lies in their ability to absorb water and transmit it to the underlying materials, or in a few places to prevent the absorption of water by the underlying bed.

Early developments of ground water in the county were primarily in the form of relatively shallow dug wells, and in the improvement of existing springs. Drilled wells similar to those generally in use today were not developed to any considerable extent until the end of the last century. The development of large supplies of ground water has depended to a considerable extent upon the development of well drilling methods and upon the improvement of well pumping machinery. In 1941 more than 37 million gallons of water a day was pumped from wells for industrial and municipal water supplies in Middlesex County. Of this amount about 22 million gallons a day was used exclusively for industrial purposes and the remainder for public water supplies.

The quality of water obtained from wells in Middlesex County is generally satisfactory for all ordinary purposes. It sometimes requires treatment for the removal of iron or for the reduction of hardness. In some areas the ground waters have been contaminated by sea water that has been drawn into the aquifers by heavy pumping. Where this contamination has been severe, the waters are of little value except for cooling.

In the course of these investigations records of water levels have been obtained in a great many wells. Some of these records now cover a period of more than twenty years. Included in this group are some wells not affected by pumping that have been used as a standard for comparison with the fluctuations in the other observation wells. They have also proved valuable as indices of the amount of water naturally stored in the ground at various times. As such they are useful outside the scope of this report for the prediction of minimum stream flow and for similar purposes. At the Perth Amboy Water Works, at Runyon, a record of precipitation, temperature and evaporation has been obtained for approximately 20 years.

Of the various aquifers within the county three are of major importance. The rocks of the Newark group are the principal source of ground water in the northwestern part of the county. The Old Bridge and Farrington sands, both members of the Raritan formation, are the principal sources of water supply in the southeastern two-thirds of the county. The other aquifers are of relatively little importance either because of the limited area in which they are available or because they are not capable of yielding substantial supplies.

The Old Bridge sand is the most important aquifer within the county. It supplies more than half the total water used for industrial and public water supplies. In 1941 a total of more than 19 million gallons a day was withdrawn from this sand in Middlesex County and 2 or 3 million gallons a day was taken from wells tapping this sand outside the county, bringing the total yield to 21 or 22 million gallons daily. In 1942 the total pumpage had increased to 25 or 26 million gallons daily. Studies made of this sand indicate that natural recharge probably could not supply this large yield of water. Fortunately, however, at least two major developments include works for artificially recharging this sand. Even so, it is believed that the safe yield of this sand has been reached. The pumpage from this sand should not be increased except in instances where it is possible and desirable to recharge the sand with surface water in an amount essentially equivalent to the additional water to be taken from wells.

The Farrington sand yielded about 8.5 million gallons daily to municipal and industrial wells during 1941. The safe yield of this sand appears to have been exceeded for a considerable period in the past. Its capacity is limited not by the amount of natural recharge or by its ability to transmit water, but rather by the fact that it is exposed in numerous localities to the intrusion of salt water from surface sources. A considerable part of this sand now contains water that is contaminated by salt water. In at least three areas the water in this sand is severely contaminated. There is substantial evidence supporting the belief that the areas of contamination will expand with continued pumping from the wells tapping this sand. A few wells that drew from this sand have already been abandoned because of salt-water contamination, and it seems probable that a considerable number of others will have to be abandoned at some time in the future. After this has occurred and the total pumpage from the sand has thereby been reduced materially, it may be possible to develop some new water supplies from this sand in areas near its intake area and remote from bodies of surface water containing salt.

The rocks of the Newark group yield water to a large number of wells in the county. In localities where they are covered by permeable material they yield substantial quantities. In areas where they are not covered by such deposits

or where they are covered by impermeable materials, the yield is very low. The water that these rocks yield comes almost entirely from cracks which form a small part of their total volume so that their storage capacity is low. Substantial yields are safely obtained only in areas where the overlying material is capable of absorbing and storing considerable amounts of water and of transmitting it freely to the underlying rock.

It seems probable that no more large ground-water developments can be made within Middlesex County. Possibly some additional water may be obtained from the Newark group, but this should not be attempted without a careful study of conditions in the vicinity of any proposed development, because draft on these rocks is already heavy. Some additional water can be developed from the Englishtown sand in the southeastern corner of the county, but care should be exercised not to injure water supplies derived from this sand down the dip in Monmouth County. On the whole it seems probable that any large additional supplies of water for Middlesex County will have to come from surface water, and very possibly from sources outside the county. The appraisal of sources of surface water is, however, outside the scope of this report.

Future studies of the Old Bridge sand should be directed primarily toward ways of increasing its intake capacity by artificial recharge. Those of the Farrington sand should be concerned primarily with the salt-water intrusion in this sand. Intensive quantitative studies should be made of the Newark group in order to estimate more accurately its safe yield in different localities. Measurements should be continued at the evaporation station at Runyon and in the Morrell and other water-table wells. A few additional observation wells should be established in parts of the county where there is no effect of pumping.




FIGURE 2.—Map of Middlesex County, showing municipal boundaries, the location of important wells or well fields, and places referred to in the text.

KEY TO WELL NUMBERS (Figure 2)

- | | |
|----------------------------------|-------------------------------------|
| 1. Perth Amboy Water Department | 94. Elizabethtown Water Company, |
| 2. Hercules Powder Company | Piscataway well field |
| 3. E. I. duPont de Nemours & Co. | 95. Plainfield-Union Water Company, |
| 4. National Lead Company | Clinton Avenue wells |
| 5. South Amboy Water Department | 96. Middlesex Water Company well |
| 6. South River Water Department | fields |
| 7. Peter J. Schweitzer Company | 97. Kingston Water Company |
| 11. Cranbury Water Company | 98. Jamesburg Water Company |
| 12. State Home for Boys | 99. Helmetta Water Company |
| 23. Kufka test well | 100. Duhermal water supply |
| 24. Fischer test well | 101. Morrell well |
| 38. Beecher test well | 102. Hulsart well |

Scope of report.—This report is based upon detailed observations of ground-water conditions which were begun at the Perth Amboy Water Works at Runyon in 1923, and have been gradually expanded to cover much of the industrial area along the estuary of the Raritan River, and upon a more generalized survey of ground-water conditions in the remainder of the county which has been carried out mainly during 1941 and 1942. Detailed field studies have been made of the geology and hydrology of the part of the county that lies in the coastal plain northeast of Jamesburg. It is in this area that most of the ground-water development in the county has taken place, and the major part of the report deals with the conditions there. For the remainder of the county, the report is more generalized.

The quality of the ground water of the area is discussed briefly in a section of the report devoted to that topic. Samples of water have been collected from representative wells tapping each of the more important aquifers and have been analyzed for their mineral content in the Water Resources Laboratory of the Geological Survey. The results of these analyses are included in tabular form. No attempt is made to determine the sanitary or bacteriological quality of the water as these features are usually not due to conditions inherent in the aquifer but to extraneous causes or to the treatment of the water after it has been pumped to the surface.

During the investigation on which this report is based much information on water levels and artesian pressure was collected. Many thousands of individual measurements of water level or artesian pressure were made and continuous records of water levels were obtained by means of automatic water-stage recorders at one time or another in about thirty wells. Most of these records have been published by the Geological Survey in its annual reports on water levels and artesian pressure.¹ The remaining records will be published in forthcoming

¹ Meinzer, O. E., Wenzel, L. K., and others, Water levels and artesian pressure in observation wells in the United States: U. S. Geol. Survey Water-Supply Papers 777, 817, 840, 843, 880, 906, 936, etc. (Annual volumes since 1935.)

adjacent counties. Effective control should therefore be State-wide and the regulation of inter-state aquifers may require inter-state cooperation. Effective control should also be broadly inclusive. Restrictions applied to one class of water users and not to another would be futile as well as unfair. No diversion of ground water should be made without the prior approval of some unbiased agency empowered to safeguard this valuable natural resource against injurious overdevelopment.

OUTLINE OF GEOLOGY

Physical Divisions

Middlesex County lies within two major physiographic provinces, the Coastal Plain Province and the Piedmont Province. This division is based largely on rocks and structure projected from nearby regions, for in Middlesex County the topography would not warrant this subdivision, mainly because it has been modified by Quaternary deposits. The part of the county which is in the Coastal Plain Province is, roughly, that which lies southeast of a line from Plainsboro to Carteret. In this area the bed rock consists of unconsolidated or poorly consolidated sands and clays of Cretaceous age (see Stratigraphic Table, page 18, for geologic time-table) which dip at low angles to the southeast.

The Piedmont Province includes the area to the north and west of the Coastal Plain Province. It is underlain by relatively hard Triassic rocks, which in most regions stand up as rounded hills above the flat coastal plain. The prominences at Sand Hills are capped by outliers of the formerly more extensive Cretaceous sediments which have been protected from erosion by the numerous consolidated layers of "iron-stone" (ferruginous sandstone) and the resistant Triassic diabase to the south. Farther north and east the Triassic shales have been eroded nearly as low as the Cretaceous sediments. This feature, together with the blanket of Quaternary deposits, has left little difference in the topography of the two provinces.

Geologic History

The geologic history of Middlesex County as observed from the rocks within its borders is necessarily far from complete. Much of it, however, can be read from rocks in nearby areas although other events are forever lost. References to the length of time which has elapsed since the deposition of some of the formations are of necessity approxi-

mate. They are based on age determinations from radio-active minerals and are given to indicate the slowness with which geologic processes operate, the vastness of the intervals in which there are no geologic records within the county and, to some extent, the relative age of the existing formations.

The gneiss of the Wissahickon formation, known only from well logs in Middlesex County, gives us the first chapter in the geologic history of the county. In pre-Paleozoic time, at least 600 million years ago, muddy sediments were deposited, which later were folded and metamorphosed (altered) and then intruded by highly heated molten rock. This igneous activity further metamorphosed and recrystallized the sediments so that they little resembled the original deposits.

A long period of erosion followed, during which the existing mountains and hills were reduced to a fairly level plain. This was followed by the development of a depression which extended from the Gulf of Mexico northeastward through the Appalachian belt and Canada, and which was occupied by an arm of the sea for many millions of years. The record of those years is read in the sediments which were deposited in the depression and in which we find today the fossils, or preserved remains of animals which lived and developed during that period (the Paleozoic era). Since these sediments are today found only northwest of Middlesex County, the presumption is that either this area was above sea-level during that entire period, or that such sediments as were deposited have since been entirely removed by erosion. Whichever assumption is right, the second oldest rocks which we find in Middlesex County today are the generally red-colored rocks of Triassic age, which are believed to be at least 400 million years younger than the Wissahickon formation.

The Triassic sediments in Middlesex County are believed to have been deposited in an intermontane valley in the latter part of that geologic period. During this same time there was considerable igneous activity, the most important of which was the intrusion of the thick sill of diabase known along the Hudson River as the Palisades. This sill is continuous in the Triassic rocks in Middlesex County from Carteret to Rocky Hill, but is found at the surface only from Deans to Rocky Hill. The Triassic rocks were later tilted, faulted and eroded during an interval of about 100 million years. This interval spanned all of the Jurassic period and more than half of the Cretaceous period.

In early Upper Cretaceous times the land surface in Middlesex County consisted of a plain of moderate relief sloping to the southeast at about 60 feet to the mile. The bed rock in the southern third of the

area consisted of the Wissahickon formation and the rest consisted of Triassic rocks, above which the resistant diabase sill stood as a ridge. Then the land was submerged and Upper Cretaceous sands and clays were deposited on it in alternating layers dipping to the southeast. These sediments tended to thicken oceanward so that the older sediments dipped parallel to the underlying plain while the higher formations were more nearly horizontal. During this period there were fluctuations in the depth of water, as indicated by the alternation of shallow and deep water fossils in the Cretaceous formations. The general relationship of the various rocks in the county is shown on the geologic section in figure 3.

In the Tertiary period which followed, there were intervals of deposition and of erosion, but any sediments which may have been deposited in Middlesex County have since been removed by erosion, together with much of the older Cretaceous deposits.

In the Quaternary period, which dates from the beginning of the Ice Age and in which we are now living—a period of some 2 million years—there were four advances of great ice sheets moving from centers in Canada into the northern part of the United States, interspaced with times of partial submergence and deposition. In Middlesex County there is evidence of only the last ice sheet. This consists of the Wisconsin drift which blankets the northern third of the county. The oldest non-glacial Quaternary deposits have been entirely removed from the county. The Pensauken formation, which is much older than the Wisconsin drift, is found capping the hills and higher divides but has been removed from the larger stream valleys. The Cape May formation, which is probably slightly older than the Wisconsin drift, is found mainly in stream valleys. Since the retreat of the Wisconsin ice sheet there have been only relatively slight physiographic changes in the county.

Outline of the Stratigraphy

The areal geology of Middlesex County is shown on figures 4, 5 and 6 on pages 19, 20, and 21. The geologic formations shown thereon range from soft, unconsolidated alluvial deposits formed within the last few thousand years, to compacted rocks whose origin dates back many millions of years. The following stratigraphic table, arranged in normal sequence (i. e. youngest formation at the top) includes a still older formation (the Wissahickon) which has been penetrated by a number of deep wells within the county. Detailed descriptions of the formations are given in the section on hydrology and geology of the rock formations beginning on page 52.




FIGURE 3.—Generalized geologic section from Stelton through Runyon to the county line.

STRATIGRAPHIC TABLE FOR MIDDLESEX COUNTY, N. J.

Cenozoic sequence

Quaternary system

Recent series

Alluvium

Eolian deposits

Pleistocene series

Wisconsin drift

Cape May formation

Pensauken formation

UNCONFORMITY

Mesozoic sequence.

Cretaceous system

Upper Cretaceous series

Mount Laurel and Wenonah sands

Marshalltown formation

Englishtown sand

Woodbury clay

Merchantville clay

Magothy formation

Raritan formation

Amboy stoneware clay

Old Bridge sand member

South Amboy fire-clay

Sayreville sand member

Woodbridge clay

Farrington sand member

Raritan fire-clay

UNCONFORMITY

Triassic system

Upper Triassic series (Newark group)

Brunswick shale

Lockatong formation

Stockton formation

UNCONFORMITY

Proterozoic sequence (?)

Pre-Cambrian (?)

Wissahickon formation




FIGURE 4.—Map of Middlesex County showing the areal distribution of the rocks of the Quaternary system. Small quantities of good water are obtained from the eolian deposits, the stratified drift, the Cape May and Pensauken formations, and the unclassified deposits.




FIGURE 5.—Map of Middlesex County showing the exposures of the rocks of the Triassic and Cretaceous systems. Small quantities of good water are obtained from the Mount Laurel and Wenonah sands, the Englishtown sand and the Magothy formation within the county. Substantial quantities are derived from the Raritan formation and the rocks of the Newark group.




FIGURE 6.—Map of Middlesex County showing the intake areas of the important aquifers. Large quantities of good water are obtained from the Old Bridge and Farrington sand members of the Raritan formation. Small quantities are obtained from the Englishtown sand and the Mount Laurel and Wenonah sands. The rocks of the Newark group yield moderately large supplies where overlain by permeable materials, but elsewhere their yield is small.

MAGOTHY FORMATION

2187. Browntown; $\frac{3}{4}$ mile west of, from road cut about $\frac{1}{4}$ mile south of highway, 25 feet above base.
 2190. do ; $\frac{3}{4}$ mile west of, from same location and about 2 feet above sample 2187.
 2191. Cheesequake; Perrine's pit, 8 feet above base of formation.
 2198. Runyon; $\frac{1}{4}$ miles NE of, from small sand pit about 100 yards north of highway, about 10 feet above base.
 1582. Browntown; $\frac{3}{4}$ mile SE of, Dr. Ostberg's well, 160 to 165 foot depth.

OLD BRIDGE SAND MEMBER OF THE RARITAN FORMATION

2167. South River; Marcus Wright's pit, 5 feet above water level, elevation above base of formation not determined.
 2169. do ; Marcus Wright's pit, 11 feet above sample 2167.
 2170. do ; do , 14 feet above sample 2168.
 2171. do ; do , 24 feet above sample 2170 and 6 feet below contact with Pensauken formation.
 2173. Parlin; Crossman pit, 8 feet above contact with South Amboy fire clay.
 2174. do ; do , 18 feet above base of sand.
 2175. do ; do , 28 feet above base of sand.
 2176. do ; do , 39 feet above base of sand.
 2177. do ; do , 48 feet above base of sand and 5 feet below contact with Pensauken formation.
 2181. Old Bridge; South River Sand Company pit, 20 feet below contact with Amboy stoneware clay.
 1630. Runyon; test well A-41, 13 foot depth.
 1637. do ; test well K-1, 7 foot depth.
 1638. do ; test well J-4, 7 foot depth.

SAYREVILLE SAND MEMBER OF THE RARITAN FORMATION

2172. Sayreville; from pit near Raritan River, 3 feet above contact with Woodbridge clay and 4 feet below contact with South Amboy fire clay.

FARRINGTON SAND MEMBER OF THE RARITAN FORMATION

2160. South River; abandoned sand pit about $1\frac{1}{2}$ miles north of town, 20 feet above Raritan fire clay.
 2161. Same pit as 2160, 25 feet above Raritan fire clay.
 2162. Same pit as 2160, 35 feet above Raritan fire clay.
 2163. South River; about 1 mile northwest of town, $2\frac{1}{2}$ feet below Woodbridge clay.
 2164. Same locality as 2163, $3\frac{1}{2}$ feet below Woodbridge clay (represents locally coarse streak).
 2165. Milltown; from highway cut about 1 mile east of town, 1 foot above Raritan fire clay.
 2166. Milltown; Marcus Wright's pit, $13\frac{1}{2}$ feet above Raritan fire clay.

The volumetric samples were collected by driving a sampling tube perpendicularly into a smooth flat surface of the aquifer. The depth to which the tube was driven was carefully measured. The material along one side of it was then excavated without disturbing the tube or its contents. The sample was cut off flush with the end of the sampler transferred to a can and sealed for shipment to the laboratory. The known area of the sampling tube and the depth to which it is driven make possible a computation of the volume occupied by the sample in nature. The sampling apparatus and technique were devised by Mr. Meinzer and are described in detail by Stearns.¹¹ Volumetric samples are considered more reliable than samples from wells, because there is less likelihood of collecting foreign material or of losing fine particles from the sample. Furthermore in making determinations of porosity and permeability in the laboratory an attempt is made to adjust the volume of the sample to that occupied by it in nature.

A description of the laboratory procedure used to determine the various factors shown in the table and a discussion of their significance is also given by Stearns in the same paper. The significance of the coefficient of permeability and the various laboratory and field methods of determining it are further discussed by Wenzel¹² in a paper published in 1942. A brief discussion and explanation of the various features shown in the table is given below.

The apparent specific gravity is the specific gravity of an oven-dried sample of the sand including the pore spaces. It must not be confused with the specific gravity of the mineral grains composing the sand.

Mechanical analyses of granular materials are made by separating into groups the grains of different sizes and determining what percentage by weight each group constitutes. The United States Bureau of Soils¹³ has adopted the following nomenclature and arbitrary limiting diameters, in millimeters:

Fine gravel	2 to 1
Course sand	1 to 0.5
Medium sand	0.5 to 0.25
Fine sand	0.25 to 0.1
Very fine sand	0.1 to 0.05
Silt	0.05 to 0.005
Clay	less than 0.005

¹¹ Stearns, Norah Duwell, Op. cit., p. 122.

¹² Wenzel, L. K., Methods for determining permeability of water bearing materials with special reference to discharging well methods: U. S. Geol. Survey Water Supply Paper 887, 1942.

¹³ Mechanical analysis of soils: U. S. Dept. Agr. Bur. Soils Bull. 4, 1896. Briggs, L. J., Martin, F. O., and Pierce, J. R., The centrifugal method of mechanical soil analysis: U. S. Dept. Agr. Bur. Soils, Bull. 24, 1904. Fletcher, C. C., and Bryan, H., Modification of the method of mechanical soil analysis: U. S. Dept. Agr. Bur. Soils, Bull. 84, 1912.

made only in the more recent complete analyses of water shown in the table. They seem to indicate, however, that all the ground waters in the county, with the possible exception of some water from the Magothy formation and possibly also some from the Newark group, contain too little fluoride to be of any significance. None of them contain enough fluoride to be harmful. Analyses of waters from other parts of New Jersey seem to confirm these conclusions.

HYDROLOGY AND GEOLOGY OF THE ROCK FORMATIONS

The geologic formations occurring in Middlesex County are discussed in the following pages in the same order that they appear in the stratigraphic table on page 18. Maps showing their areal extent are given on figures 4, 5, and 6. A brief geologic description of each formation or member listed in the table is presented. In general the reader is referred to the stratigraphic table and to the text accompanying it for the geologic age and relationship of the formations discussed in this section. Discussions of the groups into which the various formations or members fall is presented only when common features may best be described in this way. The hydrology of the various aquifers is presented in more or less detail depending upon their importance. Detailed discussions of the development and safe yield of the more important aquifers are also presented.

Cenozoic Sequence

QUATERNARY SYSTEM

Recent Series

ALLUVIUM

A preponderance of evidence indicates that since the retreat of the last glacial ice sheet, southern New Jersey has remained relatively static, with little or no movement of the land, either up or down, in relation to the level of the sea. During this period the streams have worked ceaselessly to remove the blanket of sand and gravel which had been deposited in all the larger valleys in Pleistocene time, and some of it, together with mud and organic material, has been redeposited in tidal flats and along stretches of the streams where the gradients are low. Such recently deposited material is known as alluvium and it covers several square miles in Middlesex County. It is relatively impermeable and of no importance as a source of water supply. Upstream from

tidal limits the deposits are small, and so far as known, everywhere less than 10 feet thick; but bordering Cheesequake Creek, the South, and the Raritan Rivers they are broad and very much thicker. In fact, test boreholes have shown that nearly two miles southwest of the mouth of Cheesequake Creek the alluvium—here a soft mud filling—is more than 50 feet thick. Of greater importance from a water-supply standpoint is the deposit of silt and mud which has accumulated in the channel of the Raritan River north and west of Sayreville and which blankets the underlying Farrington sand member of the Raritan formation and tends to prevent the contamination of that sand by salt water from the river. Test boreholes drilled prior to the construction of the Eastern New Jersey Power Company plant at Sayreville disclosed the fact that south of Crab Island the mud extends down 53 to 55 feet, within 2 feet of the underlying bedrock.

EOLIAN DEPOSITS

At present a large percentage of the southern half of Middlesex County is forested and winds have little effect in shifting the sand and soil of the region. That it was not so during some period since the deposition of the Cape May formation may be surmised from the sand dunes about one mile south of Spotswood and the rather widespread occurrence of typical Cape May material on the hilltops and higher slopes southeast of the South River between Matchaponix, Texas and Browntown. Similar material does not mantle the slopes northwest of the South River and it would therefore seem reasonable to suppose that the strong winds which accomplished this work came from the north or northwest. Because the wind-blown material is continuous with the undisturbed Cape May deposits it is impossible to separate them in mapping except on an arbitrary basis; and since elevation 40 is about the upper limit of the Cape May formation along the shore and in the valley of the South River, that elevation was made the dividing line in mapping these deposits.

In a few small areas the Eolian deposits overlies impermeable materials, and are sufficiently thick to yield satisfactory water supplies for domestic or farmstead purposes. In such places they provide the only water supplies available for such purposes without the construction of fairly deep drilled wells. Otherwise they have relatively little hydrologic importance.

Pleistocene Series

WISCONSIN DRIFT

The Wisconsin drift was deposited by the last of four huge continental ice sheets of Pleistocene age which covered portions of northern United States. It forms a nearly continuous mantle over the underlying Triassic and Cretaceous rocks in the northeast part of the county. The southern limit reached by the Wisconsin ice sheet in Middlesex County is roughly along a curved line from Plainfield to Metuchen and the mouth of the Raritan River at Perth Amboy. The glacier advanced from the north approximately to this line, then climatic conditions became such that the rate of movement southward just equalled the rate of melting with the result that the front of the glacier oscillated back and forth along this line. The ice dropped and piled up a huge mass of debris on its margin which forms the terminal moraine and the waters from the melting glacier deposited large amounts of gravel, sand and silt to the southwest forming an outwash plain. Later, as the climate became warmer, the ice front melted back leaving a blanket of till covering all of the county northeast of the moraine. The drift is of importance from a water-supply standpoint primarily because some parts of it are permeable enough to absorb water from precipitation and transmit it readily into the underlying beds.

The *outwash plain*, found between Metuchen, Plainfield and East Bound Brook, covers an area of about 16 square miles. It consists of layers of sand and gravel which together are called stratified drift and are so mapped on figure 4 on page 19. The stratified drift is about 10 to 60 feet thick on the eastern edge near the moraine. The material becomes finer and the deposit thins to the west so that at its irregular western border it is largely sand. In general the stratified drift is quite permeable, but it is too thin and covers too small an area to be in itself an important source of water. However, it holds water which percolates into the underlying Triassic rocks and this has increased the yield of a good many wells in that formation over and above the average yield of wells drawing from uncovered Triassic shale.

The *terminal moraine* is composed of a mixture of red clay, sand, gravel and a few boulders. In most places the material is fairly impermeable and does not yield much water, but in a few localities there are beds of stratified permeable material and the yield is higher. Because these areas are small, however, large supplies are not available.

The southwestern or outer margin of the terminal moraine is fairly well defined, as its surface rises fairly abruptly 100 to 150 feet above

MINOR AQUIFERS

the outwash plain. The moraine is from one to one and one-half miles wide, and its inner border is less well defined because it grades into the till plain to the northeast. The surface of the moraine is a series of hummocks and depressions, many of which are undrained and because of the impervious nature of the material are filled by small lakes. The thickness of the moraine is variable but ranges between 80 and 150 feet.

A *till plain* of Wisconsin age covers the area from the terminal moraine to the northeastern edge of the county. The till is similar to the morainic material and consists of unassorted and relatively impermeable red clay, sand, gravel and boulders derived largely from the underlying Triassic rocks. Its average thickness is only 20 to 30 feet with about 80 feet as a maximum. It is not an important source of ground water.

In some places the materials composing the terminal moraine and the till plain are so impermeable that they probably act as a roof over the underlying rocks and exclude from them much of the water from precipitation and from stream flow. This is indicated by the number of small ponds that have formed in depressions on these materials. On the whole it is probable that they do not increase but may decrease the amount of ground water that might otherwise be available from the underlying rocks.

CAPE MAY FORMATION

The Cape May formation is typically a pinkish-yellow, fine to medium-grained quartz sand with occasional small pebbles of quartz and ironstone, but it sometimes departs considerably from this type. For example, just north of the railroad station at Morgan, it is well exposed in a small pit where the basal portion is approximately 50% gravel, whereas the upper 5 feet of the deposit is fully 75% sand. The pebbles are chiefly quartz, but ironstone and unaltered flint were also noted. Five hundred feet north the pebbly lower portion is lacking.

In the valley of the South River and along the south shore of the Raritan River the Cape May formation is rather consistently true to type and in general forms a rather thin mantle only three to ten feet thick over the underlying Cretaceous sediments except where it fills the pre-Cape May channels of these streams. North of the Raritan River, however, there is a marked change in the composition of the Cape May. There it contains numerous partly rounded pebbles and fragments of Triassic red sandstone and shale, as well as fairly numerous lumps of Cretaceous clay. Apparently in Cape May time there were

RARITAN FORMATION

The Raritan formation is composed of alternating and irregular beds of clay, sand and gravel. The sands are predominantly white or light-colored, but gray and yellow beds are not uncommon, particularly in the region west of Jamesburg, and sometimes they are colored pink or orange by small percentages of iron oxides. The clay beds range in color from white through cream and light gray to dark gray and brick red. In composition they range from dark, sandy and lignitic beds, usually containing many nodules of pyrite or marcasite, to white-burning, highly refractory clays of great value. Many of the sandy beds are relatively clean or free of clay, but all gradations occur from nearly pure quartz sand to beds containing a high percentage of clay, muscovite, limonite, feldspar or other minerals. Lignite is a fairly common constituent of both the sands and the dark impure clays.

Most of the Raritan formation is believed to have been formed in shallow, brackish water and in estuaries and lagoons rather than in the open sea. This belief is based not only upon the variable character of the formation and the lignite, but also upon fossil evidence; numerous remains of land plants having been found in an excellent state of preservation near the middle of the formation in the Woodbridge region.

Although the horizontal extent of any one bed in the Raritan formation is not very great, it is nevertheless possible to divide it into several fairly distinct and mappable units in most of Middlesex County. These units are alternating layers of sand and clay. The clays of the Raritan formation have been extensively used in the ceramic industry and have been the subject of several reports by the Geological Survey of New Jersey. In them the clays received informal names because of their economic importance. The other members, composed dominantly of sand, were not given names but received numbers. In this report, where attention is focused on the sand members, it is proposed to give these members names. Thus, the units in the Raritan formation are from top to bottom:

Amboy stoneware clay
Old Bridge sand member (No. 3 sand of previous reports)
South Amboy fire-clay
Sayreville sand member (No. 2 sand of previous reports)
Woodbridge clay
Farrington sand member (No. 1 sand of previous reports)
Raritan fire-clay

A description of these units follows.

AMBOY STONEWARE CLAY

The Amboy stoneware clay varies in color from a light gray through darker grays to a nearly black clay with considerable carbonaceous material. Rarely it has a red mottled appearance. In some places it consists of a gray, more or less sandy clay resting on the white Old Bridge sand, but in other places the gray clay is underlain by as much as 10 feet of black carbonaceous clay. In turn the gray clay may be overlain with as much as 15 feet of black sandy clay. The black clay is lignitic and very similar to black clay in the Magothy formation, except that as a rule the black lignitic clays of the Magothy contain small rounded grains of amber. These are not common in the Raritan formation.

The Amboy stoneware clay was deposited on an uneven surface and was partly eroded before the deposition of the overlying Magothy formation. Its thickness ranges from 0 to 30 feet. Where present it forms an impermeable layer between the Magothy formation and the Old Bridge sand member of the Raritan formation.

OLD BRIDGE SAND MEMBER

GEOLOGY

The most productive aquifer in Middlesex County is the Old Bridge sand, a member of the Raritan formation. This sand has not been identified in outcrop very far south of Jamesburg, or anywhere north of the Raritan River or the Raritan Bay. It crops out or is exposed beneath permeable Pleistocene deposits in an irregular band that extends from the Raritan Bay near South Amboy to and probably beyond Jamesburg. Along this band which is shown on figure 6 and which has an area of about 25 square miles, the sand is exposed to the direct infiltration of meteoric waters. As is the case with the major coastal plain formations it dips gently to the southeast and has been identified in wells several miles from its outcrop in that direction.

The Old Bridge sand is the No. 3 sand member of previous reports containing descriptions of the Raritan formation. The name Old Bridge was selected because the sand crops out at several places in and near that village. One of the best exposures is at the pit of the South River Sand Company about half a mile northeast of Old Bridge. Furthermore, Old Bridge is the center of the greatest ground water develop-

North of the Raritan River, the Sayreville sand consists of layers of fine, white, micaceous sand, cross-bedded fine to coarse-grained white sand, with or without layers of white clay, and beds of arkosic sand. The general thickness is about 35 to 40 feet. The beds are so variable that there is no order of stratigraphic sequence over more than a small area. The lenses of arkosic sand, which may be as much as 12 feet thick were once used in the manufacture of fire brick near Perth Amboy.

Though a conspicuous member of the Raritan formation in the vicinity of Woodbridge and Perth Amboy, the Sayreville sand is thin or lacking in the vicinity of Runyon. In the prominent hill half a mile southwest of the southern approach to the Victory Bridge over the Raritan River it is a fine to coarse-grained white sand, arkosic towards the base, and about 40 feet thick. A mile to the southwest it is markedly cross-bedded, contains thick beds of ironstone and is only 15 feet thick. In a good exposure in Sayreville, due south of Crab Island, it is only 6 to 7 feet thick; and though the sand is fairly coarse, it contains lumps and thin lenses of white clay. Just 1,400 feet farther southwest, in the large pit of the Sayre & Fisher Brick Company, the sand is lacking and the South Amboy fire-clay can be seen directly overlying the laminated clays of the upper part of the Woodbridge clay. This same relationship can be observed in the pit of the New Jersey Clay Products Company, one and a quarter miles to the south-southwest. This "pinching out" of the Sayreville sand is the chief reason why not one well southeast of the Camden and Amboy Railroad is yielding water from this stratum. Carefully kept logs of wells and test boreholes show that even though it is sometimes present in the Runyon area, it is thin and clayey and not therefore an important aquifer.

No important water supplies have been developed from the Sayreville sand. In fact, not a single well is known to draw its water entirely from it and it was, therefore, impossible to obtain a sample of water for analysis. However, the South Amboy fire-clay which separates the Sayreville sand from the overlying Old Bridge sand, is irregular and sometimes absent so that in one or two wells there has apparently been no separation between these two sands, and at least one well probably draws water from both the Old Bridge and the Sayreville sands.

One sample of sand was collected from this member for analysis in the Water Resources Laboratory during the present investigation. The analysis in the table on page 42 indicates that the sample contained a considerable amount of clay and other fine materials. Its porosity was

44 percent, and its moisture equivalent was 12 percent. It would appear, therefore, that the specific yield of the sand is only about 32 percent and that its ability to store water is not as great as most of the other sands in the county. Analyses of two other samples from this sand are reported by Stearns,²² and they indicate a probable specific yield of about 39 percent, which is more in line with the other sands in the area. The analysis on page — shows that the coefficient of permeability of the recent sample from the Sayreville sand was only 30, indicating that water would move through it very slowly under ordinary conditions. The two samples reported by Stearns indicate an average coefficient of permeability of about 500 which again is more in line with the other sands in this area. Samples of this sand subsequently obtained from wells, although not analyzed in the laboratory, appeared to contain a smaller percentage of fine or clayey material than the sample sent to the laboratory. A recent examination of this sand where exposed in another pit tends to confirm this conclusion. It seems probable, therefore, that the capacity of the Sayreville sand to store and transmit water is fairly high in some places. Nevertheless its thinness and lack of continuity make it most unlikely that any substantial water supply can ever be developed from it.

WOODBIDGE CLAY

The Woodbridge clay underlies the Sayreville sand and ranges from 50 to 90 feet in thickness where uneroded. The upper portion consists of well stratified, dark-gray clays containing a sufficient amount of fine-grained sand to make an ideal material for the manufacture of common brick, and it is widely used for that purpose. The middle portion of the member commonly consists of gray clay, though sandy clays or clayey sands may occur. Both the upper and middle portions of the Woodbridge clay are extensively used in the manufacture of hollow tile. The basal portion of the member contains beds of compact, tough, and highly refractory fire-clay which are white, light-gray or brick red in color.

Nodular masses of impure siderite are common in the upper portion of the Woodbridge clay near Sayreville and the South River and when present they aid in its identification. These nodules contain marine fossils thus showing that marine conditions probably prevailed for at least a part of Raritan time. The upper part of the clay also contains lignite and pyrite. Dinosaur footprints have been found in the Wood-

²² Stearns, Norah Dowell, Laboratory tests on physical properties of water heating materials; U. S. Geol. Surv. Water Supply Paper 596-P, 1927, pp. 166-167, Samples 71 and 72.

bridge clay and these, together with the lignite, indicate that a marine environment may not have existed throughout all of Woodbridge time.

Quite apart from its economic importance as a source of clay, this thick and widespread unit in the Raritan formation is of great hydrologic importance because it forms an impervious cover over the prolific Farrington sand. It limits the intake area of that sand to the area of its outcrop and farther down the dip, confines the water in the sand so that it occurs under artesian conditions.

FARRINGTON SAND MEMBER

A report describing the water supplies of the Farrington sand or No. 1 sand of previous reports dealing with the Raritan formation, was published in 1937.²³ The description of the sand and of the water supplies from it in this report are, therefore, somewhat abbreviated and emphasis is placed upon new data collected since the preparation of the earlier report. This sand occurs both north and south of the Raritan River and probably across the Arthur Kill on Staten Island. Not much water is pumped from its intake area, but it is tapped by wells in many places down the dip from the intake area where the water is encountered under artesian pressure.

Geology

The Farrington sand lies beneath the Woodbridge clay. As indicated on figure 6 on page 21, it crops out in a conspicuous band nearly a mile wide along the southeast edge of Farrington Lake where several sand pits give a good opportunity to examine it. A large amount of water enters the sand in this area which makes it very important from a hydrologic standpoint. For the above reasons, this member is called the Farrington sand in this report.

The upper part of the Farrington sand is generally medium to fine-grained. The lower portion, 10 feet to 20 feet thick, is a coarse, arkosic, light-gray or light-yellow sand usually containing a considerable sprinkling of small pebbles. The arkosic material, as seen in outcrop, is always partly kaolinized, the white kernels of the partly decomposed feldspar standing out sharply in contrast with the gray and yellow colors of the sand and gravel. The latter is composed chiefly of well rounded quartz pebbles, but also contains numerous pebbles of flint ranging in diameter from a quarter of an inch to a maximum of two

²³ Parker, G. Henry C., Water Supplies from the No. 1 Sand in the Vicinity of Parlin, New Jersey, Special Report 2.

inches. Occasionally the gravelly beds contain rather numerous small chunks of red or white clay, quite obviously derived from the underlying Raritan fire-clay and evidently redeposited close to their source. Lenses of clay, usually only a few feet thick, also occur within the limits of this member and thin clay seams are fairly common.

As recorded in well logs, the sand is often divided by clay lenses into two or more parts, but since the static levels of the water from all parts of the member are about the same for any one location, the dividing clay beds are evidently of very local extent. The following log was compiled from samples obtained from a test well drilled for the Borough of Sayreville about a mile and a quarter northwest of the Runyon pumping station.

Partial log of test well at Sayreville, New Jersey

Sample depth	Description	Formation
118-120	Clean, fine to coarse-grained, light gray sand with a little lignite and pyrite.	{ Farrington sand member of the Rari- tan formation.
120-137	Clean, coarse-grained sand and small gravel (including unweathered flint). Some grains cemented by pyrite. A little fine-grained sand and some lignite at 132 feet.	
137-163	Light gray clay with a little sand.	
163-180	Coarse gray sand and small pebbles.	
180-198	Coarse, light gray sand and gravel.	

It will be noted that the full thickness of the member is 80 feet. Half a mile southwest at the pumping station of the Borough of South River, the reported thickness in a deep well was only 44 feet; but at the Anheuser-Busch plant half a mile southwest of Old Bridge it is 78 feet 8 inches thick, at the Peter J. Schweitzer Company plant in East Spotswood it is 56 feet thick, at Runyon it is 91 feet thick and near Parlin it ranges from 50 to 104 feet thick. It is known to be continuous to the southwest at least as far as Jamesburg as it was found (83 to 129 feet thick) in the wells at the New Jersey State Home for Boys two and a quarter miles to the east-southeast and in a test borehole 0.85 mile east of Dayton and 3 miles west-northwest of Jamesburg. The Farrington sand dips to the southeast at the rate of about 55 feet per mile.

Northeast of Parlin the member thins, the sand becomes finer grained and sometimes quite clayey, and in South Amboy wells drilled in this horizon have been only moderately successful. In the district between Parlin and Jamesburg, however, the Farrington sand is one of the best aquifers in the State. Wells of large diameter and modern construction have yielded as much as two million gallons daily, and nearly all of them are rated in excess of half a million gallons daily.

The Farrington sand is thin or lacking above the buried trap ridge between the Borough of South River and Perth Amboy as shown in figure 3 on page 17. A great many wells have been drilled in this area, but those over the trap ridge with the exception of a few within a mile or so northeast of the Borough of South River have not been as successful as wells to the northwest or southwest. Hydrologically this is important because the thinning of the Farrington sand on the ridge tends to prevent the movement of salt water from the intake under the Raritan River to the centers of pumpage to the southeast.

Physical Properties

The results of laboratory tests on seven samples of this sand taken at different exposures along its outcrop are given in the table on page 42. The coefficient of permeability of the sand as determined by these tests ranges from 210 to 3,500, and a weighted average would probably be between 1,200 and 1,500. Pumping tests at the Perth Amboy Water Works gave figures for the coefficient of permeability which were in this same order of magnitude. The specific yield of the sand, as indicated by the average difference between its porosity and its moisture equivalent, is about 32 percent. With a specific yield of 32 percent, a block of the Farrington sand one foot thick and one square mile in area, would be capable of storing about 67 million gallons of available water.

Quality of Water

The uncontaminated water from the Farrington sand is exceptionally good for most purposes. Its quality varies slightly from place to place, but the total solids are usually less than 40 parts per million. The hardness is usually less than 15 parts per million. The only feature of this water that is sometimes objectionable is its iron content, which ranges from 2 to 6 parts per million in some localities.

The chloride content of the water from the Farrington sand is normally only 2 to 4 parts per million, but the sand has been contaminated by the intrusion of sea water in several places in the county.

Where this has occurred, the water has become highly mineralized and unfit for any ordinary use except cooling. Samples collected from wells in the contaminated areas have been found to contain from 10 to 7,675 parts per million of chloride. The other minerals contained in sea water, notably the hardness-forming minerals, calcium and magnesium, have, of course, increased in proportion to the increase in chlorides so that the water rapidly becomes less desirable, even before the concentration of salts renders it useless. The degree and extent of the contamination has tended to increase with continued pumping. The area, extent, and probable significance of the very serious problem created by the salt-water intrusion into this sand is discussed on pages 115 to 139.

Development and Pumpage

The first water supply developed from the Farrington sand south of the Raritan River was at the Perth Amboy Water Works at Runyon where a well tapping it was drilled in 1897. About the same time industrial wells drawing from this sand were drilled in the city of Perth Amboy. For several years after 1897 the Farrington sand at Runyon was the principal source of water supply for the city of Perth Amboy. Later this supply was augmented by pumping from the Old Bridge sand, and water from both sands was used. In Middlesex County the water from the Farrington sand is now used almost exclusively for industrial purposes.

Before the beginning of the World War of 1914, only a few industrial plants in Perth Amboy, South Amboy, and Sayreville were using water from the Farrington sand. The total pumpage from the sand within the county probably did not exceed one or two million gallons daily at that time. The favorable location of the region for export trade produced a sudden increase in industrial activity during the war and a corresponding increase in the use of water from the Farrington sand. Unfortunately there are practically no records of pumpage during these years, but from the information available about the capacity of the wells then in use it seems probable that the total rate of pumpage from the sand within the county did not exceed 7 million gallons daily.

Many of the industrial plants established in this area during the war were adapted to peace-time operations and continued or increased their use of water. New industries were attracted to the area and the pumpage increased still more. A table showing withdrawals from the Farrington sand for the years 1929 through 1935 was included in the

earlier report on this sand.²¹ This table has been revised and extended through 1942 and is given as table 8 below. It covers the period 1929 through 1942, and gives separately the pumpage from the sand by the Perth Amboy Water Works and by the wells of the Duhermal companies, as well as a summary of other pumpage both north and south of the Raritan River.

TABLE 8.—QUANTITY OF WATER PUMPED FROM THE FARRINGTON SAND MEMBER OF THE RARITAN FORMATION IN MIDDLESEX COUNTY, NEW JERSEY, 1929-1942

Year	North of Raritan River	Duhermal Companies	Perth Amboy Water Dept.	Other Pumpage South of Raritan	Total
<i>In thousands of gallons daily</i>					
1929	2,080	6,202	92	203	8,577
1930	2,970	5,994	877	309	9,120
1931	1,583	5,053	1,173	342	8,151
1932	1,210	4,352	1,198	398	7,158
1933	1,210	5,542	187	377	7,227
1934	1,215	6,570	135	369	8,389
1935	1,231	8,129	585	407	10,452
1936	1,879	9,094	655	408	12,036
1937	2,006	8,434	650	404	11,554
1938	1,874	5,495	0	408	7,777
1939	1,895	6,358	546	424	9,223
1940	1,975	4,785	301	402	7,463
1941	1,922	4,828	772	996	8,588
1942	1,875	4,015	620	556	7,066

The pumpage from the Farrington sand reached a peak in 1936 when it amounted to slightly over 12 million gallons a day. Approximately 9 million gallons a day of this amount was pumped by the industries in Sayreville Township. Intrusion of salt water into this sand at the Washington Canal caused the development of the Duhermal well field which derives its supply from the Old Bridge sand and made possible a substantial reduction in the pumpage from the Farrington sand by these industries. In 1942 the pumpage was only 4 million gallons a day, a drop of 5 million gallons a day from 1936. The decrease would probably have been even greater had it not been for the increased industrial activity due to the present war.

Pumpage from the Farrington sand by the Perth Amboy Water Department at Runyon during the period 1929-1942, inclusive, has varied from an average rate of 92,000 gallons a day in 1929 to a maximum rate of 1,198,000 gallons a day in 1932. Only one large capacity well tapping the Farrington sand is used. It is now pumped only to supplement the supply from the wells tapping the Old Bridge sand when the yield of those wells is low due to drought or when the demand for water is exceptionally great.

²¹ Parkdale, H. C., Op. Cit., Special Report 7, p. 14.

Consumption of water from the Farrington sand north of the Raritan River has varied between 1,200,000 gallons a day and 2,100,000 gallons a day since 1929. This water has been used entirely by industries in Woodbridge and Raritan Townships and in the City of Perth Amboy. Until recently a great deal of the pumpage in this area was concentrated in and near Perth Amboy. Because of contamination of the sand by salt water, however, most of the industries within the city now obtain water from the Perth Amboy Water Department. The total pumpage from the Farrington sand north of the Raritan River has not varied greatly, however, because increases in Woodbridge and Raritan Townships have offset the reductions in Perth Amboy.

Factors Affecting Safe Yield

In general, there are three factors that may limit the safe yield of an artesian aquifer such as the Farrington sand: its available recharge, its capacity to transmit water from the intake area to the well fields, and the possibility that some form of contamination may be induced or accelerated by the pumping. The true safe yield of the sand is that rate of pumping which does not exceed any of these three factors. Whichever factor permits the smallest quantity of water to be removed from the sand is the limiting factor and determines the safe yield.

Available Recharge

The recharge in the intake area of the Farrington sand was estimated in the previous report to be about 950,000 gallons daily per square mile, or 20 inches of the water from precipitation each year. The intake area of the sand as far as it has been defined is about 17 square miles, as is shown in figure 6 on page 21, and the recharge in this area is accordingly estimated to be about 16 million gallons daily. The sand is separated into two parts by the estuary of the Raritan River and by the underlying trap ridge. Recharge occurring north of the Raritan River is believed not to be available to wells south of the river and vice versa. The intake area north of the river is approximately 6.8 square miles, and its recharge is estimated to be about 6.5 million gallons daily. The intake area south of the river, so far as it has been defined, is about 10.2 square miles, and its recharge is estimated to be about 9.7 million gallons daily. The area at its southeastern end shown by shading in figure 6, is not very well defined, because of the depth of the overlying Quaternary deposits. The sand probably extends still farther south, because it is believed to have been encountered in the

(2)

deep well of the Cranbury Water Company. Any additional intake area in this direction, however, is so far from the present centers of pumping that it would probably not supply any appreciable amount of water to them.

Artificial Recharge. The natural intake capacity of the Farrington sand could, no doubt, be increased by artificial recharge. However, there has as yet been no attempt to recharge this sand artificially. The easiest and most obvious method of inducing artificial recharge would be the location of ponds on some of the smaller streams that cross its intake area, both north and south of the Raritan River.

Another possible means of recharging the sand would be to introduce water into it through wells. This method is expensive, however, and the techniques involved have not been developed to an extent that makes it thoroughly reliable. In order to successfully recharge the sand through wells, the water used should be absolutely free from any material that would be deposited in the sand outside the recharge well and thus reduce its capacity. If surface water were used for this purpose, it should be filtered and preferably sterilized as well to prevent the clogging of the sand by solid particles or by the growth of micro-organisms. Recharge wells may, of course, be redeveloped from time to time to restore their capacity, but it is difficult to maintain the original capacity of such a well even with the best of care, especially if the recharge water is not carefully prepared. Recharge of the Farrington sand through wells might be considered in the vicinity of Parlin and South Amboy, in order to retard the advance of salt water and possibly force it out of the sand. Elsewhere in the county it is not believed to be economically justifiable.

If the fullest possible use were made of all opportunities for artificially recharging the Farrington sand, it might be possible to increase its total recharge by several million gallons daily. It must be borne in mind, however, that the surface water diverted into this sand would not be available for use elsewhere. For example, the principal streams south of the Raritan River that flow across its intake area discharge into Lawrence Brook, which is being used by the city of New Brunswick as a source of public water supply.

Capacity to Transmit Water

The capacity of the Farrington sand to transmit water from the intake areas to the various wells as indicated by the coefficient of permeability of the samples analyzed in the laboratory is relatively high. It

appears improbable that this factor would limit the safe yield of the sand. For the purposes of estimating, the average coefficient of permeability may be assumed to be 1,350, and 80 feet may be used as the average thickness of the sand. In June, 1936, when the rate of pumping from the Farrington sand in the Parlin area was near its maximum (9.4 million gallons a day), water levels in the vicinity of Parlin, as determined from the duPont and Hercules observation wells averaged about 57 feet below sea level. At the same time the water level in the intake area of the sand, as determined from the Fischer well, was about 60 feet above sea level, making a total difference in head of 117 feet between the intake area and the area of pumping. The average distance from the intake area to the approximate center of pumping at Parlin is about 5 miles. The average gradient was, therefore, about 23.4 feet per mile. With this hydraulic gradient the sand would transmit $1,350 \times 80 \times 23.4$ or about 2.5 million gallons a day for each mile of its width. South of the Raritan River the width of the aquifer is at least 10 miles so that it might transmit 25 million gallons daily under the assumed conditions. In the immediate vicinity of the individual pumped wells, where the gradients are much steeper, the rate of flow was, of course, much greater.

The capacity of the sand to transmit water may also be judged by a study of the effect of pumping different quantities of water upon the head of the water in the sand at various points. The relation between pumpage from the Farrington sand and the water levels in various observation wells tapping this sand is shown on figure 11 on page 112. The location of all the wells on this diagram except the Fischer well are shown on figure 12. The location of the Fischer well is shown on figure 2, on page 6, because it is outside the limits of figure 12.

This diagram shows the pumpage by months and the fluctuations of water level in several observation wells tapping this sand. The pumpage is subdivided to show the amount taken from the wells of the Duhermal companies and the amount taken from the well at the Perth Amboy Water Works. Water level fluctuations are shown in five wells. Two of these are at Parlin: an observation well at the duPont plant, and an observation well at the plant of the Hercules Powder Company. The other three are an old deep well at Runyon, a test well at the site of the proposed Sayreville Water Works, and the Fischer well, which is an observation well in the intake area of the sand several miles from any center of pumping.




FIGURE 11.—Diagram showing the relation between water levels and pumpage in the Farrington sand member of the Raritan formation, 1929 to 1942. For locations of wells see Figs. 2 and 12.




FIGURE 12.—Map of the area between Perth Amboy and Spotswood showing the location of wells tapping the Farrington sand, the intake area of this sand, and the approximate extent of the salt-water intrusion into this sand.

KEY TO WELL NUMBERS

- | | |
|--|--|
| 1. Perth Amboy Water Department | 17. Carborundum Company (2 wells) |
| 2. Hercules Powder Company (5 wells) | 18. Raritan Copper Works (2 wells) |
| 3. E. I. duPont de Nemours & Company (6 wells) | 19. Hoechst & Hasselacher Chemical Company |
| 4. National Lead Company (3 wells) | 20. General Cable Company |
| 5. Jersey Central Power & Light Company (2 wells) | 21. Puritan Dairy |
| 6. South Amboy Water Department (3 wells not used) | 22. Hona Pule Mills |
| 7. South River Water Department (2 wells) | 23. National Fireproofing Company |
| 8. Sayreville Borough (5 test wells) | 24. Furman observation well |
| 9. Anheuser-Busch Company | 25 to 27 (inclusive) and 19. Observation wells |
| | 50. Clover Green Dairies |
| | 51. Observation well |

It will be noted that the pumpage from the wells of the three Duhermal companies accounts for the major part of the total pumpage. In recent years the well at the Perth Amboy Water Works has been operated only when it has not been possible to obtain enough water from the Old Bridge sand. In general, the fluctuations of the water level in the various wells, except the Fischer well, correspond with the total rate of pumping. The pumpage north of the Raritan River is fairly constant and does not affect appreciably the trend of the line for total pumpage. The observation wells are all south of the river.

The fluctuations of the Fischer well are believed to be due entirely to variations in precipitation and to other natural causes. It will be noted that the Runyon well fluctuates more widely in response to the pumpage at the Perth Amboy Water Works than do the other wells, and that the Hercules and duPont wells are more responsive to changes in the Duhermal pumpage than are the other wells. The pumpage was higher and the water levels were lower during 1935, 1936 and 1937 than at any other time in the period shown. This is due partly to increased demand from most of the wells tapping the sand, and partly to the fact that the wells at the plant of the National Lead Company were put into operation during 1935. The decrease in pumpage in 1938 was due to conservation measures at the plants of the three Duhermal companies, and to the fact that the summer of 1938 was relatively wet and it was not necessary to operate the deep well at the Perth Amboy Water Works. In 1939 the new Duhermal supply south of Old Bridge was put into operation and the decreased pumpage since that time has been due largely to the fact that a considerable portion of the water used by the Duhermal companies has been taken from this source.

In general, the effect on the water levels in the wells of a given rate of pumpage was about the same both before and after the three years of excessively high pumping. There have, of course, been some changes due to the fact that the construction of the National Lead Company wells in 1935 and the use of the Schweitzer well in 1941 and 1942 have changed the distribution of the pumpage in the area somewhat, but on the whole comparable rates of pumpage in the early 1930's and in the early 1940's have produced comparable water levels in the wells. There is no indication from this diagram that the rates at which the water has been pumped from the Farrington sand have produced any excessive drawdowns in the observation wells. If the rate of pumping had been greater than the capacity of the sand to transmit water from the intake area, a progressive lowering of the water level would have occurred. Even in 1935, 1936 and 1937, when the rate of pumping was about 13 million gallons daily for several months and approached

14 million gallons daily for a few months, the lowering of the water level does not appear to have been out of proportion to the rate of pumping. It may be concluded, therefore, from the study of this diagram, that the capacity of the Farrington sand to transmit water is greater than any rate at which it has been pumped up to the present time.

Salt-Water Intrusion

The factor that appears most likely to limit the safe yield of the Farrington sand, at least in the area within a few miles of the Raritan River, the South River, and the Arthur Kill, appears to be the danger of salt-water intrusion. In fact salt water has already entered the sand both north and south of the Raritan River and advanced for some distance. A considerable number of wells have been more or less severely contaminated.

The areas in which salt-water contamination of the Farrington sand has occurred, a part of the intake area of the sand, and the locations of most of the wells tapping it within the county are shown on figure 12 on page 113. An attempt has been made to indicate the degree of contamination by means of contours enclosing areas in which the salinity of the water is believed to be 10 parts per million or more, and 1,000 parts per million or more. Solid contours are used to indicate fairly well-defined areas of contamination while those less well-defined are indicated by dashed contours. It will be noted that the two largest areas in which contamination has occurred are in the city of Perth Amboy and in the area between the Washington Canal and the well fields at Parlin. Apparently, however, tongues of salt water are reaching out toward the active wells from a number of other points along the tidal streams.

North of Raritan River. A majority of the wells in Perth Amboy and along the north shore of the Raritan River have been contaminated by salt water, apparently drawn in from the river or from the Arthur Kill. In this area it appears probable that most of the wells within a mile or two of these bodies of salt water will ultimately be contaminated by salt water. They may have to be abandoned except as sources of water for cooling or similar purposes.

In most places north of the Raritan River the sand is not as thick as it is south of the river. Nevertheless, very substantial quantities of water have been withdrawn from it in the past, especially in the city of Perth Amboy. Some wells in the city have already been abandoned because of salt water contamination and it is probable that others may soon have to be abandoned. The chloride contents of the water from most of these wells are given in table 9 on page 116. Samples have

been collected from some of the wells in three different years and the table shows the changes that have occurred from time to time. Apparently the only hope for the continued withdrawal of any substantial quantity of fresh water from the Farrington sand north of the Raritan River lies in the construction of relatively shallow wells near the intake area and as far as possible from the streams that contain salt water.

South of Raritan River. As indicated on figure 12 on page 113, salt water is believed to be advancing into the Farrington sand in several localities south of the Raritan River. The largest of these is an area lying between the Washington Canal, the South River, and the well fields at Parlin. This area has been studied in considerable detail, and the intensity and extent of the contamination is fairly well known. Another area that is fairly well delimited is just north of South Amboy. Three other probable areas of salt-water contamination extend from points along the Raritan River toward the well fields at Parlin and South Amboy. These areas have not been defined with the same degree of certainty as the other two, but the available records suggest they may exist.

The Farrington sand south of the Raritan River is protected from the salt water in the river and in the material beneath it by the buried trap ridge that underlies both the river and a strip of land south of it. This buried ridge is a part of the diabase dike that forms the Palisades along the Hudson River, and rises to the surface again to the southwest. In most of Middlesex County it is buried beneath the younger Cretaceous deposits. In pre-Cretaceous times the diabase dike stood as a ridge on the land surface. In the area between Perth Amboy and the town of South River it stood so high that the Farrington sand was not deposited on top of it, except perhaps in some gaps or low places. Numerous test wells have been drilled through the materials overlying the buried ridge and the great majority of them have gone directly from the Woodbridge clay, which overlies the Farrington sand, into the diabase. Unfortunately, however, the ridge was not high enough to furnish much, if any, protection to the Farrington sand in the vicinity of the Washington Canal and the salt water has easy access to the sand in this area. It seems probable, however, that in the other areas of salt-water contamination referred to above, the salt water is advancing across the trap ridge through relatively shallow gaps that do not permit a large flow.

The investigations that preceded the earlier report on the Farrington sand²⁵ in this area brought out the fact that it is possible for salt water

²⁵ Harkadale, H. C., Op. Cit., Special Report 7.

to enter the sand in the vicinity of the Washington Canal and probably in the meanders of the South River that extend near the intake area of the sand. It was pointed out that the deepening of the Washington Canal in 1929 provided a ready means of access, whereby the salt water could enter the Farrington sand, and that the heavy rate of pumping at Parlin and elsewhere in the area might have reduced the fresh water head near the canal to such an extent that the intrusion of salt water was possible.

In 1937 and 1938 a series of test wells (Nos. 27, 28, 29, 30, 32, and 33 on figure 12) were drilled, and the analysis of water from them showed that salt water had advanced into the sand in the direction of Parlin to an alarming extent. Chlorides ranging as high as 6,581 parts per million were found in samples from test well 29, and as high as 2,670 in samples from test well 27. Chlorides of almost 300 parts per million were found in samples from test well 32, and test well 33 yielded water containing about 20 parts per million of chloride. All the wells at Parlin were then yielding water containing only 2 to 4 parts per million. The test wells were sampled periodically in order to ascertain what fluctuations of the chloride content might occur and how fast the salt water might be advancing toward the well fields. The chloride contents of these samples are given in table 10 on page 124. The conditions in this area were discussed in a paper published in 1940.²⁶ They are discussed herein in somewhat more detail in the light of more recent information.

Salinity of Surface Waters

It is probable that the water in the Raritan Bay is usually only a little less salt than normal sea water. Samples of water from the Raritan River estuary opposite Perth Amboy, collected by the New Jersey State Board of Health, were found to contain as much as 19,000 parts per million of chlorides. Up the Raritan River and its branches the chlorides decrease as more and more fresh water is mixed with the water from the bay. In times of flood the larger volume of fresh water entering the estuary of the river forces the salt water out toward the bay, but the continual movement of the tides brings the salt water back into the tidal reaches of these streams as soon as the floods subside. In times of very low flow the salt water probably advances almost to the head of tide in the Raritan River at New Brunswick and, as already noted, appreciably increased chlorides have been

²⁶ Harkadale, H. C., The Contamination of Ground Water by Salt Water near Parlin, New Jersey. Trans. Am. Geophysical Union, 1940.

REFERENCE NO. 12

11-18-76
Trube

MIDDLESEX COUNTY 208 AREA-WIDE
WASTE TREATMENT MANAGEMENT PLANNING
TASK 8 - GROUND-WATER ANALYSIS

- A. DESCRIPTION OF GROUND-WATER SYSTEM
- B. GROUND-WATER POLLUTION SOURCES

prepared by

Geraghty & Miller, Inc.
Consulting Ground-Water Geologists and Hydrologists
44 Sintsink Drive East
Port Washington, New York 11050

November 1976

This report was prepared under a subcontract of the Middlesex 208 Joint Venture in cooperation with the Middlesex County Planning Board. The work was supported by funds provided to the Middlesex County Board of Chosen Freeholders by the U. S. Environmental Protection Agency, Region II, under EPA Grant No. P002102-01-0 as authorized by the Federal Water Pollution Control Act Amendments of 1972, PL 92-500.

HYDROGEOLOGIC FRAMEWORK

The study region is underlain by consolidated and unconsolidated rocks ranging in age from Precambrian to Recent. The northwestern part of the region covering about 160 square miles falls within the Triassic Lowland physiographic region and is underlain by sedimentary and igneous rocks. To the southeast lies the Coastal Plain, a region extending over some 220 square miles. The Coastal Plain is underlain by a thick wedge of sands, gravels, clays, and silts of Cretaceous age. These deposits were laid down by rivers in a deltaic environment and generally thicken in a downdip direction. Younger sediments overlie older sediments in a southeastward direction. The stratigraphic sequence of the various rock units together with their water-bearing properties is shown on Table 1.

Major ground-water reservoirs which are also the most heavily pumped are Triassic sandstones and shales of the Brunswick Formation and the Farrington and Old Bridge Sands of Cretaceous age. Aquifers of lesser importance are the Sayreville Sand, the Englishtown Sand, and the Mount Laurel and Wenonah Sands, all of Cretaceous age and the Pensauken Formation and glacial drift deposits of Pleistocene age.

The Triassic bedrock north of the Raritan River is overlain by sediments of glacial age. East of Plainfield, these deposits consist mostly of glacial till (unsorted sand, gravel, boulders and clay), but to the west and south, permeable glacial outwash deposits are present. The aquifers extend beyond the confines of the study region; the Triassic aquifer northward into Union County and westward across the Millstone River into Somerset County, and the

Table 1 - (Continued)

System	Unit	Lithologic description	Thickness (feet)	Water-bearing characteristics
Cretaceous	Magothy Formation	Fine lignitic sand and black clay	90 - 130	Not important as aquifer. Well yields are low but sufficient for domestic purposes.
	Amboy Stoneware Clay	Gray to black clay with carbonaceous material	0 - 30	Considered to be lower facies of Magothy Formation. Confining bed.
	Old Bridge Sand	Fine- to coarse-grained white to yellow sand	20 - 110	Major aquifer tapped by many wells. Median specific capacity is 20 gpm. Transmissivity range 140,000 to 230,000 gpd/ft. Artificially recharged in places. Well yields 200 to 1,000 gpm.
	South Amboy Fire Clay	Varicolored clay	0 - 35	Confining bed.
	Sayreville Sand	Fine, white micaceous sand	0 - 40	Not continuous. Unimportant as aquifer.
	Woodbridge Clay	Gray clay and clayey sand	50 - 100	Major confining bed overlying Farrington Sand.
	Farrington Sand	Gray to yellow fine- to medium-grained sand. Contains some clay layers.	30 - 150	Major aquifer tapped by many wells. Median specific capacity is 29 gpm. Transmissivity range 50,000 to 150,000 gpd/ft. Well yields 500 to 2,000 gpm.
	Raritan Fire Clay	Varicolored basal clay	0 - 90	Confining bed.
Triassic	Brunswick Formation	Red shale interbedded with siltstone and sandstone	5,000+	Major aquifer north of Raritan River. Specific capacity is 0.1 to 25 gpm. Transmissivity range 1,000 to 4,000 gpd/ft. Well yields 50 to 700 gpm.
	Lockatong Formation	Hard shale and argillite	1,000+	
	Stockton Formation	Conglomerate and sandstone	1,000+	

Newark Group

} Present only in small areas. Of little importance as aquifers.

Coastal Plain aquifers start at the Fall Line and probably continue southward into Mercer and Monmouth Counties. Tracing of the Old Bridge and Farrington Sands beyond the Middlesex County borders is difficult due to complex stratigraphic conditions.

Ground water in the bedrock aquifer is found in fractures and other openings, in contrast to the unconsolidated Coastal Plain deposits where ground water fills the voids between individual grains of the sediment. Both water-table and confined or artesian aquifers are present. The Triassic sandstone and shale and both the Farrington and Old Bridge Sands are under water-table conditions where exposed in the outcrop area. Where overlain by other sediments or zones of low permeability, these aquifers become confined.

Water-table aquifers are recharged by precipitation and sometimes by fluids disposed of in the subsurface, such as septic tank or cesspool effluent. Ordinarily, surface-water bodies act as discharge areas for water-table aquifers; however, in areas of heavy pumping where ground-water levels have fallen below river, stream, or lake levels, the water-table aquifers might receive recharge through surface-water infiltration if geologic conditions are favorable.

The artesian aquifers receive recharge from several sources, namely precipitation on the outcrop area, vertical leakage from confining beds above or below the aquifer, and infiltration of water from rivers or lakes in contact with the aquifer. The impact of man's activities has led to water-level declines and changes in natural head relationships as will be discussed shortly.

On the Coastal Plain, the extensively distributed and thick clay beds such as the Wood-

bridge, Merchantville and Woodbury act as confining beds and to a large degree prevent downward or upward movement of water in the hydrologic section. Under pre-pumping conditions, the aquifers were brimful with water, discharging excess water to streams that crossed the outcrop area or causing ground-water flow to move downdip through the confined aquifer to discharge points along the Atlantic Ocean. For example, heads in the Farrington Sand at the beginning of exploitation in 1897 were about 30 to 40 feet above land surface in the Perth Amboy well field and the wells flowed. Increased pumpage over the years decreased the head and the present potentiometric surface in the region is about 70 feet below sea level, indicating a historic head decline of roughly 100 feet. No historical decline of the water table in the Old Bridge Sand or Triassic rocks is known in spite of large seasonal water-level variations.

Historical trends of water levels in the Farrington Sand are shown on Figures 1 and 2. These records from U. S. Geological Survey observation wells depict downward trends in the South River, Perth Amboy and Duhernal Sayreville (Dusay) observation wells located in the pumping zones. The Fisher observation well (Figure 1) shows a stable water-level trend; it is located in the recharge area removed from the influence of pumping (locations of all wells are shown on Plate 14). Figures 3 and 4 show the historical record of water-level fluctuation in seven observation wells tapping the Old Bridge Sand (for locations of wells see Plate 13). As shown, water levels in the Duhernal wells declined to below sea level during the drought period 1963-65 but have now recovered to pre-drought elevations. No long-term dewatering of the Old Bridge aquifer is evident.




Figure 1 - Yearly high and low water levels in U. S. Geological Survey observation wells tapping the Farrington Sand.

SALT-WATER INTRUSION

Salt-water intrusion in the Middlesex 208 region is limited to the Farrington Sand in the vicinity of the Raritan and South Rivers; no salt-water intrusion has occurred in the Old Bridge Sand. The Farrington Sand occurs stratigraphically between the Raritan Fire Clay and the Woodbridge Clay (see Plate 3 - Cross Section II) and outcrops in a northeast-trending belt both north and south of the Raritan River. Although the outcrop area of this formation is divided by the Raritan River, the Farrington does occur beneath it. A buried northeast trending Triassic age diabase ridge, 4,000 to 6,000 feet wide, underlies the Farrington Sand in the area of the Raritan River between Sayreville and Perth Amboy (see Plate 8 - Contours on Upper Surface of Bedrock Beneath Coastal Plain). The surface of this buried ridge is highly irregular, but its general topographic expression in upper Cretaceous time had a strong effect on Farrington sedimentation. Many test wells drilled through the materials overlying the ridge have gone directly from the Woodbridge Clay into the diabase and it is apparent that in many places between Sayreville and Perth Amboy, the Farrington Sand was either not deposited on top of this diabase ridge, or else was laid down and subsequently eroded. The sand was deposited in enough places however, so that salt water from the Raritan and South Rivers and the Washington Canal can move across the top of the ridge and into the Farrington Sand south of the Raritan River.

In Special Report 7 ³⁾, it was pointed out that deepening of the Washington Canal in 1929 provided easy access for salt water to enter the Farrington Sand. In addition, it was also noted that heavy pumpage centered in the Parlin area and elsewhere might

intrusion into the Farrington Sand from both the Raritan River and Arthur Kill. Because of the thinness of the aquifer here and the natural low head, continued pumping in close proximity to these two surface-water bodies will cause additional salt-water intrusion.

No widespread salt-water intrusion problems exist in the Old Bridge Sand. The main reason for this is that while the Old Bridge aquifer is heavily pumped (30 mgd in 1974), most of this pumpage is in the outcrop area where the aquifer is recharged, thereby keeping the water level in the Old Bridge Sand generally above sea level. Also, artificial recharge ponds at the Duhernal Water System and Sayreville and Perth Amboy Water Departments increase the effective ground-water recharge in this area. By maintaining the head above sea level, intrusion of salt water from the surrounding saline and brackish surface-water bodies is prevented.

Furthermore the Old Bridge Sand, unlike the Farrington which underlies the Raritan River, Washington Canal and South River, is exposed to saline surface-water bodies at only two localities. In the general area of the South Amboy well field, the Old Bridge Sand outcrops adjacent to the Raritan Bay and probably underlies it for some distance off shore. Also, downstream of Duhernal Dam the Old Bridge outcrop area is crossed by the South River and two of its tributaries, Deep Run and Tennent Brook. The South River, Deep Run, and Tennent Brook are affected by tides in Raritan Bay. The chloride content of these three streams varies depending on the tidal stage and the ground- and surface-water flow entering the stream, but appreciably increased chloride concentrations have been found in the South River upstream almost as far as Duhernal Dam.

ent. On Triassic areas, infiltration is low and surface runoff quite high, whereas the opposite is true for the sands and gravels of the Coastal Plain. The Coastal Plain area north of the Raritan River was excluded from the water balance as the aquifers there are of little or no importance. In preparing the two water budgets, a number of assumptions were made. Underflow of ground water into the water budget regions was assumed to be equal to underflow out of the region, thus cancelling this component. Also, the hydrologic systems were considered to be in long-term dynamic equilibrium with negligible changes in ground-water storage.

Water-budget analyses of both the Coastal Plain and the Triassic Lowland are given in Table 6. In the overall Coastal Plain water budget, the water input is 400 mgd based on 44 inches of precipitation per year, which is equivalent to roughly 2 mgd per square mile. Half of this quantity, 22 inches or 200 mgd, is lost to the atmosphere by evapotranspiration, and 20 inches or 180 mgd runs off in streams. Evapotranspiration of shallow ground water in swampy areas covering 15 square miles equals 15 mgd and spring flow to salt-water bodies is estimated at 5 mgd.

The ground-water budget for the Coastal Plain shows ground-water recharge of about 140 mgd, which is derived through subtracting direct or storm runoff (estimated at 60 mgd or 15 percent of annual precipitation) and evapotranspiration from precipitation (400 mgd). Outflow of ground-water discharge to streams equals about 13 inches per year or 120 mgd. Evapotranspiration losses of shallow ground water and spring flow total 20 mgd.

In the Triassic Lowland, the overall water budget shows precipitation equaling 340 mgd, based on 44 inches or about 2 mgd per square mile, half of which is lost to evapotranspiration

Withdrawing large quantities of water in excess of natural replenishment, however, produces a decline in water levels as water is taken from storage, which in turn may lead to salt-water intrusion in coastal zones. As the eastern portion of the Farrington Sand is experiencing large head declines and locally, salt-water intrusion, removing additional ground water from storage within the aquifer in that area would not be recommended. Instead a more widely distributed pumping network might be required to eliminate excessive drawdowns in the coastal zone and to utilize the large ground-water reserves. More detailed recommendations for ground-water management techniques in both the Coastal Plain and Triassic Lowland are given in a later section of the report.

EFFECT OF THE PROPOSED CRAB ISLAND RESERVOIR ON GROUND-WATER SUPPLIES OF THE FARRINGTON AND OLD BRIDGE SANDS

A tidal dam has been proposed on the Raritan River downstream from Crab Island. The proposed reservoir surface would be 7.5 feet above mean sea level. The purpose of the reservoir is for flood protection, water supply, and recreation. The reservoir would prevent salt water from moving with the tides of the Raritan River, Washington Canal, and South River to recharge areas of the aquifers. It would raise fresh-water heads in the aquifers, thereby lowering the potential for salt-water intrusion. It is hoped that the reservoir would act to recharge water to the aquifers in response to ground-water pumpage. Water from the reservoir could also be used for artificial recharge of the aquifers.

The effect of the proposed reservoir on ground-water supplies in both the Farrington and Old Bridge Sands was studied by Remson and Fungaroli ⁷⁾ of the U.S. Geological Survey

REFERENCE NO. 13

***Geological Investigations of the
Coastal Plain of Southern New Jersey***

Part 2:

A. Hydrogeology and the Coastal Plain

edited by Claude M. Epstein

B. Paleontologic Investigations

edited by Raymond W. Talkington

***2nd Annual Meeting of the
Geological Association of New Jersey***

*sponsored by
Geology Program
Stockton State College
Pomona, New Jersey*

Pomona



sand that generally strike northeast-southwest and thicken as a wedge southeasterly from a feathered edge at the outcrop to more than 1,000 feet in southeastern Monmouth County (Zapecza, 1984).

The Farrington aquifer, which consists of the Farrington Sand Member of the Raritan Formation, overlies a crystalline rock basement in the western part of the study area and the Raritan Fire Clay down dip of the outcrop area. In areas near its outcrop, the Farrington Sand Member also overlies the diabase Palisades sill (figures 1 and 2). The member consists of sands and gravels with clay lenses. The Farrington aquifer thickens from 50 feet in and near its outcrop to about 100 to 125 feet in the southeastern part of the study area (Zapecza, 1984). In the study area, the aquifer is overlain by the Woodbridge Clay Member of the Raritan Formation. Locally, this micaceous silt and clay confining bed includes sand and clay lenses of the Sayreville Sand and the South Amboy Fire Clay Members of the Raritan Formation (Farlekas, 1979). The confining-bed thickness increases from less than 50 feet in the outcrop area to more than 150 feet farther down dip in this area (Zapecza, 1984).

The Old Bridge aquifer, generally, is equivalent to the Old Bridge Sand Member, the basal unit of the Magothy Formation. Locally, where the South Amboy Fire Clay member of the Raritan Formation is thin or missing, the Old Bridge aquifer may include the Sayreville Sand Member as shown in figure 2 (Farlekas, 1979). The aquifer is composed of medium sands locally interbedded with clayey silts (Farlekas, 1979). From the outcrop, the unit thickens to about 125 feet down dip at a depth of 700 to 800 feet below sea level in the southeastern part of the study area. Localized interbedded sand, silt, and clay sequences pinch out and interfinger with the overlying confining bed down dip (Zapecza, 1984).

The Merchantville-Woodbury confining bed overlies the PRMA system throughout the study area. Zapecza (1984) described it as the most extensive confining bed in the New Jersey Coastal Plain. The confining bed thickness ranges from about 100 feet in the study area to approximately 300 to 350 feet toward the east (Zapecza, 1984).

Detailed discussions of geologic characteristics and stratigraphy of the Raritan and Magothy Formations and overlying Coastal Plain deposits are in Barksdale and others (1943), Gill and Farlekas (1976), and Zapecza (1984).

PREVIOUS INVESTIGATIONS IN THE VICINITY OF SAYREVILLE,
AND SOUTH RIVER BOROUGHES, AND THE
CITY OF SOUTH AMBOY

Unpublished test-borehole data resulting from commercial development has provided most of the hydrogeologic information in the Boroughs of Sayreville, and South River and the city of South Amboy for this investigation. The earliest information comes from the pits that were dug into the clay beds near the South River and Raritan River. Meredith Johnson compiled U.S. Army Corps of Engineers (USACE) and New Jersey Department of Transportation test borings in the South and Raritan Rivers (M. Johnson, unpublished worksheets on file at NJDEP, 1925-40). Johnson's worksheets show that the Farrington aquifer pinches out against the Palisades diabase sill in some locations near the estuary waterways.

Barksdale and others (1943), reported on the regional hydrogeology and ground-water supply. His report included an areal delineation of the extent of the Palisades sill. Subsequent analysis on the extent and the depth of the sill from borings and well records was done by Steven Whitney of the NJGS (Whitney, S., New Jersey Geological Survey, written commun., 1969). An aeromagnetic survey of this area by the U.S. Geological Survey (1979) may indicate that the sill is present further to the west than previously determined by either Whitney or Barksdale.

Two projects proposed by the USACE in the 1960's concerned the hydrogeology of this area. The first was a proposal to dam the South River and form a freshwater reservoir (U.S. Army Corps of Engineers, 1962). Appel (1962) prepared a preliminary report for this project that included data on the permeability properties and distribution of the alluvium along the South and Raritan Rivers. Another study examined the potential effects of continued dredging of the rivers by the USACE (Appel, U.S. Geological Survey, written commun., 1962). This study shows the extent and location of the Farrington aquifer, and the confining alluvium above and the confining Palisades sill below the aquifer. The study also shows that the areal distribution of the chloride migration pattern is a function of both the sediment permeability beneath the estuary waterways and the irregular aquifer thickness. Table 3 summarizes the hydrogeologic data for this area.

REFERENCE NO. 14

WELL RECORD

STOLT TERMINALS INC.

920 STATE ST.

1. OWNER STOLT TERMINALS INC. ADDRESS 920 STATE ST.
Owner's Well No. _____
2. LOCATION Lot: 1A Block: 425 SURFACE ELEVATION _____ Feet
Municipality: Perth Amboy City
3. DATE COMPLETED 8/20/85 DRILLER Somerville Well Drilling Co.
4. DIAMETER: Top 10 inches Bottom 6 inches TOTAL DEPTH 580 Feet
5. CASING: Type drive Diameter 6 inches Length 160 Feet
6. SCREEN: Type _____ Size of Opening _____ Diameter _____ inches Length _____ Feet
Range in Depth { Top _____ Feet
Bottom _____ Feet Geologic Formation _____
Tail Piece: Diameter _____ inches Length _____ Feet
7. WELL FLOWS NATURALLY _____ Gallons per minute at _____ Feet above surface
Water rises to _____ Feet above surface
8. RECORD OF TEST: Date 8/20/85 Yield 45 Gallons per minute
Static water level before pumping 50 Feet below surface
Pumping level 460 feet below surface after R hours pumping
Drawdown 410 Feet Specific Capacity 2 Gals. per min. per ft. of drawdown
How pumped air How measured weir
Observed effect on nearby wells none
9. PERMANENT PUMPING EQUIPMENT:
Type _____ Mfrs. Name _____
Capacity _____ G.P.M. How Driven _____ H.P. _____ R.P.M. _____
Depth of Pump in well _____ Feet Depth of Footpiece in well _____ Feet
Depth of Air Line in well _____ Feet Type of Meter on Pump _____ Size _____ inches
10. USED FOR incustrial AMOUNT { Average _____ Gallons Daily
Maximum _____ Gallons Daily
11. QUALITY OF WATER good Sample: Yes ☒ No _____
Taste none Odor none Color clear Temp. _____ of.
12. LOG 0-160' sand/clay-160-580' cerintine Are samples available? no
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy.)
13. SOURCE OF DATA Somerville Well Drilling Co., Inc.
14. DATA OBTAINED BY same Date 8/20/85

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements, etc.)

ATTACHMENT: C

REFERENCE NO. 15

GROUNDWATER SITE DATA

DATA RELIABILITY (C3)

field checked, location, poor data, minimal checked, un-

SITE TYPE (C2)

collector, drain, excavation, sink-hole, connector, multiple wells, nutcrop, pond, tunnel, well, test hole

DATE OF CONSTRUCTION (C21)

month - day - 19 year

USE OF SITE (C23)

anode, standby, drain, geo- seismic, heat, mine, observation, oil or recharge, repressurize, test, unused, with, waste, destroyed, emer. supply, thermal, reservoir, gas, surges

SECONDARY USE OF SITE (C301) (SEE USE OF SITE)

TERTIARY USE OF SITE (C302) (SEE USE OF SITE)

USE OF WATER (C24)

A B C D E F H I J K M N P Q R S T U Y Z
air cond., bottling, commercial, de-water, power, fire, domestic, irrigation, industrial mining, medicinal, industrial, public supply, aquaculture, recreation, stock, institutional, unused, desalination, other

SECONDARY USE OF WATER (C25) (SEE USE OF WATER)

TERTIARY USE OF WATER (C26) (SEE USE OF WATER)

AQUIFER TYPE (C713)

U N C M X
unconfined single, unconfined multiple, confined single, confined multiple, mixed

PRIMARY AQUIFER (C714)

HOLE DEPTH (C27)

.

WELL DEPTH (C28)

.

SOURCE OF DEPTH DATA (C29)

A D G L M O R S Z
other gov't., driller, geologist, logs, memory, owner, other reported, agency

WATER LEVEL (C30)

.

DATE WATER LEVEL MEASURED (C31) (Mandatory if C30, water level, has a value)

month - day - 19 year

METHOD OF WATER-LEVEL MEASUREMENT (C34)

A B C E G H L M N R S T V Z
airline, analog, calibrated airline, estimated, pressure gage, calibrated press. gage, geophysical logs, manometer, non-rec. gage, reported, steel tape, electric tape, calibrated elec. tape, other

SITE STATUS FOR WATER LEVEL (C37)

D E F G H I J N O P R S T V W X Z
dry, recently flowing, flowing, nearby flowing, nearby recently flowing, injector site, injector site monitor, measurement discon., obstruction, pumping, recently pumped, nearby pumping, nearby recently pumped, foreign subs., well destroyed, surface water effects, other

SOURCE OF WATER-LEVEL DATA (C33)

A D G L M O R S Z
other gov't., driller, geologist, logs, memory, owner, other reported, agency

CONSTRUCTION DATA

RECORD TYPE (C754)

RECORD SEQUENCE NO. (C723)

DATE OF CONSTRUCTION (C60)

month - day - 19 year

NAME OF CONTRACTOR (C63)

.

SOURCE OF DATA (C64)

A D G L M O R S Z
other gov't., driller, geologist, logs, memory, owner, other reported, agency

METHOD OF CONSTRUCTION (C65)

A B C D H J P R T V W Z
air-rotary, bored or augered, cable tool, dug, hydraulic rotary, jetted, air percussion, reverse rotary, trenching, driven, drive wash, other

TYPE OF FINISH (C66)

C F G H O P S T W X Z
porous gravel, gravel, horts., open end, part. or slotted, sand point, welled, open hole, other

TYPE OF SEAL (C67)

B C G N Z
bentonite, clay, cement, none, other

BOTTOM OF SEAL (C68)

.

METHOD OF DEVELOPMENT (C69)

A B C J N P S Z
air-lift pump, belled, compressed air, jetted, none, pumped, surged, other

HOURS OF DEVELOPMENT (C70)

.

SPECIAL TREATMENT (C71)

C D E F H M Z
chemicals, dry ice, explosives, deflocculants, hydro-fracturing, mechanical, other

34	100CNZC	CENOZOIC ERATHEM
34	110QRNR	QUATERNARY SYSTEM
34	111ALVM	HOLOCENE ALLUVIUM
34	111HLCN	HOLOCENE SERIES
34	111HPPM	UNDIFFERENTIATED HOLOCENE, PLEISTOCENE, PLIOCENE, AND MIOCENE
34	111SWMP	SWAMP DEPOSIT
34	112BRDG	BRIDGETON FORMATION
34	112CPHY	CAPE MAY FORMATION
34	112DLTC	DELTAIC SAND FACIES
34	112ESRNC	ESTUARINE CLAY FACIES
34	112ESRNS	ESTUARINE SAND FACIES
34	112GCLK	GLACIAL LAKE DEPOSITS
34	112GKMK	KAME AND KAME TERRACE DEPOSITS
34	112GLCD	GLACIAL DELTA DEPOSITS
34	112HLBC	HOLLY BEACH WATER-BEARING ZONE
34	112MORN	MORaine
34	112MRIN	MARINE SAND FACIES
34	112PKBG	PENSAUKEN-BRIDGETON FORMATIONS
34	112PLCC	PLEISTOCENE SERIES-COHANSEY SAND
34	112PLSC	PLEISTOCENE SERIES
34	112PNSK	PENSAUKEN FORMATION
34	112SDFD	STRATIFIED DRIFT
34	112TILL	TILL
34	120TRTR	TERTIARY SYSTEM
34	121BCHL	BEACON HILL GRAVEL
34	121CKKD	COHANSEY SAND-KIRKWOOD FORMATION
34	121CNSY	COHANSEY SAND
34	121PCMC	PLIOCENE-MIOCENE SERIES
34	121PLCN	PLIOCENE SERIES
34	122KRKD	KIRKWOOD FORMATION
34	122KRKDL	KIRKWOOD FORMATION, LOWER SAND
34	122KRKDU	KIRKWOOD FORMATION, UPPER SAND
34	122MOCN	MIOCENE SERIES
34	123OLGC	OLIGOCENE SERIES
34	124EOCN	Eocene SERIES
34	124MNSQ	MANASQUAN FORMATION
34	124MQVC	MANASQUAN-VINCETOWN FORMATIONS
34	124PNPN	PINEY POINT FORMATION
34	124SKRV	SHARK RIVER MARL
34	125HRRS	HORNERSTOWN SAND
34	125PLCN	PALEOCENE SERIES
34	125VCHR	VINCETOWN FORMATION-HORNERSTOWN SAND
34	125VNCN	VINCETOWN FORMATION
34	200MSZC	MESOZOIC ERATHEM
34	210CRCS	CRETACEOUS SYSTEM
34	211EGLS	ENGLISHTOWN FORMATION
34	211FRNG	FARRINGTON SAND MEMBER OF RARITAN FORMATION
34	211MCVL	MERCHANTVILLE FORMATION
34	211MGRR	MAGOTHY-RARITAN FORMATIONS
34	211MGTY	MAGOTHY FORMATION
34	211HLRL	MOUNT LAUREL SAND
34	211MLRW	MOUNT LAUREL SAND-WENONAH FORMATION
34	211MRPA	MAGOTHY-RARITAN-POTOMAC AQUIFER SYSTEM, UNDIFFERENTIATED
34	211MRPAL	MAGOTHY-RARITAN-POTOMAC AQUIFER SYSTEM, LOWER AQUIFER
34	211MRPAM	MAGOTHY-RARITAN-POTOMAC AQUIFER SYSTEM, MIDDLE AQUIFER
34	211MRPAU	MAGOTHY-RARITAN-POTOMAC AQUIFER SYSTEM, UPPER AQUIFER
34	211MRSL	MARSHALLTOWN FORMATION
34	211NVSK	NAVESINK FORMATION
34	211ODBG	OLD BRIDGE SAND MEMBER OF MAGOTHY FORMATION
34	211RDBK	RED BANK SAND
34	211RRTN	RARITAN FORMATION
34	211SRVL	SAYREVILLE SAND MEMBER OF RARITAN FORMATION
34	211TNTN	TINTON SAND
34	211WBMV	WOODBURY CLAY-MERCHANTVILLE FORMATION
34	211WDBR	WOODBURY CLAY
34	211WNNH	WENONAH FORMATION
34	217PTMC	POTOMAC GROUP
34	227BNTN	BOONTON FORMATION
34	227BRCK	BRUNSWICK GROUP
34	227BRCKS	BRUNSWICK GROUP SEDIMENTARY
34	227BSLT	BASALT
34	227CGLM	CONGLOMERATE
34	227DIBS	DIABASE
34	227FLVL	FELTVILLE FORMATION

RECEIVED

JUN 02 1990

NUS COMM

FLOH

SENT TO

34	227HKMN	HOOK MOUNTAIN BASALT
34	227NWRK	NEWARK SUPERGROUP
34	227ORGM	ORANGE MOUNTAIN BASALT
34	227PRKS	PREAKNESS BASALT
34	227PSSC	PASSAIC FORMATION
34	227TOWC	TOWACO FORMATION
34	230TRSC	TRIASSIC SYSTEM
34	231CGLMU	UNCLASSIFIED CONGLOMERATES
34	231HMCK	HAMMER CREEK FORMATION
34	231LMCG	LIMESTONE CONGLOMERATE
34	231LCKG	LOCKATONG FORMATION
34	231QRCG	QUARTZITE CONGLOMERATE
34	231SCKN	STOCKTON FORMATION
34	300PLZC	PALEOZOIC ERATHEM
34	300WSCK	WISSAHICKON GNEISS
34	324KTTNL	LOWER KITTATINY LIMESTONE
34	324KTTNM	MIDDLE KITTATINY LIMESTONE
34	340DVNN	DEVONIAN SYSTEM
34	341SKMK	SKUNNEMUNK CONGLOMERATE
34	344BLVL	BELLVALE SANDSTONE
34	344CRNL	CORNWALL SHALE
34	344ESPS	ESOPUS FORMATION
34	344KNUS	KANOUSE SANDSTONE
34	344MRCL	MARCELLUS SHALE
34	344ONDG	ONONDAGA LIMESTONE
34	347CHNS	COEYMANS FORMATION
34	347DEPU	DEPUE LIMESTONE MEMBER OF COEYMANS FORMATION
34	347DNVL	DUTTONVILLE MEMBER OF RONDOUT FORMATION
34	347FBKV	FLATBROOKVILLE MEMBER OF NEW SCOTLAND FORMATION
34	347KKBG	KALKBERG LIMESTONE
34	347MNSK	MINISINK LIMESTONE
34	347MPCG	MASHIPACONG MEMBER OF RONDOUT FORMATION
34	347MSKZ	MASKENOZHA MEMBER
34	347NSCD	NEW SCOTLAND FORMATION
34	347ORSK	ORISKANY FORMATION
34	347PREN	PORT EVEN SHALE
34	347PRVL	PETERS VALLEY MEMBER OF COEYMANS FORMATION
34	347RNDT	RONDOUT FORMATION
34	347RVEN	RAVENA MEMBER OF COEYMANS LIMESTONE
34	347SILD	SHAWNEE ISLAND MEMBER OF COEYMANS FORMATION
34	347SMVL	STORMVILLE MEMBER OF COEYMANS FORMATION
34	347TCKR	THACKER MEMBER OF MANLIUS LIMESTONE
34	347WTPR	WHITEPORT DOLOMITE MEMBER OF RANDOUT FORMATION
34	350GRPD	GREEN POND CONGLOMERATE
34	350HGFL	HIGH FALLS FORMATION
34	350SLRN	SILURIAN SYSTEM
34	351BDVL	BOSSARDVILLE LIMESTONE
34	351CVBK	CLOVE BROOK MEMBER OF DECKER FORMATION
34	351DCKR	DECKER FORMATION
34	351LNGD	LONGWOOD SHALE
34	351PXID	POXONO ISLAND FORMATION
34	351WPKC	WALLPACK CENTER MEMBER OF DECKER FORMATION
34	354SNGK	SHAWANGUNK FORMATION
34	360KTTN	KITTATINNY LIMESTONE
34	360ODVC	ORDOVICIAN SYSTEM
34	361BSKL	BUSHKILL MEMBER OF MARTINSBURG SHALE
34	361HRBG	MARTINSBURG SHALE
34	361PAGL	PEN ARGYL MEMBER OF MARTINSBURG SHALE
34	361RMBG	RAMSEYBURG MEMBER OF MARTINSBURG SHALE
34	364JKBG	JACKSONBURG LIMESTONE
34	367EPLR	EPLER FORMATION
34	367KTTNU	UPPER KITTATINY LIMESTONE
34	367RCKB	RICKENBACH DOLOMITE
34	370CMBR	CAMBRIAN SYSTEM
34	371ALNN	ALLENTOWN DOLOMITE
34	374LSVL	LEITHSVILLE FORMATION
34	377HRDS	HARDYSTON QUARTZITE
34	400BLMR	BALTIMORE GNEISS
34	400FRKL	FRANKLIN LIMESTONE
34	400PCMB	PRECAMBRIAN ERATHEM
34	BASEMENT	BASEMENT
34	BEDROCK	BEDROCK

GWSI

UNIQUE ID	SITE OWNER	LOCAL ID	MUNICIPALITY	LAT	CON	ALTITUDE	DEPTH	DIAMETER	STATION ID	AQUIFER	SCREENED INTERVAL	W S	DATE	PERMIT	DEPTH DRILLED	UNIQUE ID
230354	SAYREVILLE W D	SWD F	SAYREVILLE BORO	402614	0741955	28.00	74.0		402614074195501	2110DBG	53.00	74.00	P W 19590221			230356
230357	SAYREVILLE W D	SWD TEST 4	SAYREVILLE BORO	402616	0742029	29.00	89.0		402616074202901	2110DBG	78.00	89.00	U T 1963			230357
230358	SAYREVILLE W D	SWD N	SAYREVILLE BORO	402617	0741945	48.00	90.0		402617074194501	2110DBG	70.00	80.00	P W 19651006			230358
230359	SAYREVILLE W D	SWD D	SAYREVILLE BORO	402618	0741952	29.00	75.0		402618074195201	2110DBG	64.00	75.00	P W 19580926			230359
230360	SAYREVILLE W D	SWD TEST 2	SAYREVILLE BORO	402618	0741952	50.00	78.0		402618074195202	2110DBG	67.00	78.00	U T 1963			230360
230361	SAYREVILLE W D	SWD E	SAYREVILLE BORO	402617	0741958	28.00	62.0		402617074195801	2110DBG	39.00	62.00	P W 1958			230361
230362	PERTH AMPOY WATER DEPT	TEST 1 1944	SAYREVILLE BORO	402619	0742009	25.00	67.0		402619074200901	2110DBG	52.00	67.00	P W 19701117			230362
230363	SAYREVILLE W D	SWD J	SAYREVILLE BORO	402620	0742124	23.00	205		402620074212401	2110FRNG	185.00	205.00	U T 19441025			230363
230364	SAYREVILLE W D	SWD L	SAYREVILLE BORO	402623	0742120	5.70	160		402623074212001	2110FRNG	148.00	160.00	U D 1937			230364
230365	SAYREVILLE W D	SWD G	SAYREVILLE BORO	402624	0741939	63.00	89.0		402624074193901	2110DBG	79.00	89.00	P W 1941202			230365
230366	SAYREVILLE W D	SWD H	SAYREVILLE BORO	402624	0741944	46.00	87.0		402624074194401	2110DBG	56.00	87.00	P W 19600323			230366
230367	SAYREVILLE W D	SWD I	SAYREVILLE BORO	402626	0741936	58.00	94.0		402626074193601	2110DBG	83.00	94.00	P W 1960			230367
230368	SAYREVILLE W D	SWD M	SAYREVILLE BORO	402630	0741949	45.00	83.0		402630074194901	2110DBG	67.00	83.00	P W 19600816			230368
230369	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402631	0742053	20.00	194		402631074205301	2110FRNG	164.00	194.00	U W 19460805			230369
230370	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402638	0742022	48.00	228		402638074202201	2110FRNG	182.00	228.00	U W 19290319			230370
230371	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402642	0741932	85.00	108		402642074193201	2110DBG	98.00	108.00	U T 1963			230371
230372	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402643	0741932	95.00	106		402643074193201	2110DBG	95.00	106.00	U T 19630419			230372
230373	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402647	0741936	110.00	60.0		402647074193601	2110DBG	49.00	128.00	U T 1963			230373
230374	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402648	0741930	100.00	129		402648074193001	2110DBG	117.00	128.00	U T 1963			230374
230375	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402649	0742025	40.80	220		402649074202501	2110FRNG	180.00	220.00	N W 19280302			230375
230376	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402654	0742043	40.00	223		402654074204301	2110FRNG	212.00	223.00	U D 1954			230376
230377	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402654	0742126	20.00	120		402654074212601	2110FRNG	110.00	120.00	N W 1958			230377
230378	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402656	0742104	30.00	184		402656074210401	2110FRNG	184.00	237.00	N W 19271222			230378
230379	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402657	0742020	47.50	237		402657074202001	2110FRNG	181.00	237.00	N W 19271222			230379
230380	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402701	0742159	103			402701074215901	2110DBG	98.00	118.00	U W 1927			230380
230381	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402703	0741859	73.00	118		402703074185901	2110DBG	98.00	118.00	U W 19271105			230381
230382	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402703	0741859	96.56	116		402703074185902	2110DBG	97.00	118.00	N W 19540811			230382
230383	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402705	0742023	54.30	225		402705074202301	2110FRNG	170.00	225.00	N W 19391229			230383
230384	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402706	0742130	27.00	125		402706074213001	2110FRNG	253.00	314.00	N W 19300404			230384
230385	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402711	0742045	40.00	193		402711074204501	2110FRNG	183.00	193.00	U U 19430527			230385
230386	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402711	0742045	40.00	323		402711074204502	2110FRNG	212.00	223.00	U Z 1954			230386
230387	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402710	0741910	108.92	309		4027107419101	2110FRNG	257.00	304.00	N W 1928			230387
230388	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402710	0741910	108.92	309		4027107419102	2110FRNG	249.00	304.00	N W 1928			230388
230389	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402710	0742045	35.00	193		40271074204501	2110FRNG	187.00	198.00	U D 19530805			230389
230390	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402711	0742030	46.70	226		402711074203001	2110FRNG	163.00	172.00	U Z 1928			230390
230391	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402711	0742030	46.70	226		402711074203002	2110FRNG	187.00	226.00	U U 1924			230391
230392	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402716	0741920	101.60	286		402716074192001	2110FRNG	237.00	291.00	N W 1924			230392
230393	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402715	0741932	94.38	284		402715074193201	2110FRNG	246.00	285.00	N W 19250901			230393
230394	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402715	0741932	94.38	284		402715074193202	2110FRNG	244.00	284.00	N W 19250901			230394
230395	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402715	0742050	36.00	175		402715074210201	2110FRNG	175.00	175.00	U Z 1938			230395
230396	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402718	0742213	8.00			402718074221301	2110FRNG	169.00	175.00	U Z 19460524			230396
230397	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402728	0742044	70.00	189		402728074204401	2110FRNG	185.00	189.00	U Z 19480916			230397
230398	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402736	0741949	90.00	255		402736074194901	2110FRNG	230.00	235.00	U Z 19480916			230398
230399	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402741	0741958	70.00	240		402741074195801	2110FRNG	230.00	240.00	U Z 19480902			230399
230400	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163501	2110DBG	57.00	82.00	P W 19600907			230400
230401	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163502	2110DBG	57.00	82.00	P W 19600907			230401
230402	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163503	2110DBG	57.00	82.00	P W 19600907			230402
230403	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163504	2110DBG	57.00	82.00	P W 19600907			230403
230404	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163505	2110DBG	57.00	82.00	P W 19600907			230404
230405	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163506	2110DBG	57.00	82.00	P W 19600907			230405
230406	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163507	2110DBG	57.00	82.00	P W 19600907			230406
230407	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163508	2110DBG	57.00	82.00	P W 19600907			230407
230408	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163509	2110DBG	57.00	82.00	P W 19600907			230408
230409	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163510	2110DBG	57.00	82.00	P W 19600907			230409
230410	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163511	2110DBG	57.00	82.00	P W 19600907			230410
230411	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163512	2110DBG	57.00	82.00	P W 19600907			230411
230412	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163513	2110DBG	57.00	82.00	P W 19600907			230412
230413	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163514	2110DBG	57.00	82.00	P W 19600907			230413
230414	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163515	2110DBG	57.00	82.00	P W 19600907			230414
230415	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163516	2110DBG	57.00	82.00	P W 19600907			230415
230416	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163517	2110DBG	57.00	82.00	P W 19600907			230416
230417	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163518	2110DBG	57.00	82.00	P W 19600907			230417
230418	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163519	2110DBG	57.00	82.00	P W 19600907			230418
230419	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163520	2110DBG	57.00	82.00	P W 19600907			230419
230420	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163521	2110DBG	57.00	82.00	P W 19600907			230420
230421	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163522	2110DBG	57.00	82.00	P W 19600907			230421
230422	HERCULES POWDER	HERCULES 40	SAYREVILLE BORO	402745	0741635	100.00	82.0	20.00	402745074163523	2110DBG	57.00	82.00	P W 19600907			230422
230423	HERCULES POWDER	HERCULES 40	SAYRE													

UNIQUE ID	SITE OWNER	LOCAL ID	MUNICIPALITY	LAT	CON	ALTITUDE	DEPTH	DIAMETER	STATION ID	AQUIFER	SCREENED INTERVAL	W S	DATE	PERMIT	DEPTH DRILLED	UNIQUE ID	
230438	SOUTH RIVER BOR	SRWD	SOUTH RIVER BORO	402559	0742142	19.70	187	12.00	402559074214202	211FRNG	132.00	182.00	P W	197707	28-09722	202	230438
230438	SOUTH RIVER W D	SRWD	SOUTH RIVER BORO	402559	0742142	19.70	187		402559074214202	211FRNG			P W			202	230438
230439	SOUTH RIVER W D	SRWD 2 OBS	SOUTH RIVER BORO	402633	0742200	20.69	126		402633074220001	211FRNG	121.00	126.00	U D	1967			230439
230440	CHADWICK, THOMAS	1	SOUTH RIVER BORO	402648	0742226	15.00	195		402647074222701	211FRNG			N W	1922			230440
230440	BKE CAB CO	1	SOUTH RIVER BORO	402648	0742226	15.00	195		402647074222701	211FRNG			N W				230440
230441	HODGES BUS CO	1	SOUTH RIVER BORO	402648	0742226	15.00	195		402647074222701	211FRNG			N W				230440
230441	HEBERT SAND CO	HSC 3	SOUTH RIVER BORO	402742	0742309	4.40			402748074230601	211FRNG	49.00	52.00	U T	1964			230441
230442	SPOTSWOOD WD	SRWD 3	SPOTSWOOD BORO	402252	0742432	30.00	91.0		402252074243201	211ODBG	63.50	77.92	P W	197306	28-07828		230442
230442	SPOTSWOOD WD	SRWD 3	SPOTSWOOD BORO	402252	0742432	30.00	91.0		402252074243201	211ODBG	64.00	78.00	P W				230442
230443	SPOTSWOOD WD	TEST WELL 3	SPOTSWOOD BORO	402329	0742318	20.00	79.0		402318074233101	211ODBG	59.00	79.00	U T	19700727			230443
230444	DUHERNAL W CO	DUHERNAL 4	SPOTSWOOD BORO	402328	0742318	12.00	264	12.00	402328074231801	211FRNG	62.00	72.00	U D	19381026			230444
230445	SPOTSWOOD WD	TW 4F-76	SPOTSWOOD BORO	402328	0742318	12.00	264		402328074231801	211FRNG	195.00	215.00	U T	197607		328	230445
230445	SPOTSWOOD WD	TW 4F-76	SPOTSWOOD BORO	402328	0742318	12.00	264		402328074231801	211FRNG	219.00	239.00	U T			328	230445
230445	SPOTSWOOD WD	TW 4F-76	SPOTSWOOD BORO	402328	0742318	12.00	264		402328074231801	211FRNG	254.00	251.00	U Z	19460427		328	230445
230446	DUHERNAL W CO	DUHERNAL OBS 50F	SPOTSWOOD BORO	402328	0742318	12.00	264		402328074231801	211FRNG	273.00	280.00	U Z				230446
230446	SPOTSWOOD WD	DUHERNAL OBS 50F	SPOTSWOOD BORO	402328	0742318	12.00	264		402328074231801	211FRNG	64.00	85.00	P W	19561126	28-02172		230446
230447	SPOTSWOOD WD	DUHERNAL OBS 50F	SPOTSWOOD BORO	402328	0742318	12.00	264		402328074231801	211FRNG	62.00	83.00	U Z	19571122	28-02173		230447
230448	SPOTSWOOD WD	DUHERNAL 17	SPOTSWOOD BORO	402330	0742316	20.00	83.0		402330074231601	211ODBG			U D				230448
230449	DUHERNAL W CO	DUHERNAL OPS 11	SPOTSWOOD BORO	402330	0742316	20.00	83.0		402330074231601	211ODBG	69.00		U D				230449
230450	SCHWEITZER, P. J.	5	SPOTSWOOD BORO	402401	0742243	36.00	89.0		402401074224301	211FRNG	49.00	89.00	N W	19410826			230450
230451	SCHWEITZER, P. J.	8	SPOTSWOOD BORO	402401	0742243	36.00	89.0		402401074224301	211FRNG	226.00	285.00	N W	19470522			230451
230452	SCHWEITZER, P. J.	1	SPOTSWOOD BORO	402401	0742243	36.00	89.0		402401074224301	211FRNG	265.00	285.00	N W	19290121			230452
230453	SCHWEITZER, P. J.	3	SPOTSWOOD BORO	402404	0742233	30.00	285		402404074223301	211FRNG	49.00	74.00	N W	19290321			230453
230454	SCHWEITZER, P. J.	2	SPOTSWOOD BORO	402404	0742233	30.00	285		402404074223301	211FRNG	36.00	61.00	N W	19290129			230454
230455	SCHWEITZER, P. J.	1R	SPOTSWOOD BORO	402404	0742233	30.00	285		402404074223301	211FRNG	235.00	275.00	N W	19560606			230455
230456	SCHWEITZER, P. J.	7	SPOTSWOOD BORO	402405	0742247	30.00	73.0		402405074224701	211ODBG	53.00	73.00	N W	19421024			230456
230457	SCHWEITZER, P. J.	3R	SPOTSWOOD BORO	402408	0742243	33.00	76.0		402408074224301	211ODBG	61.00	76.00	N W	19460625			230457
230458	SCHWEITZER, P. J.	7	SPOTSWOOD BORO	402412	0742248	35.00	68.0		402412074224801	211ODBG	53.00	68.00	N W	19600218			230458
230459	SCHWEITZER, P. J.	4R	SPOTSWOOD BORO	402421	0742230	25.00	63.0		402421074223001	211ODBG	49.00	59.00	N W	19610216			230459
230460	UNION CARBIDE	CARBIDE 1	WOODBRIDGE TWP	403043	0741842	15.00	57.0		403043074184201	211FRNG	47.00	57.00	N W	19650928			230460
230461	HEYDEN CHEM CO	1	WOODBRIDGE TWP	403050	0741916	10.00	190		403050074191601	211FRNG			N W	1934			230461
230462	HEYDEN CHEM CO	3-1934	WOODBRIDGE TWP	403050	0741916	10.00	190		403050074191601	211FRNG			N W	1934			230462
230463	HEYDEN CHEM CO	4-1934	WOODBRIDGE TWP	403050	0741916	10.00	190		403050074191601	211FRNG			N W	1934			230463
230464	CATALIN CORP	1	WOODBRIDGE TWP	403051	0741931	10.00	38.0		403051074193101	211FRNG			N W	1940			230464
230465	CATALIN CORP	1	WOODBRIDGE TWP	403051	0741931	10.00	38.0		403051074193101	211FRNG			N W	1940			230465
230466	CATALIN CORP	1	WOODBRIDGE TWP	403051	0741931	10.00	38.0		403051074193101	211FRNG			N W	1940			230466
230467	CATALIN CORP	1	WOODBRIDGE TWP	403051	0741931	10.00	38.0		403051074193101	211FRNG			N W	1940			230467
230468	CATALIN CORP	1	WOODBRIDGE TWP	403051	0741931	10.00	38.0		403051074193101	211FRNG			N W	1940			230468
230469	CATALIN CORP	1	WOODBRIDGE TWP	403051	0741931	10.00	38.0		403051074193101	211FRNG			N W	1940			230469
230470	CATALIN CORP	1	WOODBRIDGE TWP	403051	0741931	10.00	38.0		403051074193101	211FRNG			N W	1940			230470
230471	CATALIN CORP	1	WOODBRIDGE TWP	403051	0741931	10.00	38.0		403051074193101	211FRNG			N W	1940			230471
230472	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403233	0741633	30.00	59.0		403233074163301	211FRNG	39.00	59.00	N W	19531123			230472
230473	SWIFT AND CO	SWIFT 1	WOODBRIDGE TWP	403233	0741633	30.00	59.0		403233074163301	211FRNG	41.00	61.00	N W	19531210			230473
230474	HAAGEN DAZS INC	SWIFT 1	WOODBRIDGE TWP	403233	0741633	30.00	59.0		403233074163301	211FRNG			N W				230474
230475	RECHARGE WELL	RECHARGE WELL	WOODBRIDGE TWP	403233	0741633	30.00	59.0		403233074163301	211FRNG			N W				230475
230476	HAAGEN DAZS INC	RECHARGE WELL	WOODBRIDGE TWP	403233	0741633	30.00	59.0		403233074163301	211FRNG			N W				230476
230477	CLOVER GREEN DY	DAIRY WELL	WOODBRIDGE TWP	403233	0741633	30.00	59.0		403233074163301	211FRNG			N W				230477
230478	NJ WOOD FINISH	NJ WOOD 3	WOODBRIDGE TWP	403234	0741633	35.00	77.0		403234074163301	211FRNG			N W	1936			230478
230479	ALPHA ASSOC	NJ WOOD 3	WOODBRIDGE TWP	403234	0741633	35.00	77.0		403234074163301	211FRNG			N W	19420227			230479
230480	VULCAN DETINING	1	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W	1913			230480
230481	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG	45.00	60.00	N W	19581215	26-01889		230481
230482	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG	44.00	54.00	U Z	19470129			230482
230483	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG	46.00	56.00	U Z				230483
230484	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG	63.00	73.00	U Z				230484
230485	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG	64.00	75.00	U Z				230485
230486	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W	1910			230486
230487	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W	1927			230487
230488	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG	44.00	54.00	U D				230488
230489	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230489
230490	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230490
230491	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230491
230492	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230492
230493	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230493
230494	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230494
230495	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230495
230496	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230496
230497	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230497
230498	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230498
230499	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230499
230500	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230500
230501	AMERICAN CYANAMID CO	CYAN WDBRG F3	WOODBRIDGE TWP	403236	0741616	10.00	10.0		403236074161601	211FRNG			N W				230501

GWSI

UNIQUE ID	SITE OWNER	LOCAL ID	MUNICIPALITY	LAT	LON	ALTITUDE	DEPTH	DIAMETER	STATION ID	AQUIFER	SCREENED INTERVAL	W S	DATE	PERMIT	DEPTH DRILLED	UNIQUE ID
230512	ERDMAN, W		E BRUNSWICK TWP	402531	0742822	85.00			402531074282201	211FRNG		H				230512
230513	WILLIAMS, FOR		E BRUNSWICK TWP	402357	0742632	95.00	20.0		402357074263202	211FRNG		S				230513
230514	HEFFERT SAND CO		E BRUNSWICK TWP	402755	0742258	4.70	35.0	6.00	402755074225801	211FRNG	25.00	35.00	19760820		40.0	230514
230515	RAAB, GEORGE		E BRUNSWICK TWP	402425	0742520	109.00			402425074252001	211UDBG		I				230515
230516	NOVAK		HULSART	402123	0741849	110.00	19.0		402123074184901	211EGLS	0.00	19.00				230516
230517	KAISER AG CHEM		MONROE TWP	401923	0742830	120.00	176	12	401923074283001	211UDBG	165.00	196.00			300	230517
230518	COMPUTER SYSTEMS		NUE-AIR CONDITIO	402155	0743213	80	147		402155074321301	231SCKN	205.00	347.00	19600217	28-03746	347	230518
230519	NUE CORP		NUE-AIR CONDITIO	402155	0743213	80	147		402155074321301	231SCKN					347	230519
230520	BOYKIL, OLLIE		FLAINSBORO TWP	402044	0743342	80.00	73.0	6.00	402044074334201	211UDBG	68.00	73.00	19761019	28-09369	75.0	230520
230521	COLUMBIAN CARBN		FLAINSBORO TWP	402023	0743740	80.00	300		402023074374001	231LCKG						230521
230522	SCHWEITZER, P J		SPOTSWOOD BORO	402413	0742241	25.00	63.0	24.00	402413074224101	211UDBG	53.00	63.00	19781014	48-00030	68.0	230522
230523	STANLEY CORP		PERTH AMBOY CITY	403229	0741635	15.0	61.5	14.00	403229074163501	211FRNG	46.50	61.50	19770616		68.0	230523
230524	BIRD & SONS		PERTH AMBOY CITY	403212	0741619	20.00	67.0	12.00	403212074161901	211FRNG	57.00	67.00	19791008	26-04798	67.0	230524
230525	FORRESTAL LARS		FLAINSBORO TWP	402050	0743608	100.00	449		402050074360801	231BRCK						230525
230526	DOW JONES CO		SOUTH BRUNSWICK TWP	402218	0743512	80.00		505	402218074351201	231LCKG	37	505	19620424	28-04393	305	230526
230527	COLUMBIAN CARBN		SOUTH BRUNSWICK TWP	402218	0743512	80.00		505	402218074351201	231LCKG					305	230527
230528	GULF OIL CO		ABAN	402402	0743342	80.00	705	10.00	402402074334201	231BRCK	23.00	702.00	19510210	28-00222	705	230528
230529	RUMATOWSKI, C		SOUTH BRUNSWICK TWP	402447	0743020	95.00	220		402447074302001	211HRPA						230529
230530	KURE JAPANESE REST		EAST BRUNSWICK TWP	402448	0742730	90.00			402448074273001	211FRNG					274	230530
230531	BRUNSWICK TWP WC		EAST BRUNSWICK TWP	402448	0742730	90.00			402448074273001	211FRNG					274	230531
230532	BRUNSWICK RUBBER		SOUTH BRUNSWICK TWP	402518	0743309	180.00	805	12.00	402518074330901	231BRCK	32.00	805.00	19591202		805	230532
230533	BRUNSWICK TWP WC		SOUTH BRUNSWICK TWP	402526	0743129	125.00	257	8	402526074312901	231BRCK	42	257	19610621		257	230533
230534	FLAGPOST INN		SOUTH BRUNSWICK TWP	402526	0743414	140.00	486	12.00	402526074341401	231BRCK	59.00	486.00	19600208		486	230534
230535	PERTH AMBOY WATER DEPART		SOUTH BRUNSWICK TWP	402528	0743138	130.00	400		402528074313801	231BRCK						230535
230536	BRUNSWICK TWP WC		OLD BRIDGE TWP	402536	0742018	10.00			402536074201802	211UDBG					96.0	230536
230537	JOHNSON & JOHNSON CO		SOUTH BRUNSWICK TWP	402547	0743305	170.00	703	12.00	402547074330501	231BRCK	34.00	703.00	19590820		703	230537
230538	BAHATTA BUILDER		NORTH BRUNSWICK TWP	402620	0741015	100.00			402620074101501	231BRCK					296	230538
230539	E I DUPONT		MILLTOWN BORO	402645	0742620	65.00	300		402645074262001	231BRCK						230539
230540	RODIE RUBBER CO		SAYREVILLE BORO	402734	0741925	130.00	146		402734074192501	211FRNG						230540
230541	JOHNSON & JOHNSON CO		NEW BRUNSWICK CITY	402920	0742647	120.00	225		402920074264701	211HRPA						230541
230542	SHELL OIL CO		NORTH BRUNSWICK TWP	403000	0742644	40.00	601		403000074264401	231BRCK						230542
230543	SHELL OIL CO		WOODBURGE TWP	403231	0741518	17.00	36.0		403231074151801	211FRNG						230543
230544	SHELL OIL CO		WOODBURGE TWP	403232	0741522	5.00	22.0		403232074152201	211FRNG						230544
230545	SHELL OIL CO		WOODBURGE TWP	403242	0741526	24.76	42.0		403242074152601	211FRNG						230545
230546	SHELL OIL CO		WOODBURGE TWP	403243	0741533	20.00	28.5		403243074153301	211FRNG						230546
230547	SHELL OIL CO		WOODBURGE TWP	403249	0741538	22.00	43.0		403249074153801	211FRNG						230547
230548	SHELL OIL CO		WOODBURGE TWP	403250	0741534	26.00	43.0		403250074153401	211FRNG						230548
230549	SAYREVILLE W D		WOODBURGE TWP	403257	0741539	16.92	36.0		403257074153901	211FRNG						230549
230550	A J PRINTING CO		SAYREVILLE BORO	402745	0741645	23.00	111	0.00	402745074164501	211UDBG	70.00	111.00	19800501	29-10500	137	230550
230551	SOUTH RIVER W D		DUNELLEN BORO	403537	0742720	60.00	325	12.00	403537074272001	231BRCK					325	230551
230552	SOUTH BRUNSWICK MUA		SOUTH RIVER BORO	402548	0742153	47.00	213	20.00	402548074215301	211FRNG	155.00	208.00	19500831		217	230552
230553			SOUTH BRUNSWICK TWP	402018	0743021	105.00	166	32.00	402018074302102	211FRNG	116.00	126.00	19790501	28-11524	184	230553
230554	MONROE TWP MUA		MONROE TWP	401950	0742750	105.00	166		401950074275001	211FRNG	146.00	166.00			184	230554
230555	SAYREVILLE W D		SAYREVILLE BORO	402745	0741645	100.00	286	9.00	402745074164501	211FRNG	213.00	286.00	19800717		464	230555
230556	MONROE TWP MUA		MONROE TWP	402010	0742811	136.00	208	20.00	402010074281101	211FRNG	168.00	208.00	19800421	28-11720	309	230556
230557	MONROE TWP MUA		MONROE TWP	401950	0742721	137.00	215	9.00	401950074272101	211FRNG	160.00	215.00	19800725	28-11719	385	230557
230558	SOUTH AMBOY W D		MONROE TWP	401950	0742721	137.00	215		401950074272101	211FRNG	185.00	215.00	19801009		444	230558
230559	FUT, STEPHEN		SAYREVILLE BORO	402820	0741629	20.00	58.0	20.00	402820074162901	211UDBG	48.00	58.00	19790721	26-04812	58.0	230559
230560	SECURITY STEEL		WOODBURGE TWP	403220	0741820		302		403220074182001	231BRCK						230560
230561	NATIONAL VARNISH		WOODBURGE TWP	403420	0741633		614		403420074163301	231BRCK						230561
230562	HOME FOR DIAR VETS		WOODBURGE TWP	403553	0741527		405		403553074152701	231BRCK						230562
230563	NEW DOVER CHURCH		EDISON TWP	403313	0741607		614		403313074160701	231BRCK						230563
230564	PERTH AMBOY WATER DEPART		EDISON TWP	403500	0742033		111		403500074203301	231BRCK						230564
230565	SOUTH BRUNSWICK TOWNSHIP		OLD BRIDGE TWP	402527	0742007		260		402527074200701	211FRNG						230565
230566	MONROE TWP MUA		SOUTH BRUNSWICK TWP	402015	0743018	100.00	164	12.00	402015074301801	211FRNG	134.00	164.00	19780627	28-10332	196	230566
230567	STAUFFER CHEM		MONROE TWP	401958	0742819	130.00	197	0.00	401958074281902	211UDBG	165.00	197.00	19800814		383	230567
230568	MONROE TWP MUA		SOUTH BRUNSWICK TWP	402129	0742901	124.10	225	0.00	402129074290102	211FRNG	122.00	225.00	19820302	28-12856	239	230568
230569			MONROE TWP	401950	0742750	137.00	244	0.00	401950074275002	211UDBG	163.00	171.00	19830707	28-13397	250	230569
230570			MONROE TWP	401950	0742750	137.00	244		401950074275002	211UDBG	181.00	187.00			250	230570
230571			MONROE TWP	401950	0742750	137.00	244		401950074275002	211UDBG	193.00	213.00			250	230571
230572			MONROE TWP	401950	0742750	137.00	244		401950074275002	211UDBG	234.00	244.00			250	230572
230573	SCHWEITZER, P J		SAYREVILLE BORO	402410	0742231	25.00	280	0.00	402410074223101	211FRNG	210.00	280.00	19830217	28-12880	289	230573
230574	SAYREVILLE W D		SAYREVILLE BORO	402745	0741645	23.00	111	0.00	402745074164501	211UDBG	102.00	132.00	19820323	29-11861	163	230574
230575	PERTH AMBOY WATER DEPART		OLD BRIDGE TWP	402536	0741700	10.00	137	0.00	402536074170001	211UDBG	60.00	80.00	19821108	29-12351	86.0	230575
230576	PERTH AMBOY WATER DEPART		OLD BRIDGE TWP	402531	0741932	15.00	82.0	0.00	402531074193201	211UDBG	67.00	82.00	19830328	29-12352	90.0	230576
230577	CIRAKY, NICHOLAS		WOODBURGE TWP	403207	0741817	150.00	133	0.00	403207074181701	211FRNG					123	230577
230578	PONSKA, FRANK		SAYREVILLE BORO	402737	0741736	100.00	135	0.00	402737074173601	211FRNG	125.00	135.00	19710602	26-04398	140	230578
230579	MCREON, JOHN		SOUTH AMBOY CITY	402925	0741704	15.00	133	0.00	402925074170401	211FRNG	127.00	133.00	19751015	26-04635	165	230579
230580	SPINELLO CONST CO		SOUTH AMBOY CITY	402933	0741718	30.00	165	0.00	402933074171801	211UDBG						230580
230581	CHEVRON OIL CO		PERTH AMBOY CITY	403210	0741520	6.80	57.0	7.88	403210074152001	211FRNG	37.00	57.00	19811105	26-05321	61.0	230581
230582	PERTH AMBOY WATER DEPART		WOODBURGE TWP	403236	0741543	5.00	64.2	7.88	403236074154302	211FRNG	44.20	64.20	19811113	26-05324	75.3	230582
230583	PARLIN SUPPLY CO		OLD BRIDGE TWP	402517	0742050	20.00	62.0	0.00	402517074205001	211UDBG	57.00	62.00	19541220	28-01524	85.0	230583
230584	MID CO UTIL AUTH		SAYREVILLE BORO	402505	0742029	80.00	44.0	0.00	402505074202901	211UDBG	24.00	44.00	19740601	28-08423	70.0	230584
230585	AIR PRODUCTS		OLD BR													

UNIQUE ID	SITE OWNER	LOCAL ID	MUNICIPALITY	LAT	LO	ALTITUDE	DEPTH	DIAMETER	STATION ID	AQUIFER	SCREENED INTERVAL	W	S	DATE	PERMIT	DEPTH DRILLED	UNIQUE ID	
230771	SCHARF, STEVEN	SCHARF 1	MONROE TWP	401718	0742449	110.00	320	4.00	401718074244901	2110DBG	310.00	320.00	H	W	19821123	28-13112	330	230771
230772	KOKOSA, EDGIE	KOKOSA 1	MONROE TWP	402036	0742706	145.00	150	0.00	402036074270601	2110DBG	147.00	150.00	H	W	19560804	28-01994	151	230772
230773	TEE-N-JAY FARM	T-N-J 1	MONROE TWP	401942	0742232	90.00	295	0.00	401942074223201	2110DBG	285.00	295.00	H	W	19731201	28-08150	295	230773
230774	RESNICK, LEWIS	RESNICK 1	MONROE TWP	401623	0742819	110.00	215	0.00	401623074281901	2110DBG	205.00	215.00	H	W	19810530	28-12288	215	230774
230775	SEPTAK, JOHN J	SEPTAK 1	MONROE TWP	401717	0742721	120.00	190	0.00	401717074272101	2110DBG	182.00	190.00	H	W	19791019	28-11436	190	230775
230776	SIMONSON BROS	HOUSE WELL	FLAINSBORO TWP	402047	0743329	80.00	70.0	0.00	402047074332901	211FRNG	65.00	70.00	H	W	19850731	28-15632	70.0	230776
230777	CHOU (SHADOW OAKS)	CHOU 1	CRANBURY TWP	401786	0743181	100.00	88.0	0.00	401786074318101	211FRNG	80.00	88.00	H	W	19810603	28-11996	88.0	230777
230778	FINN, WILLIAM	FINN 1	CRANBURY TWP	401833	0743043	120.00	120	0.00	401833074304301	211FRNG	122.00	130.00	H	W	19830602	28-13514	130	230778
230779	BERTSFORD, JAMES	THRIFT STORE	CRANBURY TWP	401826	0743330	100.00	90.0	0.00	401826074333001	211FRNG	110.00	120.00	C	W	19750404	28-08750	120	230779
230780	ZAITS, MAX (HIRSCH)	THRIFT	CRANBURY TWP	402225	0741821	60.00	235	0.00	4022250741822501	2110DBG	225.00	235.00	H	W	19800128	28-06575	90.0	230780
230781	JOCAMA CONST CO	OLD BRIDGE TWP	OLD BRIDGE TWP	402353	0742056	30.00	337	0.00	402353074205601	211FRNG	250.00	255.00	P	W	19840801	28-14095	255	230781
230782	OLD BRIDGE MUA	OLD BRIDGE TWP	OLD BRIDGE TWP	402353	0742056	30.00	337	0.00	402353074205601	211FRNG	255.00	265.00	P	W			345	230782
230782		OLD BRIDGE TWP	OLD BRIDGE TWP	402353	0742056	30.00	337	0.00	402353074205601	211FRNG	272.00	302.00	P	W			345	230782
230782		OLD BRIDGE TWP	OLD BRIDGE TWP	402353	0742056	30.00	337	0.00	402353074205601	211FRNG	312.00	317.00	P	W			345	230782
230782		OLD BRIDGE TWP	OLD BRIDGE TWP	402353	0742056	30.00	337	0.00	402353074205601	211FRNG	322.00	327.00	P	W			345	230782
230782		OLD BRIDGE TWP	OLD BRIDGE TWP	402353	0742056	30.00	337	0.00	402353074205601	211FRNG	330.00	337.00	P	W			345	230782
230783	OLD BRIDGE PARASREC	SOCCER ASSN 1	OLD BRIDGE TWP	402327	0741620	90.00	265	0.00	402327074162001	2110DBG	245.00	265.00	U	W	19830518	29-12817	265	230783
230784	NAVEDO, JOE	NAVEDO 1	OLD BRIDGE TWP	402327	0742054	30.00	69.0	0.00	402327074205401	2110DBG	63.00	69.00	H	W	19820701	28-13023	70.0	230784
230785	SKITIMAS, CHARLES	FEROSA 1	EAST BRUNSWICK TWP	402358	0742518	140.00	121	0.00	402358074251801	2110DBG	116.00	121.00	H	W	19820701	28-08649	124	230785
230786	HOSTETLER, HENRY	HOLETELER 1	EAST BRUNSWICK TWP	401919	0743403	100.00	63.0	0.00	401919074340301	211FRNG	55.00	63.00	H	W	19791120	28-11501	63.0	230786
230786	ELY, JOHN	DBS WELL 7	SOUTH BRUNSWICK TWP	402128	0743055	100.00	110	0.00	402128074305501	211FRNG	100.00	110.00	H	W	19810807	23-12434	120	230786
230788	EAST BRUNSWICK TWP	DBS WELL 6	EAST BRUNSWICK TWP	402430	0742552	95	132.75		402430074255201	211FRNG	126.75	132.75	U	Z	19731016	28-08650	160	230788
230789	EAST BRUNSWICK TWP	DBS WELL 7	EAST BRUNSWICK TWP	402416	0742553	130	276.25		402416074255301	211FRNG	212.25	217.25	U	Z	19731002	28-08612	289	230789
230789	EAST BRUNSWICK TWP	DBS WELL 6	EAST BRUNSWICK TWP	402427	0742553	130	276.25		402427074255301	211FRNG	271.25	276.25	U	Z			289	230789
230790	US GEOLOGICAL SURVEY	S. RIVER HIGH	SOUTH RIVER BORO	401940	0743353	80		6.25	402627074224701				U	T	19850905	28-15614	147	230790
230791	US GEOLOGICAL SURVEY	LINPRO	FLAINSBORO TWP	402039	0743601	97.6	60.0	6.25	402058074335301	231SCKN	31.0	60.0	U	T	19850912	28-15615	130	230791
230792	PRINCETON UNIVERSITY	TEST WELL 1	FLAINSBORO TWP	402100	0743601	97.7	68.0		402059074360101	231SCKN	31.0	60.0	U	T	19851201	28-16112	60.0	230792
230793	PRINCETON UNIVERSITY	TEST WELL 2	FLAINSBORO TWP	402100	0743559	95.9	81.0		402058074360001	231SCKN	30.0	68.0	U	T	19851201	28-16113	68.0	230793
230794	PRINCETON UNIVERSITY	TEST WELL 3	FLAINSBORO TWP	402100	0743559	96.7	120.0		402058074360002	231SCKN	100.0	120.0	U	T	19851201	28-16114	81.0	230794
230795	PRINCETON UNIVERSITY	TEST WELL 4	FLAINSBORO TWP	402058	0743559	96.7	60.0		402058074355901	231SCKN	20	60.0	U	T	19851201	28-16115	120.0	230795
230796	PRINCETON UNIVERSITY	TEST WELL 5	FLAINSBORO TWP	402100	0743557	95.9	73.0		402059074355701	231SCKN	26	73.0	U	T	19851201	28-16117	73.0	230796
230797	PRINCETON UNIVERSITY	TEST WELL 6	FLAINSBORO TWP	402100	0743600	93.4	85.0		402059074360001	231SCKN	41.0	85.0	U	T	19851201	28-16118	85.0	230797
230798	PRINCETON UNIVERSITY	TEST WELL 7	FLAINSBORO TWP	402100	0743558	93.8	75.0		402059074355801	231SCKN	30	75.0	U	T	19851201	28-16119	75.0	230798
230799	PRINCETON UNIVERSITY	TEST WELL 8	FLAINSBORO TWP	402058	0743559	96.8	110.0		402058074355902	231SCKN	90.0	110.0	U	T	19850201	28-16120	110.0	230799
230800	PRINCETON UNIVERSITY	TEST WELL 9	FLAINSBORO TWP	402058	0743601	97.1	125.0		402059074360102	231SCKN	100.0	125.0	U	T	19850201	28-16251	125.0	230800
230801	PRINCETON UNIVERSITY	TEST WELL 10	FLAINSBORO TWP	402323	0742838	100	122	8.5	402323074283801	211FRNG	112	122	H	W	19801022	28-12037	126	230801
230802	BREESE	BREESE 1	SOUTH BRUNSWICK TWP	402224	0742500	40	60	4	402224074250001	2110DBG	30	60	H	W	19801101	28-14178	60	230802
230803	GABOURY	GABOURY 1	MONROE TWP	402945	0741937	3.4			402945074193701								36.3	230803
230804	MIDDLESEX COUNTY UTILITIE	R-02	WOODBRIIDGE TWP	402948	0741939	4.4			402948074193901								37.1	230804
230805	MIDDLESEX COUNTY UTILITIE	R-04	WOODBRIIDGE TWP	402932	0741939	3.5			402932074193901								31.3	230805
230806	MIDDLESEX COUNTY UTILITIE	R-05	WOODBRIIDGE TWP	402937	0741933	5.0			402937074193301								26.3	230806
230807	MIDDLESEX COUNTY UTILITIE	R-06	WOODBRIIDGE TWP	403008	0741919	2.8			403008074191901								31.3	230807
230808	MIDDLESEX COUNTY UTILITIE	R-07	WOODBRIIDGE TWP	403012	0741913	4.4			403012074191301								26.3	230808
230809	MIDDLESEX COUNTY UTILITIE	R-08	WOODBRIIDGE TWP	402946	0741935	16.3			402946074193501								36	230809
230810	MIDDLESEX COUNTY UTILITIE	R-09	WOODBRIIDGE TWP	402936	0741928	4.4			402936074192801								38.3	230810
230811	MIDDLESEX COUNTY UTILITIE	R-10	SAYREVILLE BORO	402922	0741918	4.4			402922074191801				U	T	19670000		38.3	230811
230812	MIDDLESEX COUNTY UTILITIE	R-11	SAYREVILLE BORO	402919	0741916	-8.1			402919074191601				U	T	19670000		38	230812
230813	MIDDLESEX COUNTY UTILITIE	TC-243	OLD BRIDGE TWP	402803	0741405	0.0			402803074140501				U	T	19670000		46.0	230813
230814	TITANIUM PIGMENT CO.	TP-101R	WOODBRIIDGE TWP	403034	0741728	0.0			403034074172801				U	T	19670000		29.1	230814
230815	TITANIUM PIGMENT CO.	TP-102B	WOODBRIIDGE TWP	403039	0741808	0.0			403039074180801				U	T	19670000		30	230815
230816	TITANIUM PIGMENT CO.	TP-103B	WOODBRIIDGE TWP	403029	0741838	0.0			403029074183801				U	T	19670000		75	230816
230817	TITANIUM PIGMENT CO.	TP-104	WOODBRIIDGE TWP	403029	0741837	0.0			403029074183701				U	T	19670000		59.3	230817
230818	TITANIUM PIGMENT CO.	TP-105B	WOODBRIIDGE TWP	403022	0741843	0.0			403022074184301				U	T	19670000		32	230818
230819	TITANIUM PIGMENT CO.	TP-106	WOODBRIIDGE TWP	403021	0741838	0.0			403021074183801				U	T	19670000		30	230819
230820	TITANIUM PIGMENT CO.	TP-107	WOODBRIIDGE TWP	403020	0741844	0.0			403020074184401				U	T	19670000		37	230820
230821	TITANIUM PIGMENT CO.	TP-108B	WOODBRIIDGE TWP	403019	0741840	0.0			403019074184001				U	T	19670000		37	230821
230822	TITANIUM PIGMENT CO.	TP-109	WOODBRIIDGE TWP	403018	0741845	0.0			403018074184501				U	T	19670000		37	230822
230823	TITANIUM PIGMENT CO.	TP-110	SAYREVILLE BORO	403017	0741841	0.0			403017074184101				U	T	19670000		32.3	230823
230824	TITANIUM PIGMENT CO.	TP-111B	SAYREVILLE BORO	403016	0741845	0.0			403016074184501				U	T	19670000		37	230824
230825	TITANIUM PIGMENT CO.	TP-112	SAYREVILLE BORO	403014	0741842	0.0			403014074184201				U	T	19670000		51	230825
230826	TITANIUM PIGMENT CO.	TP-113	SAYREVILLE BORO	403013	0741847	0.0			403013074184701				U	T	19670000		48.7	230826
230827	TITANIUM PIGMENT CO.	TP-114	SAYREVILLE BORO	403010	0741844	0.0			403010074184401				U	T	19670000		57.3	230827
230828	TITANIUM PIGMENT CO.	TP-115	SAYREVILLE BORO	403008	0741845	0.0			403008074184501				U	T	19670000		57.3	230828
230829	TITANIUM PIGMENT CO.	TP-116	SAYREVILLE BORO	403007	0741850	0.0			403007074185001				U	T	19670000		53	230829
230830	TITANIUM PIGMENT CO.	TP-117	SAYREVILLE BORO	403005	0741846	0.0			403005074184601				U	T	19670000		41	230830
230831	TITANIUM PIGMENT CO.	TP-118	SAYREVILLE BORO	403005	0741851	0.0			403005074185101				U	T	19670000		36	230831
230832	TITANIUM PIGMENT CO.	TP-119B	SAYREVILLE BORO	403002	0741848	0.0			403002074184801				U	T	19670000		52.3	230832
230833	TITANIUM PIGMENT CO.	TP-120B	SAYREVILLE BORO	403003	0741852	0.0			403003074185201				U</					

WELL ID	SITE	LOCAL ID	MUNICIPALITY	LAT	LONG	ALTITUDE	DEPTH	DIAMETER	STATION ID	AQUIFER	SCREENED INTERVAL	W S	DATE	PERMIT	DEPTH DRILLED	UNIQUE ID
230855	US ARMY CORPS OF ENGINEERS	DH-23E	SAYREVILLE BORO	402818	0742208	6.0			402818074220801			U	T		36.	230855
230856	US ARMY CORPS OF ENGINEERS	DH-24E	EDISON TWP	402826	0742100	4.0			402826074210001			U	T		36.	230856
230857	US ARMY CORPS OF ENGINEERS	DH-25E	EDISON TWP	402832	0742144	6.1			402832074214401			U	T		36.	230857
230858	US ARMY CORPS OF ENGINEERS	DH-26E	EDISON TWP	402837	0742133	7.0			402837074213301			U	T		36.	230858
230859	US ARMY CORPS OF ENGINEERS	DH-27E	SAYREVILLE BORO	402846	0742115	7.4			402846074211501			U	T		36.	230859
230860	US ARMY CORPS OF ENGINEERS	DH-28E	SAYREVILLE BORO	402855	0742100	7.0			402855074210001			U	T		36.	230860
230861	US ARMY CORPS OF ENGINEERS	DH-31F	EDISON TWP	402837	0742138	6.1			402837074213801			U	T		36.	230861
230862	MIDDLESEX COUNTY UTILITIES	0-01	SOUTH AMBOY CITY	402912	0741640	8.4			402912074164001			U	T	19550300	17.	230862
230863	MIDDLESEX COUNTY UTILITIES	0-04	SOUTH AMBOY CITY	402932	0741806	8.9			402932074180601			U	T	19550300	39.	230863
230864	MIDDLESEX COUNTY UTILITIES	0-16	SOUTH AMBOY CITY	402848	0741442	0.0			402848074144201			U	T	19550300	98.	230864
230865	MIDDLESEX COUNTY UTILITIES	0-19	SOUTH AMBOY CITY	402851	0741455	0.0			402851074145501			U	T	19550300	88.	230865
230866	MIDDLESEX COUNTY UTILITIES	0-29	SOUTH AMBOY CITY	402900	0741542	0.0			402900074154201			U	T	19550300	30.	230866
230867	MIDDLESEX COUNTY UTILITIES	0-30	SOUTH AMBOY CITY	402901	0741550	0.0			402901074155001			U	T	19550300	101.	230867
230868	MIDDLESEX COUNTY UTILITIES	0-33	SOUTH AMBOY CITY	402904	0741605	0.0			402904074160501			U	T	19550300	25.	230868
230869	MIDDLESEX COUNTY UTILITIES	0-35	SOUTH AMBOY CITY	402905	0741615	0.0			402905074161501			U	T	19550300	20.	230869
230870	MIDDLESEX COUNTY UTILITIES	0-37	SOUTH AMBOY CITY	402908	0741630	0.0			402908074163001			U	T	19550300	20.5	230870
230871	MIDDLESEX COUNTY UTILITIES	0-43	SOUTH AMBOY CITY	402910	0741643	13.4			402910074164301			U	T	19550300	21.	230871
230872	MIDDLESEX COUNTY UTILITIES	0-50	SOUTH AMBOY CITY	402915	0741654	25.5			402915074165401			U	T	19550300	34.	230872
230873	MIDDLESEX COUNTY UTILITIES	0-54	SOUTH AMBOY CITY	402925	0741740	28.5			402925074174001			U	T	19550300	30.5	230873
230874	MIDDLESEX COUNTY UTILITIES	0-57A	SOUTH AMBOY CITY	402926	0741822	118.			402926074182201			U	T	19550300	110.	230874
230875	MIDDLESEX COUNTY UTILITIES	0-57A6	SOUTH AMBOY CITY	402928	0741816	108.8			402928074181601			U	T	19550300	39.	230875
230876	MIDDLESEX COUNTY UTILITIES	0-58	SOUTH AMBOY CITY	402924	0741828	103.2			402924074182801			U	T	19550300	86.	230876
230877	MIDDLESEX COUNTY UTILITIES	SR-01	SAYREVILLE BORO	402802	0742212	6.0			402802074221201			U	T	19750314	40.	230877
230878	MIDDLESEX COUNTY UTILITIES	SR-02	SAYREVILLE BORO	402800	0742213	4.9			402800074221301			U	T	19750314	39.5	230878
230879	MIDDLESEX COUNTY UTILITIES	SR-03	SAYREVILLE BORO	402757	0742216	5.4			402757074221601			U	T	19750319	31.5	230879
230880	MIDDLESEX COUNTY UTILITIES	SR-04	SAYREVILLE BORO	402753	0742217	6.6			402753074221701			U	T	19750319	30.	230880
230881	MIDDLESEX COUNTY UTILITIES	SR-05	SAYREVILLE BORO	402748	0742218	3.0			402748074221801			U	T	19750317	30.	230881
230882	MIDDLESEX COUNTY UTILITIES	SR-06	SAYREVILLE BORO	402743	0742215	3.0			402743074221501			U	T	19750317	30.	230882
230883	MIDDLESEX COUNTY UTILITIES	SR-07	SAYREVILLE BORO	402739	0742215	3.4			402739074221501			U	T	19750319	31.5	230883
230884	MIDDLESEX COUNTY UTILITIES	SR-08	SAYREVILLE BORO	402735	0742215	3.6			402735074221501			U	T	19750319	36.	230884
230885	MIDDLESEX COUNTY UTILITIES	SR-09	SAYREVILLE BORO	402731	0742215	5.			402731074221501			U	T	19750318	30.	230885
230886	MIDDLESEX COUNTY UTILITIES	SR-10	SAYREVILLE BORO	402727	0742214	5.3			402727074221401			U	T	19750318	31.5	230886
230887	MIDDLESEX COUNTY UTILITIES	SR-11	SAYREVILLE BORO	402725	0742214	8.6			402725074221401			U	T	19750318	30.	230887
230888	MIDDLESEX COUNTY UTILITIES	SR-12	SAYREVILLE BORO	402721	0742213	0.			402721074221301			U	T	19750318	30.	230888
230889	MIDDLESEX COUNTY UTILITIES	SR-13	SAYREVILLE BORO	402719	0742213	10.8			402719074221301			U	T	19750319	30.	230889
230890	MIDDLESEX COUNTY UTILITIES	SR-14	SAYREVILLE BORO	402717	0742213	8.7			402717074221301			U	T	19750319	31.5	230890
230891	MIDDLESEX COUNTY UTILITIES	SR-15	SAYREVILLE BORO	402716	0742211	2.4			402716074221101			U	T	19750319	30.	230891
230892	MIDDLESEX COUNTY UTILITIES	SR-16	SAYREVILLE BORO	402712	0742212	9.0			402712074221201			U	T	19750321	31.5	230892
230893	MIDDLESEX COUNTY UTILITIES	SR-17	SAYREVILLE BORO	402709	0742212	7.2			402709074221201			U	T	19750321	31.5	230893
230894	MIDDLESEX COUNTY UTILITIES	SR-18	SAYREVILLE BORO	402705	0742209	7.8			402705074220901			U	T	19750407	32.	230894
230895	MIDDLESEX COUNTY UTILITIES	SR-19	SAYREVILLE BORO	402703	0742206	7.4			402703074220601			U	T	19750404	32.	230895
230896	MIDDLESEX COUNTY UTILITIES	SR-20	SAYREVILLE BORO	402659	0742201	10.			402659074220101			U	T	19750321	26.5	230896
230897	MIDDLESEX COUNTY UTILITIES	SR-21	SAYREVILLE BORO	402658	0742159	5.9			402658074215901			U	T	19750321	26.5	230897
230898	MIDDLESEX COUNTY UTILITIES	SR-23	SAYREVILLE BORO	402652	0742152	8.5			402652074215201			U	T	19750321	26.5	230898
230899	MIDDLESEX COUNTY UTILITIES	SR-24	SAYREVILLE BORO	402651	0742143	8.3			402651074214301			U	T	19750321	26.5	230899
230900	MIDDLESEX COUNTY UTILITIES	SR-25	SAYREVILLE BORO	402651	0742139	8.0			402651074213901			U	T	19750321	26.5	230900
230901	MIDDLESEX COUNTY UTILITIES	SR-26	SAYREVILLE BORO	402651	0742132	10.6			402651074213201			U	T	19750321	32.	230901
230902	MIDDLESEX COUNTY UTILITIES	SR-28	SAYREVILLE BORO	402647	0742129	3.5			402647074212901			U	T	19750325	26.5	230902
230903	MIDDLESEX COUNTY UTILITIES	SR-30	SAYREVILLE BORO	402642	0742129	5.6			402642074212901			U	T	19750408	32.	230903
230904	MIDDLESEX COUNTY UTILITIES	SR-31	SAYREVILLE BORO	402628	0742122	9.18			402628074212201			U	T	19750325	33.	230904
230905	MIDDLESEX COUNTY UTILITIES	SR-32	SAYREVILLE BORO	402623	0742121	9.74			402623074212101			U	T	19750325	37.	230905
230906	MIDDLESEX COUNTY UTILITIES	SR-34	SAYREVILLE BORO	402614	0742115	7.03			402614074211501			U	T	19750408	27.	230906
230907	MIDDLESEX COUNTY UTILITIES	SR-35	SAYREVILLE BORO	402608	0742113	8.84			402608074211301			U	T	19750328	31.5	230907
230908	MIDDLESEX COUNTY UTILITIES	SR-36	SAYREVILLE BORO	402605	0742112	8.25			402605074211201			U	T	19750328	21.5	230908
230909	MIDDLESEX COUNTY UTILITIES	SR-37	SAYREVILLE BORO	402593	0742107	7.19			402593074210701			U	T	19750328	27.	230909
230910	MIDDLESEX COUNTY UTILITIES	SR-39	SAYREVILLE BORO	402553	0742107	1.12			402553074210701			U	T	19750403	43.	230910
230911	MIDDLESEX COUNTY UTILITIES	SR-41	SAYREVILLE BORO	402543	0742108	8.66			402543074210801			U	T	19750326	22.	230911
230912	MIDDLESEX COUNTY UTILITIES	SR-42	SAYREVILLE BORO	402535	0742110	3.99			402535074211001			U	T	19750327	22.	230912
230913	MIDDLESEX COUNTY UTILITIES	SR-43	SAYREVILLE BORO	402527	0742111	9.0			402527074211101			U	T	19750328	27.	230913
230914	MIDDLESEX COUNTY UTILITIES	SR-44	SAYREVILLE BORO	402525	0742112	11.91			402525074211201			U	T	19750327	21.5	230914
230915	MIDDLESEX COUNTY UTILITIES	SR-46	SAYREVILLE BORO	402519	0742113	7.38			402519074211301			U	T	19750327	22.5	230915
230916	MIDDLESEX COUNTY UTILITIES	SR-47	SAYREVILLE BORO	402517	0742115	1.3			402517074211501			U	T	19750401	38.2	230916
230917	MIDDLESEX COUNTY UTILITIES	SR-48	OLD BRIDGE TWP	402516	0742116	3.27			402516074211601			U	T	19750327	21.5	230917
230918	MIDDLESEX COUNTY UTILITIES	SR-48C	OLD BRIDGE TWP	402514	0742114	2.61			402514074211401			U	T	19750411	24.	230918
230919	MIDDLESEX COUNTY UTILITIES	SR-53	OLD BRIDGE TWP	402509	0742123	4.0			402509074212301			U	T	19750411	22.	230919
230920	MIDDLESEX COUNTY UTILITIES	SR-53	OLD BRIDGE TWP	402505	0742129	11.99			402505074212901			U	T	19750328	21.5	230920
230921	MIDDLESEX COUNTY UTILITIES	SR-54	OLD BRIDGE TWP	402502	0742134	4.27			402502074213401			U	T	19750328	22.	230921
230922	MIDDLESEX COUNTY UTILITIES	SR-56	OLD BRIDGE TWP	402459	0742139	1.4			402459074213901			U	T	19750402	33.	230922
230923	MIDDLESEX COUNTY UTILITIES	SR-57	OLD BRIDGE TWP	402457	0742142	4.25			402457074214201			U	T	19750328	21.5	230923
230924	MIDDLESEX COUNTY UTILITIES	SR-58	EAST BRUNSWICK TWP	402454	0742149	7.93			402454074214901			U	T	19750331	22.	230924
230925	MIDDLESEX COUNTY UTILITIES	SR-60	EAST BRUNSWICK TWP	402449	0742201	15.3			402449074220101			U	T	19750331	27.	230925
230926	MIDDLESEX COUNTY UTILITIES	SR-65	EAST BRUNSWICK TWP	402406	0742118	15.			402406074211801			U	T	19760318	27.	230926
230927	MIDDLESEX COUNTY UTILITIES	SR-66	EAST BRUNSWICK TWP	402405	0742123	8.48			402405074212301			U	T	19760318	22.	230927
230928	MIDDLESEX COUNTY UTILITIES	SR-67	EAST BRUNSWICK TWP	402403	0742123	2.98			402403074212301			U	T	19760319	22.	230928
230929	MIDDLESEX COUNTY UTILITIES	SR-68	EAST BRUNSWICK TWP	402403	0742128	1.96			402403074212801			U	T	19760319	22.	230929
230930	MIDDLESEX COUNTY UTILITIES	SR-71	EAST BRUNSWICK TWP	402401	0742133	0.1			402401074213301			U	T	19760323	27.	230930
230931	MIDDLESEX COUNTY UTILITIES	SR-72	EAST BRUNSWICK TWP	402402	0742135	15.73			402402074213501			U	T	19760322	30.	230931
230932	PRINCETON UNIVERSITY	CORE HOLE 1	PLAINFIELD TWP	402058	0743559	98.			402058074355901	2315CKN		U	Z		120	230932
230																

UNIQUE ID	SITE OWNER	LOCAL ID	MUNICIPALITY	LAT	LONG	ALTITUDE	DEPTH	DIAMETER	STATION ID	AQUIFER	SCREENED INTERVAL	W S	DATE	PERMIT	DEPTH DRILLED	UNIQUE ID	
230744	MIDDLESEX COUNTY UTILITIES	L-10	SAYREVILLE BORO	402825	0742226	4.4			402825074222601			U	19750402		42.	230944	
230945	MIDDLESEX COUNTY UTILITIES	L-11	SAYREVILLE BORO	402828	0742232	10.8			402828074223201			U	19750409		42.	230943	
230946	MIDDLESEX COUNTY UTILITIES	L-12	SAYREVILLE BORO	402828	0742233	.07			402828074223301			U	19750410		42.	230946	
230947	MIDDLESEX COUNTY UTILITIES	L-13	SOUTH RIVER BORO	402829	0742234	.7			402829074223401			U	19750410		42.	230947	
230948	MIDDLESEX COUNTY UTILITIES	L-14	SOUTH RIVER BORO	402830	0742236	5.0			402830074223601			U	19750509		42.	230948	
230949	MIDDLESEX COUNTY UTILITIES	L-15	SOUTH RIVER BORO	402830	0742237	3.9			402830074223701			U	19750402		37.	230949	
230950	MIDDLESEX COUNTY UTILITIES	L-16	SOUTH RIVER BORO	402831	0742240	3.6			402831074224001			U	19750401		36.	230950	
230951	MIDDLESEX COUNTY UTILITIES	L-17	SOUTH RIVER BORO	402831	0742242	3.96			402831074224201			U	19750331		37.	230951	
230952	MIDDLESEX COUNTY UTILITIES	L-18	SOUTH RIVER BORO	402836	0742249	3.66			402836074224901			U	19750328		33.	230952	
230953	MIDDLESEX COUNTY UTILITIES	L-19	SOUTH RIVER BORO	402838	0742253	5.06			402838074225301			U	19750327		36.	230953	
230954	MIDDLESEX COUNTY UTILITIES	L-20	SOUTH RIVER BORO	402840	0742259	4.26			402840074225901			U	19750324		31.	230954	
230955	MIDDLESEX COUNTY UTILITIES	L-21	SOUTH RIVER BORO	402841	0742301	3.1			402841074230101			U	19750325		25.	230955	
230956	MIDDLESEX COUNTY UTILITIES	L-22	SOUTH RIVER BORO	402844	0742306	4.9			402844074230601			U	19750403		34.	230956	
230957	MIDDLESEX COUNTY UTILITIES	L-23	SOUTH RIVER BORO	402846	0742309	7.21			402846074230901			U	19750404		35.3	230957	
230958	MIDDLESEX COUNTY UTILITIES	L-24	SOUTH RIVER BORO	402849	0742311	7.6			402849074231101			U	19750403		40.	230958	
230959	MIDDLESEX COUNTY UTILITIES	L-25	SOUTH RIVER BORO	402851	0742313	11.16			402851074231301			U	19750327		21.	230959	
230960	MIDDLESEX COUNTY UTILITIES	L-26	SOUTH RIVER BORO	402853	0742316	11.34			402853074231601			U	19750326		23.	230960	
230961	MIDDLESEX COUNTY UTILITIES	L-27	SOUTH RIVER BORO	402854	0742318	10.2			402854074231801			U	19750324		39.	230961	
230962	MIDDLESEX COUNTY UTILITIES	L-28	SOUTH RIVER BORO	402855	0742320	10.0			402855074232001			U	19750324		18.	230962	
230963	MIDDLESEX COUNTY UTILITIES	L-29	SOUTH RIVER BORO	402856	0742326	7.4			402856074232601			U	19750324		30.	230963	
230964	MIDDLESEX COUNTY UTILITIES	L-30	SOUTH RIVER BORO	402855	0742329	7.7			402855074232901			U	19750324		30.	230964	
230965	MIDDLESEX COUNTY UTILITIES	L-31	SOUTH RIVER BORO	402854	0742333	20.9			402854074233301			U	19750321		50.	230965	
230966	MIDDLESEX COUNTY UTILITIES	L-32	SOUTH RIVER BORO	402854	0742336	17.			402854074233601			U	19750320		52.	230966	
230967	MIDDLESEX COUNTY UTILITIES	L-33	SOUTH RIVER BORO	402853	0742341	0.0			402853074234101			U	19750409		15.	230967	
230968	MIDDLESEX COUNTY UTILITIES	L-34	SOUTH RIVER BORO	402854	0742342	9.6			402854074234201			U	19750328		41.	230968	
230969	MIDDLESEX COUNTY UTILITIES	L-35	SOUTH RIVER BORO	402855	0742343	9.9			402855074234301			U	19750327		33.	230969	
230970	MIDDLESEX COUNTY UTILITIES	L-36	SOUTH RIVER BORO	402857	0742346	1.3			402857074234601			U	19750411		19.8	230970	
230971	MIDDLESEX COUNTY UTILITIES	L-37	SOUTH RIVER BORO	402903	0742347	6.3			402903074234701			U	19750319		28.	230971	
230972	MIDDLESEX COUNTY UTILITIES	L-38	NEW BRUNSWICK CITY	402906	0742346	6.5			402906074234601			U	19750318		27.	230972	
230973	NEW JERSEY HIGHWAY DEPT	NJ-01	SAYREVILLE BORO	403023	0741804	2.6			403023074180401			U	19380107		68.5	230973	
230974	NEW JERSEY HIGHWAY DEPT	NJ-02	SAYREVILLE BORO	403023	0741803	2.6			403023074180301			U	19380108		62.	230974	
230975	NEW JERSEY HIGHWAY DEPT	NJ-03	SAYREVILLE BORO	403026	0741804	2.6			403026074180401			U	19380111		78.5	230975	
230976	NEW JERSEY HIGHWAY DEPT	NJ-04	SAYREVILLE BORO	403025	0741802	2.6			403025074180201			U	19380112		66.	230976	
230977	NEW JERSEY HIGHWAY DEPT	NJ-05	SAYREVILLE BORO	403027	0741804	2.6			403027074180401			U	19380117		73.	230977	
230978	NEW JERSEY HIGHWAY DEPT	NJ-06	SAYREVILLE BORO	403027	0741803	2.6			403027074180301			U	19380115		93.	230978	
230979	NEW JERSEY HIGHWAY DEPT	NJ-07	SAYREVILLE BORO	403030	0741804	2.6			403030074180401			U	19380119		92.	230979	
230980	NEW JERSEY HIGHWAY DEPT	NJ-08	SAYREVILLE BORO	403031	0741802	2.6			403031074180201			U	19380118		81.	230980	
230981	NEW JERSEY HIGHWAY DEPT	NJ-09	SAYREVILLE BORO	403033	0741803	2.6			403033074180301			U	19380113		68.	230981	
230982	NEW JERSEY HIGHWAY DEPT	NJ-10	SAYREVILLE BORO	403033	0741802	2.6			403033074180201			U	19380111		74.5	230982	
230983	NEW JERSEY HIGHWAY DEPT	NJ-11	WOODBRIDGE TWP	403035	0741803	2.6			403035074180301			U	19380110		75.	230983	
230984	NEW JERSEY HIGHWAY DEPT	NJ-12	WOODBRIDGE TWP	403034	0741802	2.6			403034074180201			U	19380110		75.	230984	
230985	NEW JERSEY HIGHWAY DEPT	NJ-13	WOODBRIDGE TWP	403037	0741803	2.6			403037074180301			U	19380108		71.	230985	
230986	NEW JERSEY HIGHWAY DEPT	NJ-14	WOODBRIDGE TWP	403037	0741802	2.6			403037074180201			U	19380107		74.2	230986	
230987	NEW JERSEY HIGHWAY DEPT	NJ-15	WOODBRIDGE TWP	403037	0741803	2.6			403037074180301			U	19380114		74.6	230987	
230988	NEW JERSEY HIGHWAY DEPT	NJ-16	WOODBRIDGE TWP	403039	0741802	2.6			403039074180201			U	19380113		73.	230988	
230989	NEW JERSEY HIGHWAY DEPT	NJ-17	WOODBRIDGE TWP	403040	0741803	2.6			403040074180301			U	19380112		77.	230989	
230990	NEW JERSEY HIGHWAY DEPT	NJ-18	WOODBRIDGE TWP	403041	0741802	2.6			403041074180201			U	19380111		77.	230990	
230991	NEW JERSEY HIGHWAY DEPT	NJ-19	WOODBRIDGE TWP	403042	0741803	2.6			403042074180301			U	19380108		79.	230991	
230992	NEW JERSEY HIGHWAY DEPT	NJ-20	WOODBRIDGE TWP	403042	0741802	2.6			403042074180201			U	19380104		75.	230992	
230993	NEW JERSEY HIGHWAY DEPT	NJ-21A	SAYREVILLE BORO	403025	0741804	2.6			403025074180401			U	19380221		64.	230993	
230994	NEW JERSEY HIGHWAY DEPT	NJ-22	SAYREVILLE BORO	403025	0741803	2.6			403025074180301			U	19380221		62.3	230994	
230995	NEW JERSEY HIGHWAY DEPT	NJ-23	SAYREVILLE BORO	403028	0741804	2.6			403028074180401			U	19380221		80.	230995	
230996	NEW JERSEY HIGHWAY DEPT	NJ-24	SAYREVILLE BORO	403027	0741802	2.6			403027074180201			U	19380221		94.5	230996	
230997	NEW JERSEY HIGHWAY DEPT	NJ-25	SAYREVILLE BORO	403030	0741804	2.6			403030074180402			U	19380223		97.	230997	
230998	NEW JERSEY HIGHWAY DEPT	NJ-26	SAYREVILLE BORO	403030	0741803	2.6			403030074180301			U	19380221		81.	230998	
230999	NEW JERSEY HIGHWAY DEPT	NJ-27	SAYREVILLE BORO	403025	0741804	2.6			403025074180402			U	19380226		80.	230999	
231000	US ARMY CORPS OF ENGINEERS	DH-1	SAYREVILLE BORO	402845	0741529	0.0			402845074152901			U	19630600		41.7	231000	
231001	US ARMY CORPS OF ENGINEERS	DH-2	SAYREVILLE BORO	402813	0741512	0.0			402813074151201			U	19630600		22.	231001	
231002	US ARMY CORPS OF ENGINEERS	DH-3	OLD BRIDGE TWP	402823	0741436	0.0			402823074143601			U	19630600		40.1	231002	
231003	US ARMY CORPS OF ENGINEERS	DH-4	OLD BRIDGE TWP	402751	0741413	0.0			402751074141301			U	19630600		27.	231003	
231004	US ARMY CORPS OF ENGINEERS	DH-27A	SAYREVILLE BORO	402813	0741530	0.0			402813074153001			U	19630600		31.5	231004	
231005	US ARMY CORPS OF ENGINEERS	DH-28	OLD BRIDGE TWP	402755	0741458	0.0			402755074145801			U	19630600		31.5	231005	
231006	US ARMY CORPS OF ENGINEERS	DH-30	OLD BRIDGE TWP	402731	0741348	0.0			402731074134801			U	19630600		40.	231006	
231007	CLARK, ROMAN	DOMESTIC	EAST BRUNSWICK TWP	402414	0742623	120	66		402414074262301	211CDB	58	66	H	19830222	28-13318	78	231007
231008	YARDS, JOHN	DOMESTIC	SOUTH BRUNSWICK TWP	402157	0743525	110	51		402157074352501	211MRPA			H	19620816	28-04465	51	231008
231009	ZINSMEISTER, JACK	DOMESTIC	PLAINSBORO TWP	401844	0743448	60	79		401844074344801	211FRNG	76	79	H	19670901	28-06237	81	231009
231010	MAN. & ENG. CORP.	MVE2	SAYREVILLE BORO	402833	0742041	6.			402833074204101			U	19290000		63.	231010	
231011	MAN. & ENG. CORP.	MVE2A	SAYREVILLE BORO	402819	0742046	22.			402819074204601			U	19290000		73.6	231011	
231012	MAN. & ENG. CORP.	MVE2B	SAYREVILLE BORO	402806	0742044	35.			402806074204401			U	19290000		163.	231012	
231013	MAN. & ENG. CORP.	MVE2C	SAYREVILLE BORO	402806	0742044	35.			402806074204401			U	19290000		163.	231013	
231014	MAN. & ENG. CORP.	MVE3	SAYREVILLE BORO	402739	0742027	100.			402739074202701			U	19290000		311.	231014	
231015	HERCULES POWDER CO	TEST WELL 5	SAYREVILLE BORO	402819	0742107	28.	128.		402819074210701	211FRNG	120.9	128.	U	19380113		129.	231015
231016	E.I. DUPONT	LAYNE #4	SAYREVILLE BORO	402722	0741942	88.	277.5		402722074194201	211FRNG	221.58	257.	U	19270807		292.	231016
231017	E.I. DUPONT	LAYNE #4	SAYREVILLE BORO	402722	0741942	88.	277.5		402722074194201	211FRNG	267.17	277.5	U			292.	231017
231018	SAYRE & FISHER	29A	SAYREVILLE BORO	402818	0742037	16.			402818074203701			U			77.5	231018	
231019	E.I. DUPONT	1-A	SAYREVILLE BORO	402840	0742037	5.0			402840074203701			U			80.5	231019	
231020	E.I. DUPONT	2-B	SAYREVILLE BORO	402838	0742022	10.			402838074202201			U			106.42	231020	
231021	E.I. DUPONT	3-C	SAYREVILLE BORO	402836	0742014	15.			402836074201401			U			83.25	231021	

UNIQUE ID	SITE OWNER	LOCAL ID	MUNICIPALITY	LAT	LONG	ALTITUDE	DEPTH	DIAMETER	STATION ID	AQUIFER	SCREENED INTERVAL	W S	DATE	PERMIT	DEPTH DRILLED	UNIQUE ID	
231033	NATIONAL LEAD	19-5	SAYREVILLE BORO	40.2933	0741846	18.			5.	402933074184601		U	19410205		111.5	231033	
231034	NATIONAL LEAD	20-T	SAYREVILLE BORO	40.2937	0741840	18.			5.	402937074184001		U	19410203		113.67	231034	
231035	CALIFORNIA REFINING	TEST WELL #4	PERTH AMBOY CITY	40.3210	0741621	25.			6.	403210074162101		U	19510905	26-00111		231035	
231036	CALIFORNIA REFINING	TEST WELL #6	PERTH AMBOY CITY	40.3200	0741605	37.			6.	403200074160501		U	19510905	26-00122	106.	231036	
231037	CALIFORNIA REFINING	TEST WELL #7	PERTH AMBOY CITY	40.3156	0741626	54.			6.	403156074162601		U	19510905	26-00125	136.	231037	
231038	CALIFORNIA REFINING	TEST WELL #8	PERTH AMBOY CITY	40.3214	0741714	66.			6.	403214074171401		U	19510905	26-00126	113.	231038	
231039	CALIFORNIA REFINING	TEST WELL #9	PERTH AMBOY CITY	40.3138	0741608	33.			6.	403138074160801		U	19510905	26-00123	116.	231039	
231040	CALIFORNIA REFINING	TEST WELL #15	PERTH AMBOY CITY	40.3156	0741622	56.			6.	403156074162201		U	19510905	26-00257	139.5	231040	
231041	MIDDLESEX COUNTY UTILITIES	MONITORING #1	SAYREVILLE BORO	40.2807	0742204	5.	58.		211FRNG		48.	58.	U	19780200	28-10143	76.	231041
231042	MIDDLESEX COUNTY UTILITIES	MONITORING #2	SAYREVILLE BORO	40.2757	0742214	5.	57.		211FRNG		47.	57.	U	19780200	28-10142	68.	231042
231043	DOW JONES CO	BACKUP-2	SOUTH BRUNSWICK TWP	40.2607	0743510	120	150		231LCKG		73	150	U	19790700	28-11131	130	231043
231044	MAGYAR SAVINGS & LOAN ASS	MAGYAR 1	SOUTH BRUNSWICK TWP	40.2630	0743206	130	185		231BRCK		50	185	C	W 19691104	28-06766	185	231044
231045	MAGYAR 1		SOUTH BRUNSWICK TWP	40.2630	0743206	130	185		231BRCK				C	W		185	231045
231046	NJ DEPT OF TRANSPORTATION	SAND HILLS 1	SOUTH BRUNSWICK TWP	40.2434	0743238	240	245		231LCKG		71.83	245	W	19590629	28-03473	245	231046
231047	CITIES SERVICE CO.	15-1970	SOUTH BRUNSWICK TWP	40.2301	0743320	75	342		231LCKG		67	342	N	W 19700831	28-06486	342	231047
231048	COLUMBIAN CHEMICALS	15-1970	SOUTH BRUNSWICK TWP	40.2301	0743320	75	342		231LCKG				N	W		342	231048
231049	DIKEN, JR. FD	DIKEN 1	NORTH BRUNSWICK TWP	40.2602	0742910	110	85		231BRCK		50	85	U	19810717	28-12317	85	231049
231050	DIKEN, JR. FD	DIKEN 1	NORTH BRUNSWICK TWP	40.2602	0742910	110	85		231BRCK				U			85	231050
231051	CARDONE, ANGELO C	CARDONE	NORTH BRUNSWICK TWP	40.2757	0742928	120	74		231BRCK		25	74	W	19640826	28-05084	74	231051
231052	CARDONE, ANGELO C	CARDONE	NORTH BRUNSWICK TWP	40.2757	0742928	120	74		231BRCK				W			74	231052
231053	REVEY, EMERY J.	SOD FARM WELL	NORTH BRUNSWICK TWP	40.2721	0743031	100	234		231BRCK		26	234	W	19800921	28-11860	234	231053
231054	RUIGERS UNIVERSITY	COOK FARM HOUSE	NORTH BRUNSWICK TWP	40.2804	0742539	50	160		231BRCK		53	160	W	19740227	28-17373	160	231054
231055	RUIGERS UNIVERSITY	COOK FARM HOUSE	NORTH BRUNSWICK TWP	40.2804	0742539	50	160		231BRCK				W			160	231055
231056	GARY MANUFACTURING	INDUSTRIAL-1977	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK		54	125	N	W 19771000	25-19397	125	231056
231057	RUIGERS UNIVERSITY	INDUSTRIAL-1977	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				N	W		125	231057
231058	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK		55	300	U	19800630	25-21440	300	231058
231059	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231059
231060	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231060
231061	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231061
231062	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231062
231063	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231063
231064	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231064
231065	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231065
231066	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231066
231067	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231067
231068	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231068
231069	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231069
231070	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231070
231071	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231071
231072	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231072
231073	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231073
231074	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231074
231075	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231075
231076	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231076
231077	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231077
231078	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231078
231079	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231079
231080	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231080
231081	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231081
231082	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231082
231083	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231083
231084	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231084
231085	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231085
231086	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231086
231087	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231087
231088	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231088
231089	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231089
231090	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231090
231091	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231091
231092	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231092
231093	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231093
231094	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231094
231095	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231095
231096	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231096
231097	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125	231097
231098	RUIGERS UNIVERSITY	RUIGERS GOLF COU	NEW BRUNSWICK CITY	40.2806	0742839	90	125		231BRCK				U			125</	

REFERENCE NO. 16

TO: EL Beth File (J030)

DATE: March 26, 1992

FROM: Claire Bannix

COPIES: —

SUBJECT: Potable water supply wells located within 4 miles of the EL Beth site.

REFERENCE: See below.

Summary: Potable water supply wells that are located within a 4-mile radius of the EL Beth site have been identified and the number of people served have been determined. Private wells and public wells (including emergency supply wells) have been addressed.

The Sayreville Water Dept. and South Amboy Water Dept. wells are located within 4 miles of the EL Beth site, across the Raritan River. The South Amboy wells currently are not in use; they are reserved for emergency use only. South Amboy obtains its water from the Perth Amboy system. No other public potable water supply wells are located within 4 miles of the site. Other municipalities in the area obtain their water from wells located outside of the site's 4-mile radius, or from surface water supplies, which are not located along the site's 15-mile superfund route. USGS data for wells with production rates greater than 75 gal/minute in Middlesex County includes, within 4 miles of the EL Beth site, three domestic wells. Two of the wells are reported to be not in use; one is located 4 miles from the EL Beth site, and its current status has not been confirmed.

Wells and populations served are listed on the following page. A list of references is given, and references are attached.

(continued on reverse)

Page 2 of 25

Potable Water Supply Wells Located Within 4 miles of the EL Beth Site.

Distance Category, miles	Potable Water Supply Well Identification	Population Served	Comments
0.0 to 0.25	(none)	0	—
> 0.25 to 0.50	(none)	0	—
> 0.50 to 1.0	(none)	0	—
> 1.0 to 2.0	(none)	0	—
> 2.0 to 3.0	South Amboy public wells	8,500	These wells currently are not in use; they are being maintained for emergency use only. South Amboy obtains its water from the Beth Amboy supply. These wells are located across the river from the EL Beth site Paritan
> 3.0 to 4.0	Sayreville public wells	approximately 12,000	Five wells; 2 draw from the aquifers of Concord (Farrington) and 3 draw from the more shallow, Old Bridge aquifer. The water from the deep and shallow wells at this location is mixed. Recharge water from the South River is also mixed with the well water.
	Private well approx. (Estimate 4 people) 4 miles from EL Beth site.		Current status not confirmed

TO: EL Both File

DATE: March 26, 1992

FROM: Claire Bampfis

COPIES: -

SUBJECT: Potable water supply wells located within 4 miles of the EL Both site.

REFERENCE: The following references document potable water supply wells within 4 miles of the EL Both site, and those communities served by other sources:

1. Telecon Note: Conversation between Mr. Joe Rudy, Sayreville Water Dept., and Claire Bampfis, HNUS, March 16, 1992.
2. Telecon Note: Conversation between Kathy, South Amboy Water Dept., and Claire Bampfis, HNUS, March 13, 1992.
3. Telecon Note: Conversation between Mrs. Myers, Middlesex Water Company, March 13, 1992 and Claire Bampfis, HNUS, March 13, 1992.
4. Telecon Note: Conversation between Mr. Rich Sadowski, Elizabethtown Water Company, and Claire Bampfis, HNUS, March 10, 1992.
5. Telecon Note: Conversation between Mr. William Lund, Edison Engineering Dept., and Claire Bampfis, HNUS, March 13, 1992.
6. Telecon Note: Conversation between Mr. Turan Ramadan, Perth Amboy Water Dept., and Claire Bampfis, HNUS, March 13, 1992.
7. Telecon Note, (#2); Conversation between Mr. Turan Ramadan, Perth Amboy Water Dept., and Claire Bampfis, HNUS, March 13, 1992.
8. Telecon Note; Conversation between Mr. Joe Rudy, Sayreville Water Dept., and Diane Minnavage, HNUS, October 24, 1991.
9. Telecon Note: Conversation between Mr. Jerry Gairot, South Amboy Water Dept., and Diane Minnavage, October 22, 1991.
10. Telecon Note: Conversation between Mr. Richard Mercharic, South Amboy Water Dept., and Maria Cales, HNUS, Feb 21, 1992.
11. Telecon Note: Conversation between Mr. Joe Ritter, Middlesex Water Company, and Edmund Knysol, Jr., NUS, September 25, 1990.

Continued -

Potable Water Supply Wells Located Within 4 miles of the El Beth Site.

12. Telecon Note: Conversation between Mr. Frank Falco, Middlesex Water Company, and Sue Lenczyk, NUS, February 9, 1990.

13. Telecon Note: Conversation between Mr. Guy Lighton, Woodbridge Twp. Engineering Office, and Edmund Knyf, Jr., NUS, Sept 25, 1990.

14. Telecon Note: Conversation between Mr. Jay Elliott, Dept. of Health and Human Resources, Edison, and Sue Lenczyk, NUS, March 15, 1990.

15. Telecon Note: Conversation between Mr. Jay Elliott, Edison Dept. of Health and Human Services, and Sue Lenczyk, NUS, March 19, 1990.

~~16. Telecon Note: Conversation between Mr. Jay Elliott, Edison Health Dept., and Sue Lenczyk, NUS, March 19, 1990. cs~~

16. Telecon Note: Conversation between City Engineer, Township of Edison, and D. Lamond, NUS, June 19, 1986.

17. Telecon Note: Conversation between Mr. Havrett, S. Amboy Water Dept., and Bob Cortagallo, NUS, August 30, 1990.

18. Telecon Note: Conversation between Mrs. Girsky, well owner in Fords, N.J., and Bruce Sanders, NUS, July 11, 1990.

CONTROL NO.:

J030

DATE:

March 16, 1992

TIME:

1040

DISTRIBUTION:

EL Both file

Page 1012

BETWEEN:

Mr. Joe Rudy

OF:

Sayreville Water Dept.

PHONE:

(908) 390-7067

AND:

Claire Barupis

(NUS)

DISCUSSION:

Mr. Rudy said that the Sayreville Water Dept. has 2 plants, in town.

One is located at Bordentown Avenue + Journey Mill Road; the wellfield is located right behind the plant; it occupies a radius of about 4 acres and consists of 11 wells.

The other plant is located in the Morgan section of Sayreville Township, at Route 35 South - it's about 1/2 mile north of the border with Old Bridge, by Gordon Ave, about 1 block from Route 35. There are 5 wells at this plant; 3 are shallow and 2 are deep. The shallow wells draw from the Old Bridge aquifer, and are 125 to 130 feet deep, and screened at about 80 feet deep; R' well at about 90 feet and T' well at about 83 feet. The deep wells draw from the Farrington aquifer; their depth is about 280 feet; The water level, well S' is about 250 feet deep and screen is about 34 feet long.

Regarding the Old Bridge (shallow) wells, he said they are not to pump below depth of 100 feet.

ACTION ITEMS:

He said the supply is a loop system; the 2 water plants serve 2 sections, and also, the Dept. purchases 2 million gallons per day from Middlesex Water Co. He said that very seldom does Morgan well water go to the Bordentown section, because water pressure from the Middlesex Water Co. supply prevents this. He said that a total population of 38,000 is served. He estimates that the plant in the Morgan section

CONTROL NO.:

J030

DATE:

March 16, 1992

TIME:

1040

DISTRIBUTION:

EL Beth file

Page 2 of 2

BETWEEN:

Mr. Joe Rudy

OF:

Sayreville Water
Dept.

PHONE:

(908) 390-7067

AND:

Claire Barupis

(NUS)

DISCUSSION:

serves approximately one-third of this population, or 12,000 people. He said that in the summer (peak) season, the Morgan system supplies 3.2 MGD (million gallons per day), the Bordentown system supplies about 4 MGD and Middlesex Water Co. supplies 2 MGD. He said the relative amount supplied by Middlesex Water Co., a surface water supply, is higher in winter.

He said that Sayreville Water Dept. also uses about 1 MGD of surface water from recharge lagoons - pumped from the South River to lagoons - the lagoon water is mixed with well water.

ACTION ITEMS:

Note: the water supply located in the Morgan section is located between 3 and 4 miles from the EL Beth site.

CONTROL NO.: J030	DATE: March 13, 1992	TIME: 1425
DISTRIBUTION: E L Beth file		
BETWEEN: Kathy	OF: South Amboy Water Dept.	PHONE: (908) 721-1211
AND: Claire Brangia		
DISCUSSION: Kathy said that currently, South Amboy is still buying its water from Perth Amboy. South Amboy is not using any of its own wells. The South Amboy ^{water} treatment plant would open for emergency use only. She said that Mr. Garnet will return in about 20 minutes, and agreed that if he has further information, such as when the South Amboy water Dept wells may be used again, he will return my call.		
ACTION ITEMS:		

CONTROL NO.:

JO30

DATE:

March 13, 1992

TIME:

1618

DISTRIBUTION:

EL Beth file

BETWEEN:

Mrs. Myers

OF:

Middlesex
Water Company

PHONE:

(908) 634-1500

AND:

Claire Barupis

(NUS)

DISCUSSION:

Mrs. Myers said that Middlesex Water Co. has no emergency supply wells in Edison or Woodbridge.

She said that this water company's wells are located in South Plainfield and at North Tingley and South Tingley Lakes in Edison.

ACTION ITEMS:

Note that Middlesex Water Co. wells are not located within 4 miles of the EL Beth site.

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO.:

J030

DATE:

March 10, 1992

TIME:

1510

DISTRIBUTION:

E.L. Beth file

BETWEEN:

Mr. Rich Sadowski

OF:

Elizabethtown
Water Company

PHONE:

(908) 654-1234

AND:

Claire Bampfie

(NUS)

DISCUSSION:

Mr. Sadowski said that Elizabethtown Water Company does not have any wells in the following towns: Edison, Woodbridge (or Port Reading, Sewaren, Hopelawn, Fords, Kearsby), Sayreville and South Amboy.

ACTION ITEMS:

CONTROL NO.:

J030

DATE:

March 13, 1992

TIME:

1553

DISTRIBUTION:

EL Beth file

BETWEEN:

William Lund

OF:

Edison Engineering
Dept. (Director)

PHONE:

(908) 287-0900

AND:

Claire Barup

(NUS)

DISCUSSION:

Mr. Lund said that it has been many years since
emergency supply wells in Edison were used.

ACTION ITEMS:

CONTROL NO.:

JO30

DATE:

March 13, 1992

TIME:

1450

DISTRIBUTION:

EL Beth file

BETWEEN:

Turan Ramadan

OF: Perth Amboy Water
Dept. (Superintendent)

PHONE:

(908) 442-2397

AND:

Clair Rumpo

(NUS)

DISCUSSION:

I phoned to confirm the locations of Perth Amboy water supply wells (public potable water supply):

He said that the City of Perth Amboy has wells near Tennent Pond in Old Bridge, which pump from the Old Bridge Sand; Well Nos. 5, 6 and 7 are at the north side of the pond, and Well No. 8 is southeast of the pond. Also, Perth Amboy has what are called collector wells (also called 'Ramney' well), near Deep Run in Old Bridge, about 4000 feet south of Tennent Pond - this also draws from the Old Bridge Sand. He said that the City of Perth Amboy has no emergency wells in Woodbridge. The Perth Amboy water system serves the City of Perth Amboy, and is shared with South Amboy.

Mr. Ramadan noted that there is a reservoir at Florida Grove Road. He asked that I phone back at about 4:00, as he must now go to a meeting; we can complete the discussion when I call back.

ACTION ITEMS:

CONTROL NO.:

J030

DATE:

March 13, 1992

TIME:

1605

DISTRIBUTION:

EL Beth File

BETWEEN:

Mr. Turan Ramadan

OF: Perth Amboy Water
Dept. (Superintendent)

PHONE:

(908) 1442-2397

AND:

Claire Baruffa

(NUS)

DISCUSSION:

(Continuation of telecon at 1450 hrs on March 13, 1992)

Mr. Ramadan said that the City of Perth Amboy has a finished water reservoir located in Perth Amboy, at Florida Grove Road. (Mr. Ramadan said that it is 5 acres in size, and is the largest reservoir in the U.S.A.). The reservoir serves only Perth Amboy ~~and South Amboy~~. Water from the Perth Amboy public supply wells is treated, and, the reservoir water is from this system.

Also, there is a groundwater recharge reservoir at the Ranney well; he said that when the Ranney well is done it will be very large (88 acres) and it will be supplied by this reservoir.

ACTION ITEMS:

Note that the City of Perth Amboy public water supply wells are located more than 4 miles from the EL Beth site (the wells are near, and south of, Tennent Pond in Old Bridge).

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO.: J008	DATE: October 24, 1991	TIME: 1426
DISTRIBUTION: South Amboy Gas Works		
BETWEEN: Joe Rudy	OF: Sayreville Water Department	PHONE: (908) 390-7067
AND: Diane Minsavage		

(NUS)

DISCUSSION:

I called Mr. Rudy to determine what municipal wells are in service and the population served by Sayreville Water Department. I told Mr. Rudy, that I had plotted wells listed on a 1989 DEP printout, and had come up with two well-fields in use within 4 miles of the site. Mr. Rudy said that the Bordentown Water Plant, uses wells A through L (M is not in use), all of which are in service (E and G are having problems and will be redrilled shortly), the total volume from this well field is approximately 2.5 Mgal/day; the Morgan well field (wells P through T) is in service, (P and S tap into the Farrington and usually only one of the two is in use at a given time), this field produces approximately 2M gal/day. Sayreville also purchases 2M gal/day from Middlesex, and has four 11M gallon reserves. While water is not blended, Sayreville operates a circular system (interconnected) which serves approximately 38,000 people. JDM.

ACTION ITEMS:

The Bordentown wells are 3-4 miles from the site and serve 38.46% of Sayreville's customers; population served is 14,615.*

The Morgan wells are 1-2 miles from the site and serve 30.77% of Sayreville's customers; population served is 11,693.*

* These values were calculated based on pumpage.

Note: Only 3 of the Morgan wells tap into the Old Bridge Sand aquifer; therefore the population served was recalculated \Rightarrow 8,770 people (75% of Morgan)

(13)

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO.:

J008

DATE:

October 22, 1991

TIME:

1138

DISTRIBUTION:

South Amboy Gas Works

BETWEEN:

Jerry Garnet

OF:

South Amboy Water
Department

PHONE:

(908) 721-1211

AND:

Diane Minsavage

(NUS)

DISCUSSION:

I called Mr. Garnet to ascertain the water service available in South Amboy. Mr. Garnet stated that while South Amboy has two shallow groundwater wells and a water treatment plant; however, they are currently not using the wells but are purchasing all of their water from Perth Amboy. The South Amboy Water Department serves approximately 8,000 people (7,800 plus "change").

JDM

ACTION ITEMS:

South Amboy wells "SAWD10" and "SAWD9A" are operational, although not in use.

CONTROL NO:

02-9001-10

DATE:

2/21/90

TIME:

9:15 AM

DISTRIBUTION:

File - Celotex (A)

BETWEEN:

Richard Muchanic

OF:

S. Amboy Water Dept

PHONE:

(201) 721-1211

AND:

Maria Coker

DISCUSSION:

(NUS)

I called Richard Muchanic back to get information on the two wells maintained by the S. Amboy Water Department. He gave me the following information:

- 1.) The wells tap the Oldbridge Aquifer Sands at 48 ft.
- 2.) The well permits numbers are 26-4212 and 26-4078
- 3.) The population served is 8500
- 4.) The wells are located at Lower Broadway and the Public Works Compound of S. Amboy

5.) The water from the two wells is pumped into a reservoir where it receives pretreatment (PH disinfection). It is then pumped to ~~the~~ water tower where it is mixed with water from Sayreville and Perth Amboy.

- 6.) In the case that the water from the wells is contaminated, Sayreville and Perth Amboy wells are the alternative sources of water.

ACTION ITEMS:

- 7.) A third well is permitted for South Amboy. However, this well hasn't been tapped in five years due to high levels of iron. These levels of iron are attributable to the composition of the aquifers.

- 8.) Mr. Muchanic also told me that he strictly

2/21/10 at 4:15 PM

adheres to the NJDEP mandate 208 which requires testing for 16 organics twice a year and inorganics (heavy metals, nitrates) every 2 years.

The tests have so far come up negative.

He said that his only worry is the possibility of salt water intrusion.

CONTROL NO.:

02-9008-04

DATE:

9/25/90

TIME:

1520

DISTRIBUTION:

To File: NL Industries Titanium Pigment Plants
Re: Woodbridge Township Water Supply

BETWEEN:

Joe Ritter

OF:

Middlesex
Water Co.

PHONE:

(201) 634-1500

AND:

Edmund Knyfs Jr.

(NUS)

DISCUSSION:

Joe indicated that Woodbridge Township is served by wells and surface water. Areas of Woodbridge Twp north of Highway 27 are served by wells located near Spring Lake in South Plainfield. Areas south of Highway 27 are served by surface water withdrawal from the Delaware and Raritan Canal across from the Rutgers University campus. The 1980 census population for Woodbridge Township is approximately 90,100.

Edmund Knyfs Jr.

9/25/90

ACTION ITEMS:

wyl
02-9002-0

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

02-9002-01 / N3DU\$5

DATE:

February 9, 1990

TIME:

1305

DISTRIBUTION:

Revlon Inc.

BETWEEN:

Mr. Frank Falco

OF:

Middlesex Water Co.

PHONE:

(201) 634-1500

AND:

Sue Lenczyk

DISCUSSION:

I called Mr. Falco to confirm the locations of the Middlesex Water Co. supply wells.

He mentioned four well fields in South Plainfield: Spring Lake Street, Sprague Street, Maple Avenue, and Park Avenue; and two well fields in Edison: North Tingley Lane and South Tingley Lane.

In addition, there is the surface water intake along the Delaware and Raritan Canal.

ACTION ITEMS:

The information above supports the U.S.G.S. list of wells in Middlesex County but conflicts with info in the RCRA Facility Assessment prepared ^{by} the Bureau of Planning and Assessment, NJDEP, which states that the Middlesex Water Co. has a public supply well within 1.5 miles of the Revlon, Inc. site.

CONTROL NO.:

02-9008-04

DATE:

9/25/90

TIME:

1510

DISTRIBUTION:

To File: NL Industries Titanium Pigment Plant

Re: Drinking Water Supply for Woodbridge Township

BETWEEN:

Guy Leighton

OF:

Woodbridge Twp. -
Engineering

PHONE:

(201)388-9797

AND:

Edmund Knyfel Jr.

(NUS)

DISCUSSION:

Guy indicated that all the drinking water for Woodbridge Township is supplied by the Middlerex Water Company. He suggested calling them to get specific information about the location of the water supply.

Edmund Knyfel Jr.
9/25/90

ACTION ITEMS:

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO.:

02-9002-01 / NJDV

DATE:

March 15, 1990

TIME:

0815

DISTRIBUTION:

Revlon Inc.

BETWEEN:

Mr. Jay Elliot, Chief Sanitary Inspector

OF: Dept of Health and Human Resources
Edison

PHONE:

(201) 287-0900 x 476

AND:

Sue Lenczyk

DISCUSSION:

(NUS)

I asked Mr. Elliot about the computer sheets he had given me, listing the wells within a 3-mile radius of Revlon. I mentioned that some of the wells had the word "private" listed next to them, but that many of the wells had blanks next to them. He responded that the health department has information that wells are there, but it does not know for certain whether they are being used. They may be in use, they may not. To compile the computer sheets, the health department drew from different sources, including historical records kept by the NJDEP. Mr. Elliot said that the more information that is listed next to the well, the more likely that it is currently being used.

Mr. Elliot also informed me that they occasionally have requests to sample private wells for volatile organics. He said that they have yet to find a problem of contamination with volatile organics. He added that occasionally there seems to be a problem, but only with a newly drilled well. Those problems stemmed from improper methods of decontaminating equipment. When they resampled after equipment was properly decontaminated, the well samples came up clean.

ACTION ITEMS:

Sue Lenczyk 3/15/90

(2)

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

02-9002-01/NJDU

DATE:

March 19, 1990

TIME:

0 850

DISTRIBUTION:

Reulon Inc.

(Page 1 of 2)

BETWEEN:

Mr. Jay Elliot, Chief Sanitary Inspector

OF: Edison Department of Health and Human Services

PHONE:

(201) 287-0900 x 476

AND:

Sue Lenczyk

DISCUSSION:

I asked Mr. Elliot about the four public community wells listed on the computer printout of wells in Edison Township. He said that those wells are run by Edison Township and are not in use. I asked when they were last used, and he said "it has been quite some time." The wells are capped and available; they are not abandoned. During the water shortage a few years ago, the township had to develop a contingency plan in case of a more severe shortage. It was discovered that it would not be terribly difficult to get them back on line. However, as for now, they are in a field, the grass is grown around them, and they are not used.

I then inquired about the five public noncommunity wells. He said that the designation "public noncommunity" means a water supply that is not a public supply but is used by people other than just the residents. One belongs to the Roosevelt Hotel;

another is used by Roosevelt Hospital. The one at the hospital is used daily. The hospital does use public supply from Middlesex Water Company, but in the mornings and evenings when water pressure is low due to heavy use, the 500-foot-deep well used by the hospital will kick in automatically. Two other wells belong

(continued on page 2)

(21)

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

02-9002-01/NJDV

DATE:

March 19, 1990

TIME:

0850

DISTRIBUTION:

Reulon Inc. (Page 2 of 2)

BETWEEN:

Mr. Jay Elliot

OF:

Edison Health
Dept.

PHONE:

(201) 287-0900 x476

AND:

Sue Lenczyk

DISCUSSION:

to swim clubs and are used seasonally. Water from the wells is used for the pool, the concession stands, and the showers. There is another well used by a Baptist church (used on Wednesday nights and Sundays). One well is being added to this designation of public noncommunity: a house at the corner of Brunswick and Plainfield Avenues has been converted to a real estate office.

My final question to Mr. Elliot was whether the people drinking from private wells have the capability of having a hookup with the community supply. He said yes - in virtually every case. He said that at least 95 percent (and that is probably a low estimate) have the option to tie in with the municipal water system.

ACTION ITEMS:

CONTROL NO:

02-3512-01

DATE:

6/19/86

TIME:

1120

DISTRIBUTION:

File (Heller Properties)

BETWEEN:

City Engineer

OF:

Township of Edison

PHONE:

(201) 287-0900

AND:

D-LAMUND

(NUS)

DISCUSSION:

Water supply for Edison. There are several public supply wells located in Edison however they are not utilized except in an emergency as backup supplies. Water ^{Co.} in Edison just distributes water from the Elizabethtown Water ^{Co.} Co. There are other wells in area (private wells) which are used for irrigation ~~and~~ industry and monitoring.

ACTION ITEMS:

CONTROL NO.:

02-9001-10

DATE:

August 30, 1940

TIME:

2:40

DISTRIBUTION:

File - Celotex (A)

BETWEEN:

Mr. Garnett

OF:

S. Ambry Water Dept.

PHONE:

(201) 721-1211

AND:

Bob Cantagallo

(NUS)

DISCUSSION:

Mr. Garnett informed me that J. McKen receives
water from the South Ambry Water Company

ACTION ITEMS:

0002-
02-9004-17

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO.

DATE

TIME

02 - 9004-17

July 11, 1990

4:10

DISTRIBUTION

Arthur Kill Urban Industrial Park
\$475NJGFIS

BETWEEN:

OF

PHONE:

Mrs. Ciraky

65 Jenson Ave.

Fords, New Jersey

(201) 738-0898

AND:

Bruce Sanders

(NUS)

DISCUSSION:

Spoke to Mrs. Ciraky concerning the
potable groundwater well located on her
property. She stated that the well has not
been used for several years now. She said
the well caved in and it has not been repaired.

ACTION ITEMS:

REFERENCE NO. 17

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO.:

9061

DATE:

02/14/92

TIME:

11:30

DISTRIBUTION:

- Tooley's Garage
- Staff

BETWEEN:

Dan Van Abs

OF: NJDEP, Bureau of
Water Supply Planning

PHONE:

(609) 633-1179

AND:

K. Campbell

(NUS)

DISCUSSION:

Mr. Van Abs returned my call of 02/13/92, and provided the following information on Wellhead Protection Area (WHPA) delineation for the State of New Jersey:

- WHPAs are not yet delineated for the state. The Bureau of Water Supply Planning is working on a draft delineation (a multi-year process).

Mr. Van Abs will put HNEC on their mailing list to receive updates on WHPA regulations.

ACTION ITEMS:

K. Campbell 2/14/92

REFERENCE NO. 18

Friday
December 14, 1990

Federal Register

Part II

Environmental Protection Agency

40 CFR Part 300

Hazard Ranking System; Final Rule

TABLE 3-6.—HYDRAULIC CONDUCTIVITY OF GEOLOGIC MATERIALS

Type of material	Assigned hydraulic conductivity* (cm/sec)
Clay, low permeability till (compact unfractured till); shale; unfractured metamorphic and igneous rocks	10^{-9}
loesses; silt clays; sediments that are predominantly silts; moderately permeable till (fine-grained, unconsolidated till, or compact till with some fractures); low permeability limestones and dolomites (no karst); low permeability sandstone; low permeability fractured igneous and metamorphic rocks	10^{-8}
Sands; sandy silts; sediments that are predominantly sand; highly permeable till (coarse-grained, unconsolidated or compact and highly fractured); peat; moderately permeable limestones and dolomites (no karst); moderately permeable sandstone; moderately permeable fractured igneous and metamorphic rocks	10^{-6}
Gravel; clean sand; highly permeable fractured igneous and metamorphic rocks; permeable basalt; karst limestones and dolomites	10^{-4}

* Do not round to nearest integer.

TABLE 3-7.—TRAVEL TIME FACTOR VALUES *

Hydraulic conductivity (cm/sec)	Thickness of lowest hydraulic conductivity layer(s)* (feet)			
	Greater than 3 to 5	Greater than 5 to 100	Greater than 100 to 500	Greater than 500
Greater than or equal to 10^{-2}	35	35	35	25
Less than 10^{-2} to 10^{-3}	35	25	15	15
Less than 10^{-3} to 10^{-4}	15	15	5	5
Less than 10^{-4}	5	5	1	1

* If depth to aquifer is 10 feet or less or if, for the interval being evaluated, all layers that underlie a portion of the sources at the site are karst, assign a value of 35.

* Consider only layers at least 3 feet thick. Do not consider layers or portions of layers within the first 10 feet of the depth to the aquifer.

Determine travel time only at locations within 2 miles of the sources at the site, except: if observed ground water contamination attributable to sources at the site extends more than 2 miles beyond these sources, use any location within the limits of this observed ground water contamination when evaluating the travel time factor for any aquifer that does not have an observed release. If the necessary subsurface geologic information is available at multiple locations, evaluate the travel time factor at each location. Use the location having the highest travel time factor value to assign the factor value for the aquifer. Enter this value in Table 3-1.

3.1.2.5 Calculation of potential to release factor value. Sum the factor values for net precipitation, depth to aquifer, and travel time, and multiply this sum by the factor value for containment. Assign this product as the potential to release factor value for the aquifer. Enter this value in Table 3-1.

3.1.3 Calculation of likelihood of release factor category value. If an observed release is established for an aquifer, assign the observed release factor value of 550 as the

likelihood of release factor category value for that aquifer. Otherwise, assign the potential to release factor value for that aquifer as the likelihood of release value. Enter the value assigned in Table 3-1.

3.2 Waste characteristics. Evaluate the waste characteristics factor category for an aquifer based on two factors: toxicity/mobility and hazardous waste quantity. Evaluate only those hazardous substances available to migrate from the sources at the site to ground water. Such hazardous substances include:

- Hazardous substances that meet the criteria for an observed release to ground water.

- All hazardous substances associated with a source that has a ground water containment factor value greater than 0 (see sections 2.2.2, 2.2.3, and 3.1.2.1).

3.2.1 Toxicity/mobility. For each hazardous substance, assign a toxicity factor value, a mobility factor value, and a combined toxicity/mobility factor value as specified in the following sections. Select the toxicity/mobility factor value for the aquifer being evaluated as specified in section 3.2.1.3.

3.2.1.1 Toxicity. Assign a toxicity factor value to each hazardous substance as specified in Section 2.4.1.1.

3.2.1.2 Mobility. Assign a mobility factor value to each hazardous substance for the aquifer being evaluated as follows:

- For any hazardous substance that meets the criteria for an observed release by chemical analysis to one or more aquifers underlying the sources at the site, regardless of the aquifer being evaluated, assign a mobility factor value of 1.

- For any hazardous substance that does not meet the criteria for an observed release by chemical analysis to at least one of the aquifers, assign that hazardous substance a mobility factor value from Table 3-8 for the aquifer being evaluated, based on its water solubility and distribution coefficient (K_d).

- If the hazardous substance cannot be assigned a mobility factor value because data on its water solubility or distribution coefficient are not available, use other hazardous substances for which information is available in evaluating the pathway.

TABLE 3-8.—GROUND WATER MOBILITY FACTOR VALUES *


Water solubility (mg/l)	Distribution coefficient (K_d) (ml/g)			
	Karst *	≤ 10	> 10 to 1,000	$> 1,000$
Present as liquid *	1	1	0.01	0.0001
Greater than 100	1	1	0.01	0.0001
Greater than 1 to 100	0.2	0.2	0.002	2×10^{-4}
Greater than 0.01 to 1	0.02	0.002	2×10^{-4}	2×10^{-5}
Less than or equal to 0.01	2×10^{-2}	2×10^{-3}	2×10^{-4}	2×10^{-5}

* Do not round to nearest integer.


* Use if the hazardous substance is present or deposited as a liquid.

* Use if the entire interval from the source to the aquifer being evaluated is karst.

REFERENCE NO. 19




TITLE: FOUR MILE VICINITY MAP	
SITE NAME: E L BETH LTD PERTH AMBOY, N.J.	
DATE: 03-16-92	SCALE: 1" = 2000'
REPORT NUMBER: JO30	
USGS TOPO NAME: PERTH AMBOY, N.J.	



REFERENCE NO. 20

Geologic and Geohydrologic Reconnaissance of Staten Island, New York



**U.S. GEOLOGICAL SURVEY
Water-Resources Investigations
Report 87-4048**

STATEN ISLAND

LONG ISLAND

Prepared in cooperation with the

**NEW YORK STATE DEPARTMENT OF
ENVIRONMENTAL CONSERVATION**



**GEOLOGIC AND GEOHYDROLOGIC RECONNAISSANCE
OF STATEN ISLAND, NEW YORK**

by Julian Soren

U.S. GEOLOGICAL SURVEY

**Water-Resources Investigations
Report 87-4048**

Prepared in cooperation with the
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION



Syosset, New York

1988

GEOLOGIC AND GEOHYDROLOGIC RECONNAISSANCE OF STATEN ISLAND, NEW YORK

by Julian Soren

ABSTRACT

Staten Island (Richmond County) is a mainly suburban borough of the City of New York in which considerable interest in ground water has grown as a result of protracted droughts that seriously reduced the City's water supply from its upstate surface-reservoir system in the 1960's and 1980's. Hundreds of residents and business installed wells, mainly for lawn and plant-nursery irrigation, filling swimming pools, and vehicle washing, because the City prohibited use of the public-water supply for such purposes during the droughts.

Fresh ground water is available from Upper Proterozoic to Lower Jurassic bedrock and from overlying unconsolidated sandy Upper Cretaceous and upper Pleistocene deposits. The principal source of fresh ground-water recharge is precipitation that infiltrates the land surface and percolates to the water table. Fresh ground water moves downward and laterally through the unconsolidated deposits and bedrock toward discharge points--streams and tidewater that surround the island and saline ground-water that underlies it at depth.

Four maps of Staten Island's geology and water-table levels provide information on ground-water availability and serve as a basis for future ground-water investigations.

Streamflow on Staten Island has not been noticeably reduced by current ground-water development, which indicates that the ground-water reservoir has not been significantly depleted and that considerably more ground water is available for use.

INTRODUCTION

Richmond County, commonly known as Staten Island, a borough of the City of New York, has had less hydrogeologic study than the City's other four boroughs because it is the least populated and most recently developed.

Public water supply for Staten Island has been provided entirely by New York City's surface-reservoir system in upstate New York since 1971. During 1917-70, from 96 to 67 percent of the water was from upstate reservoirs; the rest was supplied by several municipally owned wells on the island. The amount pumped locally depended on the adequacy of the upstate reservoirs' reserves during drought periods. Before 1917, water from individual wells, from municipal wells, and from privately owned water-company wells, in addition to small, local surface reservoirs, supplied the water needs of Staten Island's population, which was significantly less than the 116,500 stated in the U.S. Census of 1920.

REFERENCE NO. 21

Let's protect our earth



Surface Water Quality Standards

N.J.A.C. 7:9-4.1 et seq.



AUGUST 1989

New Jersey Department of Environmental Protection
Division of Water Resources

National/State Parks and Wildlife Refuges and waters of exceptional recreational or ecological significance) as designated in N.J.A.C. 7:9-4.15(i).

"Persistent" means relatively resistant to degradation, generally having a half life of over 96 hours.

"Pinelands waters" means all waters within the boundaries of the Pineland Area, except those waters designated as FW1 in this subchapter, as established in the Pinelands Protection Act N.J.S.A. 13:18A-1 et seq., and shown on Plate 1 of the "Comprehensive Management Plan" adopted by the New Jersey Pinelands Commission in November 1980.

"PL" means the general surface water classification applied to Pinelands Waters.

"Primary contact recreation" means recreational activities that involve significant ingestion risks and includes, but is not limited to, wading, swimming, diving, surfing, and water skiing.

"Public hearing" means a legislative type hearing before a representative or representatives of the Department providing the opportunity for public comment, but does not include cross-examination.

"River mile" means the distance, measured in statute miles, between two locations on a stream, with the first location designated as mile zero. Mile zero for the Delaware River is located at the intersection of the centerline of the navigation channel and a line between the Cape May Light, New Jersey, and the tip of Cape Henlopen, Delaware.

"Saline waters" means waters having salinities generally greater than 3.5 parts per thousand at mean high tide.

"SC" means the general surface water classification applied to coastal saline waters.

→ "SE" means the general surface water classification applied to saline waters of estuaries.

"Secondary contact recreation" means recreational activities where the probability of water ingestion is minimal and includes, but is not limited to, boating and fishing.

"Shellfish" means those mollusks commonly known as clams, oysters, or mussels.

"Shellfish waters" means waters classified as Approved, Seasonally Approved, Special Restricted, Seasonally Special Restricted or Condemned that support or possess the potential to support shellfish which are within the Coastal Area Facility Review Act (C.A.F.R.A.) zone as delineated in 1973, (excluding: 1 - The Cohansey River upstream of Brown's Run; 2 - The Maurice River upstream of Route 548;

1. It is demonstrated to the satisfaction of the Department that the waters should be set aside to represent the natural aquatic environment and its associated biota; or
 2. It is demonstrated to the satisfaction of the Department that a more restrictive use is necessary to protect a unique ecological system or threatened/endangered species.
- (g) In those cases in which a thermal discharge is involved, the procedures for reclassifying segments for more restrictive uses shall be consistent with section 316 of the Federal Clean Water Act.

→ 7:9-4.12 Designated uses of FW1, PL, FW2, SE1, SE2, SE3, and SC Waters

- (a) In all FW1 waters the designated uses are:
1. Set aside for posterity to represent the natural aquatic environment and its associated biota;
 2. Primary and secondary contact recreation;
 3. Maintenance, migration and propagation of the natural and established aquatic biota; and
 4. Any other reasonable uses.
- (b) In all PL waters the designated uses are:
1. Cranberry bog water supply and other agricultural uses;
 2. Maintenance, migration and propagation of the natural and established biota indigenous to this unique ecological system;
 3. Public potable water supply after such treatment as required by law or regulations;
 4. Primary and secondary contact recreation; and
 5. Any other reasonable uses.
- (c) In all FW2 waters the designated uses are:
1. Maintenance, migration and propagation of the natural and established biota;
 2. Primary and secondary contact recreation;
 3. Industrial and agricultural water supply;

4. Public potable water supply after such treatment as required by law or regulation; and
5. Any other reasonable uses.

(d) In all SE1 waters the designated uses are:

1. Shellfish harvesting in accordance with N.J.A.C. 7:12;
2. Maintenance, migration and propagation of the natural and established biota;
3. Primary and secondary contact recreation; and
4. Any other reasonable uses.

→ (e) In all SE2 waters the designated uses are:

1. Maintenance, migration and propagation of the natural and established biota;
2. Migration of diadromous fish;
3. Maintenance of wildlife;
4. Secondary contact recreation; and
5. Any other reasonable uses.

→ (f) In all SE3 waters the designated uses are:

1. Secondary contact recreation;
2. Maintenance and migration of fish populations;
3. Migration of diadromous fish;
4. Maintenance of wildlife; and
5. Any other reasonable uses.

(g) In all SC waters the designated uses are:

1. Shellfish harvesting in accordance with N.J.A.C. 7:12;
2. Primary and secondary contact recreation;
3. Maintenance, migration and propagation of the natural and established biota; and
4. Any other reasonable uses.

(e) The surface water classifications in Table 3 are for waters of the Passaic, Hackensack and New York Harbor Complex Basin:

TABLE 3

<u>WATER BODY</u>	<u>CLASSIFICATION</u>
→ ARTHUR KILL	
(Perth Amboy) - The Kill and its saline New Jersey tributaries between the Outerbridge Crossing and a line connecting Ferry Pt., Perth Amboy to Wards Pt., Staten Island, New York	SE2
(Elizabeth) - From an east-west line connecting Elizabethport with Bergen Pt., Bayonne to the Outerbridge Crossing	SE3
(Woodbridge) - All freshwater tributaries	FW2-NT
BEAR SWAMP BROOK (Mahwah) - Entire length	FW2-TP(C1)
BEAR SWAMP LAKE (Ringwood)	FW2-NT(C1)
BEAVER BROOK	
(Meriden) - From Splitrock Reservoir Dam downstream to Meriden Road Bridge	FW2-TM
(Denville) - Meriden Road Bridge to Rockaway River	FW2-NT
BEECH BROOK	
(West Milford) - From State line downstream to Wanaque River	FW2-TM
BELCHER CREEK (W. Milford) - Entire length	FW2-NT
BERRYS CREEK (Secaucus) - Entire length	FW2-NT/SE2
BLACK BROOK	
(Meyersville) - Entire length, except segment described below	FW2-NT
(Great Swamp) - Segment and tributaries within the Great Swamp National Wildlife Refuge	FW2-NT(C1)
BLUE MINE BROOK	
(Wanaque) - Entire length, except segment described below	FW2-TM
(Norvin Green State Forest) - That portion of the stream and any tributaries within the Norvin Green State Forest	FW2-TM(C1)
BRUSHWOOD POND (Ringwood)	FW2-TM(C1)
BUCKABEAR POND (Newfoundland) - Pond, its tributaries and connecting stream to Clinton Reservoir	FW2-NT(C1)
BURNT MEADOW BROOK (Stonetown) - Entire length	FW2-TP(C1)
CANISTEAR RESERVOIR (Vernon)	FW2-TM
CANISTEAR RESERVOIR TRIBUTARY (Vernon) - The southern branch of the eastern tributary to the Reservoir	FW1
CANOE BROOK (Chatham) - Entire length	FW2-NT

Oceanport (Oceanport) - Creek downstream of line described above	SE1(C1)
PARKERS CREEK	
(Fort Monmouth) - Source to a line beginning on the easternmost extent of Horseneck Point and bearing approximately 000 degrees T (True North) to its terminus on Breezy Point on the Little Silver side (north) side of the creek.	FW2-NT/SE1
(Fort Monmouth) - Creek downstream of line described above	SE1(C1)
PEAPACK BROOK (Gladstone) - Entire length	FW2-TP(C1)
PETERS BROOK (Somerville) - Entire length	FW2-NT
PIGEON SWAMP (S. Brunswick) - All waters within the boundaries of Pigeon Swamp State Park	FW2-NT(C1)
PIKE RUN (Belle Meade) - Entire length	FW2-NT
PINE BROOK (Clarks Mills) - Entire length	FW2-NT
PINE BROOK (Cooks Mill) - Entire length	FW2-TM
PLEASANT RUN (Readington) - Entire length	FW2-NT
PRESCOTT BROOK (Stanton Station) - Entire length	FW2-TM
RAMANESSIN (HOP) BROOK (Holmdel) - Entire length	FW2-TM
RARITAN BAY - Entire drainage	FW2-NT/SE1
RARITAN RIVER	
NORTH BRANCH (Also see INDIA BROOK) (Pleasant Valley) - Source to, but not including, Ravine Lake	FW2-TP(C1)
(Far Hills) - Ravine Lake dam to Rt. 512 bridge	FW2-TM
(Bedminster) - Rt. 512 bridge to confluence with South Branch, Raritan River	FW2-NT
SOUTH BRANCH RARITAN RIVER	
(Mt. Olive) - Source to the dam that is 390 feet upstream of the Flanders- Drakestown Road bridge	FW2-NT(C1)
(Mt. Olive) - Dam to confluence with Turkey Brook	FW2-TM(C1)
(Naughtright) - Confluence with Turkey Brook to confluence with Electric Brook	FW2-TP(C1)
(Clinton) - Confluence with Electric Brook to downstream end of Packers Island, except segment described separately, below	FW2-TM
(Ken Lockwood Gorge) - River and tributaries within Ken Lockwood Gorge Wildlife Management Area	FW2-TM(C1)
(Neshanic Sta.) - Downstream end of Packers Island to confluence with North Branch, Raritan River	FW2-NT
MAIN STEM RARITAN RIVER	
(Bound Brook) - From confluence of North	FW2-NT

and South Branches to Landing Lane bridge in New Brunswick and all freshwater tributaries downstream of Landing Lane bridge.	
→ (Sayreville) - Landing Lane bridge to Raritan Bay and all saline water tributaries	SE1
RINEHART BROOK (Hacklebarney) - Entire length	FW2-TP(C1)
ROCK BROOK (Montgomery) - Entire length	FW2-NT
ROCKAWAY CREEK	
NORTH BRANCH	
(Mountainville) - Source to Rt. 523 bridge	FW2-TP(C1)
(Whitehouse) - Rt. 523 bridge to confluence with South Branch	FW2-TM
SOUTH BRANCH (Whitehouse) - Entire length	FW2-TM
MAIN STEM (Whitehouse) - Confluence of North and South Branches to Lamington River	FW2-NT
ROUND VALLEY RESERVOIR (Clinton)	FW2-TM
ROYCE BROOK (Manville) - Entire length	FW2-NT
SHREWSBURY RIVER	
(Little Silver) - Source to Rt. 36 highway bridge	SE1(C1)
(Highlands) - Rt. 36 bridge to Sandy Hook bay	SE1
SIMONSON BROOK (Griggstown) - Entire length	FW2-NT
SIX MILE RUN	
(Franklin Church) - Entire length, except segment described below	FW2-NT
(Hillsborough) - Segment within the boundaries of Six Mile Run State Park	FW2-NT(C1)
SOUTH RIVER	
(Old Bridge) - Duhernal Lake to intake of the Sayreville Water Department	FW2-NT
(Sayreville) - Below the intake of the Sayreville Water Department	SE1
SPOOKY BROOK (Bound Brook)	FW2-NT
SPRUCE RUN	
(Glen Gardner) - Source to, but not including, Spruce Run Reservoir	FW2-TP(C1)
(Clinton) - Spruce Run Reservoir dam to Raritan River, South Branch	FW2-TM
SPRUCE RUN RESERVOIR (Union) - Reservoir and tributaries	FW2-TM(C1)
STONY BROOK (Washington) - Entire length	FW2-TP(C1)
STONY BROOK	
(Hopewell) - Entire length, except that segment described below	FW2-NT
(Syndertown) - Brook and tributaries within Amwell Lake Wildlife Management Area	FW2-NT(C1)
STONY BROOK (Watchung) - Entire length	FW2-NT
SUN VALLEY BROOK (Mt Olive) - Entire length	FW2-TP(C1)
SWIMMING RIVER	
(Red Bank) - Source to the intake of the	FW2-NT

REFERENCE NO. 22



APPROXIMATE SCALE

600 0 600 FEET

NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

**CITY OF
PERTH AMBOY,
NEW JERSEY
MIDDLESEX COUNTY**

ONLY PANEL PRINTED


COMMUNITY-PANEL NUMBER
340272 0001 C

MAP REVISED:
May 1, 1984



Federal Emergency Management Agency

with Washington Street, flush with ground, between curb and
side of Garfield Fire Station, 11 feet northeast of northwest
along east boundary of Alpine Cemetery in Perth Amboy, 42
feet 628 PAY, 8.4 feet west of west edge of west sidewalk along
venue, located on northeast corner near curb and 0.45 foot
35 and Brace Avenue, set in brick wall of City Stable at east
corner, stamped 389-D, set vertically.
1440, level with curb.



KEY TO MAP

500-Year Flood Boundary		
100-Year Flood Boundary		
Zone Designations* With Date of Identification e.g., 12/2/74		
100-Year Flood Boundary		
500-Year Flood Boundary		
Base Flood Elevation Line With Elevation In Feet**		513
Base Flood Elevation in Feet Where Uniform Within Zone**		(EL 987)
Elevation Reference Mark		RM7x
Zone D Boundary		
River Mile		•M1.5

**Referenced to the National Geodetic Vertical Datum of 1929

*EXPLANATION OF ZONE DESIGNATIONS



ZONE	EXPLANATION
A	Areas of 100-year flood; base flood elevations and flood hazard factors not determined.
A0	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; average depths of inundation are shown, but no flood hazard factors are determined.
AH	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; base flood elevations are shown; but no flood hazard factors are determined.
A1-A30	Areas of 100-year flood; base flood elevations and flood hazard factors determined.
A99	Areas of 100-year flood to be protected by flood protection system under construction; base flood elevations and flood hazard factors not determined.
B	Areas between limits of the 100-year flood and 500-year flood; or certain areas subject to 100-year flooding with average depths less than one (1) foot or where the contributing drainage area is less than one square mile; or areas protected by levees from the base flood. (Medium shading)
C	Areas of minimal flooding. (No shading)
D	Areas of undetermined, but possible, flood hazards.
V	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors not determined.
V1-V30	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors determined.

NOTES TO USER

Certain areas not in the special flood hazard areas (zones A and V) may be protected by flood control structures.

This map is for flood insurance and flood plain management purposes only; it does not necessarily show all areas subject to flooding in the community or all planimetric features outside special flood hazard areas. The coastal flooding elevations shown may differ significantly from those developed by the National Weather Service for hurricane evacuation planning.

Coastal base flood elevations shown on this map include the effects of



may be protected by flood control structures.

This map is for flood insurance and flood plain management purposes only; it does not necessarily show all areas subject to flooding in the community or all planimetric features outside special flood hazard areas. The coastal flooding elevations shown may differ significantly from those developed by the National Weather Service for hurricane evacuation planning.

Coastal base flood elevations shown on this map include the effects of wave action.

Coastal base flood elevations apply only landward of the shoreline shown on this map.

INITIAL IDENTIFICATION:
JUNE 21, 1974

FLOOD HAZARD BOUNDARY MAP REVISIONS:
JUNE 4, 1976


FLOOD INSURANCE RATE MAP EFFECTIVE:
DECEMBER 18, 1979

FLOOD INSURANCE RATE MAP REVISIONS:
May 1, 1984-to add base flood elevations, to change special flood hazard areas, to add the effects of wave action

To determine if flood insurance is available in this community, contact your insurance agent, or call the National Flood Insurance Program, at (800) 638-6620.




APPROXIMATE SCALE



NATIONAL FLOOD INSURANCE PROGRAM


FIRM
FLOOD INSURANCE RATE MAP



ERENCE MARKS

DESCRIPTION OF LOCATION

REFERENCE NO. 23



REFERENCE NO. 24

TO: EL Beth Ltd file
FROM: Claire Burdick
SUBJECT: Sensitive Environments Located Along the 15-mile Surface Water Route
REFERENCE: Downstream of the EL Beth Site, Bertha Ambrey, New Jersey.
(References noted below).

DATE: March 27, 1992
COPIES: —

- Correspondence sent by the U.S. Department of the Interior Fish and Wildlife Service to HNU on March 11, 1992 reports that a federally-listed endangered bird species is documented as nesting and as having successfully fledged young at the Arthur Kill. Additionally, this species is documented to be using emergent wetlands located along the Raritan River. This letter also documents a federally-protected^(Priority) wetland area.
- Based upon Atlantic Coast Ecological Inventory Mapping, ^{Newark Sheet} the Shortnose Sturgeon, a N.J. state-listed endangered species, is found in coastal waters depicted in the Newark Sheet. It may, therefore, be present at the Arthur Kill, as well as at the surface waters farther downstream. This mapping also indicates the presence of the Great Blue Heron at Sandy Hook Bay; the breeding population of this species is considered endangered or threatened in New Jersey.
- Wetlands located along the 15-mile surface water route downstream of the EL Beth site include, according to the U.S. Fish and Wildlife Service National Wetlands Inventory Mapping:
 - At Raritan Bay: Estuarine Intertidal Emergent wetland, 0.85 mile.
 - Estuarine Intertidal Scrub/Shrub (Broad leaved deciduous) / Emergent wetland, 0.60 mile
 - Palustrine Scrub/Shrub (Broad leaved deciduous)
 - Emergent wetlands, 0.22 mile.

b) At Sandy Hook Bay:

- Estuarine Intertidal Scrub/Shrub (Broad leaved deciduous) / Emergent, 0.72 mile.

- Estuarine Intertidal Emergent wetland, 1.01 mile.

- Estuarine Intertidal Aquatic Bed wetland, 0.52 mile.

c) At the Raritan River

- Estuarine Intertidal Emergent wetland, 2.13 miles

- Federally protected (Priority) wetlands: Approximately 2 miles

d) At Arthur Kill, upstream of E.L. Beth site (tidal area)

- Estuarine intertidal Emergent wetland, 0.21 mile

Total wetland footage along the E.L. Beth 15-mile surface water route (sum of above values) is 6.26 miles.



ENDANGERED AND THREATENED WILDLIFE OF NEW JERSEY

Endangered Species are those whose prospects for survival in New Jersey are in immediate danger because of a loss or change in habitat, over-exploitation, predation, competition, disease, disturbance or contamination. Assistance is needed to prevent future extinction in New Jersey.

Threatened Species are those who may become endangered if conditions surrounding them begin to or continue to deteriorate.

BIRDS

Endangered

Pied-billed Grebe, * *Podilymbus podiceps*
Bald Eagle, *Haliaeetus leucocephalus* **
Northern Harrier, * *Circus cyaneus*
Cooper's Hawk, *Accipiter cooperii*
Red-shouldered Hawk, *Buteo lineatus* (Breeding)
Peregrine Falcon, *Falco peregrinus* **
Piping Plover, *Charadrius melodus* **
Upland Sandpiper, *Bartramia longicauda*
Roseate Tern, *Sterna dougallii*
Least Tern, *Sterna antillarum*
Black Skimmer, *Rynchops niger*
Short-eared Owl, * *Asio flammeus*
Sedge Wren, *Cistothorus platensis*
Loggerhead Shrike, *Lanius ludovicianus*
Vesper Sparrow, *Pooecetes gramineus*
Henslow's Sparrow, *Ammodramus henslowii*

Threatened

American Bittern *, *Botaurus lentiginosus*
Great Blue Heron *, *Ardea herodias*
Little Blue Heron, *Egretta caerulea* *
Yellow-crowned Night Heron, *Nyctanassa violaceus*
Osprey, *Pandion haliaetus*
Northern Goshawk, *Accipiter gentilis*
Red-shouldered Hawk, *Buteo lineatus* (Non-breeding)
Black Rail, *Laterallus jamaicensis*
Long-eared Owl, *Asio otus*
Barred Owl, *Strix varia*
Red-headed Woodpecker, *Melanerpes erythrocephalus*
Cliff Swallow, * *Hirundo pyrrhonota*
Savannah Sparrow, *Passerculus sandwichensis*
Ipswich Sparrow, *Passerculus sandwichensis princeps*
Grasshopper Sparrow, *Ammodramus savannarum*
Bobolink, *Dolichonyx oryzivorus*

*Only breeding population considered endangered or threatened

**Federally endangered or threatened

REPTILES

Endangered

Bog Turtle, *Clemmys muhlenbergi*
Atlantic Hawksbill, *Eretmochelys imbricata* **
Atlantic Loggerhead, *Caretta caretta* **
Atlantic Ridley, *Lepidochelys kempi* **
Atlantic Leatherback, *Dermochelys coriacea* **
Corn Snake, *Elaphe g. guttata*
Timber Rattlesnake, *Crotalus h. horridus*

Threatened

Wood Turtle, *Clemmys insculpta*
Atlantic Green Turtle, *Chelonia mydas* **
Northern Pine Snake, *Pituophis m. melanoleucus*

**Federally endangered or threatened

ENDANGERED AND NONGAME SPECIES PROGRAM

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION AND ENERGY
DIVISION OF FISH, GAME AND WILDLIFE

AMPHIBIANS

Endangered

Tremblay's Salamander, *Ambystoma tremblayi*
Blue-spotted Salamander, *Ambystoma laterale*
Eastern Tiger Salamander, *Ambystoma t. tigrinum*
Pine Barrens Treefrog, *Hyla andersonii*
Southern Gray Treefrog, *Hyla chrysoscelis*

Threatened

Long-tailed Salamander, *Eurycea longicauda*
Eastern Mud Salamander, *Pseudotriton montanus*

MAMMALS

Endangered

Bobcat, *Lynx rufus*
Eastern Woodrat, *Neotoma floridana*
Sperm Whale *Physeter, macrocephalus***
Fin Whale, *Balaenoptera physalus***
Sei Whale, *Balaenoptera borealis***
Blue Whale, *Balaenoptera musculus***
Humpback Whale, *Megaptera novaeangliae***
Black Right Whale, *Balaena glacialis***

INVERTEBRATES

Endangered

Mitchell's Satyr (butterfly), *Neonympha m. mitchellii***
Northeastern Beach Tiger Beetle, *Cicindela d. dorsalis*
American Burying Beetle, *Nicrophorus americanus***
Dwarf Wedge Mussel, *Alasmodonta heterodon***


** Federally endangered

FISH

Endangered

Shortnose Sturgeon, *Acipenser brevirostrum***

List revisions: March 29, 1979
January 17, 1984
May 6, 1985
July 20, 1987
June 3, 1991



The lists of New Jersey's endangered and nongame wildlife species are maintained by the DEP&E's Division of Fish, Game and Wildlife's, Endangered and Nongame Species Program. These lists are used to determine protection and management actions necessary to insure the survival of the State's endangered and nongame wildlife. This work is made possible only through voluntary contributions received through the Wildlife Check-off on the New Jersey State Tax Form. The Wildlife Check-off is the only major funding source for the protection and management of the State's endangered and nongame wildlife resource. For more information about the Endangered and Nongame Species Program or to report a sighting of endangered or threatened wildlife contact: Endangered and Nongame Species Program, Northern District Office, Box 383 R.D. 1, Hampton, N.J. 08827 or call (908) 735-8975.

in RED (F) or (S) indicates species protected by
Federal or State Legislation (see text)

SYMBOL SPECIES

PLANTS (301-350)

- 301 Eastern hemlock
- 302 Spleenwort (S)
- 303 Spider lily (S)
- 304 Pond bush (S)
- 305 Watermilfoil (S)
- 306 Hooded pitcher plant (S)
- 307 Tree
- 308 Prickly pear cactus (S)
- 309 Trailing arbutus (S)
- 310 Eastern bumelia
- 311 Pitcher plant
- 312 Baldcypress
- 313 Redbay
- 314 Seaside alder
- 315 Box huckleberry
- 316 Purple fringeless orchid
- 317 Pink lady's slipper
- 318 Ebony spleenwort (S)
- 319 Orchids (S)
- 320 Golden club (S)
- 321 Florida beargrass
- 322 East-coast coontie
- 323 Fall-flowering ixia
- 324 Jackson-vine
- 325 Spoon-flower
- 326 Curtiss milkweed
- 327 Sea lavender
- 328 Hand fern
- 329 Needle palm
- 330 Yellow squirrel-banana
- 331 Beach creeper
- 332 Florida coontie
- 333 Four-petal pawpaw
- 334 Bird's nest spleenwort
- 335 Burrowing four-o'clock
- 336 Beach star
- 337 Silver palm
- 338 Dancing lady orchid
- 339 Tamarindillo
- 340 Fuch's bromeliad
- 341 Everglades peperomia
- 342 Buccaneer palm
- 343 Slender spleenwort
- 344 Pineland jacquemontia
- 345 Mahogany mistletoe
- 346 Florida thatch
- 347 Twisted air plant
- 348 Long's bittercress
- 349 Venus's flytrap

INVERTEBRATES (351-400)

- 351 Monarch butterfly
- 352 Zebra butterfly

BIRDS (401-600)

SHOREBIRDS (401-430)

- 401 Shorebirds
- 402 Terns
- 403 Gulls
- 404 Forster's tern
- 405 Arctic tern
- 406 Least tern (S)
- 407 Roseate tern (S)
- 408 Common tern
- 409 Great black-backed gull
- 410 Herring gull
- 411 Laughing gull
- 412 Black skimmer (S)
- 413 Turnstones
- 414 Plovers
- 415 Piping plover
- 416 American oystercatcher (S)

WADING BIRDS (431-460)

- 431 Wading birds
- 432 Herons
- 433 Egrets
- 434 Rails
- 435 Ibises
- 436 Bitterns
- 437 Great blue heron (S)
- 438 Wood ibis (S)
- 439 Anhinga
- 440 Little blue heron (S)
- 441 Yellow-crowned night heron (S)
- 442 Black-crowned night heron
- 443 Florida sandhill crane (S)
- 444 Louisiana heron (S)
- 445 Limpkin (S)
- 446 Roseate spoonbill (S)
- 447 Snowy egret (S)
- 448 Magnificent frigate-bird (S)
- 449 Reddish egret (S)
- 450 Clapper rail
- 451 King rail
- 452 Virginia rail
- 453 Sora rail

WATERFOWL (461-500)

- 461 Waterfowl
- 462 Swans
- 463 Geese
- 464 Dabbling ducks
- 465 Diving ducks
- 466 Common eider
- 467 Harlequin duck
- 468 Wood duck
- 469 Fulvous tree duck
- 470 Loons

newark

N. J.—N. Y.—PA.

1:250 000-scale map of Atlantic Coast Ecological Inventory



NUS CORP.

**** REFERENCE MATERIAL ****

**DO NOT FOLD, DRAW ON, MUTILATE IN ANY
WAY. COPIES CAN BE MADE IN DRAFTING.**

DATE: 6/22/89



**Produced by
U. S. FISH AND WILDLIFE
SERVICE
1980**

AQUATIC ORGANISMS

Shown in BLUE; species with special status shown
in RED (F) or (S) indicates species protected by
Federal or State Legislation (see text)

SYMBOL SPECIES

- ↓ PLANTS (1-50)
- 1 Irish moss
- 2 Rockweed
- INVERTEBRATES (51-100)
- 51 Crabs
- 52 Mussels
- 53 Oysters
- 54 Scallops
- 55 Clams
- 56 Worms
- 57 Shrimp
- 58 American lobster
- 59 Blue crab
- 60 Eastern oyster
- 61 European oyster
- 62 Bay scallop
- 63 Deep-sea scallop
- 64 Calico scallop
- 65 Surf clam
- 66 Hard clam
- 67 Soft shell clam

56.4 \$ 51
MADE IN U.S.A.

TO: EL Beth Project file

DATE: 3/31/92

FROM: Claire Bumpis

COPIES: —

SUBJECT: Clarification of species' status as referenced in Atlantic Coast

REFERENCE: Ecological Inventory.

The Atlantic Coast Ecological Inventory (work map) lists the American shad as threatened in New Jersey; this reference is dated 1990. A more recent reference issued by the NJ Dept. of Environmental Protection and Energy (last revision 1991) does not include the American shad. Because the more current reference indicates the species is not listed as state endangered or threatened, it is not included in scoring.

NOTES

SPECIES WITH SPECIAL STATUS

Shortnose sturgeon (110) is found in coastal waters depicted on the Newark sheet and migrates up the Hudson River.

American shad (116) is threatened in New Jersey.

Bald eagle and peregrine falcon (505, 507) migrate along coastal areas depicted on the Newark sheet.

AQUATIC ORGANISMS

Due to scale limitations, only representative estuarine and riverine systems are shown:

Species that can be found in the ocean waters off New Jersey depicted on the Newark sheet include:

110g, 118g, 57cdf, 58abcd, 59de, 65abcd, 111g, 113g, 115g, 117cd, 129cdf, 130cdf, 138acd, 139d, 140cd, 142ad, 147bcd, 149d, 154cdf, 157f, 158a, 160cdf, 173cdf, 177cdf, 178f, 180ad, 181cd.

Generally includes the following species:

116g, 59abcd, 111g, 112cd, 113g, 115g, 117cd, 128cdg, 129cdf, 138acd, 139d, 140cdf, 142f, 147bcd, 149bdf, 157f, 158abf, 160cdf, 177cdf, 178f, 180ad.

Generally includes the following species:

116g, 59bcl, 112cd, 113g, 115g, 117bc, 128bcfg, 129cdf, 138bcd, 139bd, 140bcd, 147b, 149b, 158b, 160bcd, 167b, 180abd.


Generally includes the following species:

116g, 59cl, 112bcd, 113abcf, 115abcd, 117b, 128abcd, 129bcfg, 138b, 139b, 140b, 147b, 160b, 180bd.

Species of importance in a particular river, creek, or sound are denoted on the map.

TERRESTRIAL ORGANISMS

Waterfowl (481), particularly geese and ducks, concentrate along the Delaware River, the Atlantic coast, and Lower New York, Raritan, and Sandy Hook Bays depicted on the Newark sheet.



- 435 Ibises
436 Bitterns
437 Great blue heron (S)
438 Wood ibis (S)
439 Anhinga
440 Little blue heron (S)
441 Yellow-crowned night heron (S)
442 Black-crowned night heron
443 Florida sandhill crane (S)
444 Louisiana heron (S)
445 Limpkin (S)
446 Roseate spoonbill (S)
447 Snowy egret (S)
448 Magnificent frigate-bird (S)
449 Reddish egret (S)
450 Clapper rail
451 King rail
452 Virginia rail
453 Sora rail

WATERFOWL (461-500)

- 461 Waterfowl
462 Swans
463 Geese
464 Dabbling ducks
465 Diving ducks
466 Common eider
467 Harlequin duck
468 Wood duck
469 Fulvous tree duck
470 Loons
471 Grebes
472 Brant geese
473 Snow goose
474 Gadwall
475 Black duck

RAPTORS (501-530)

- 501 Raptors
502 Owls
503 Kites
504 Hawks
505 Bald eagle (F)
506 Osprey (S)
507 Peregrine falcon (F)
508 Copper's hawk (S)
509 Swallow-tailed kite
510 Marsh hawk (S)
511 Southeastern American kestrel (S)
512 Florida burrowing owl (S)

SEABIRDS (531-550)

- 531 Seabirds
532 Petrels, shearwaters, and albatrosses
533 Pelican and allies
534 Alcids
535 Brown pelican (F)
536 Black guillemot
537 Leach's petrel
538 Razorbill
539 Common puffin
540 Double-crested cormorant
541 Gannet
542 Wilson's petrel
543 Northern phalarope
544 Audubon's shearwater
545 Greater shearwater
546 Shearwaters
547 Petrels
548 Jaegers
549 White pelican

SONGBIRDS AND OTHERS (551-600)

- 551 Songbirds and others
552 Red-cockaded woodpecker (F)
553 Chachalaca
554 Bachman's warbler (F)
555 Wild turkey
556 American woodcock
557 Pileated woodpecker
558 Swainson's warbler
559 Ruffed grouse
560 Bobwhite
561 Mourning dove
562 Warblers
563 Ring-necked pheasant
564 Bank swallow
565 Dusky seaside sparrow (F)
566 White-crowned pigeon (S)

REPTILES AND AMPHIBIANS (601-700)

- 601 Eastern narrow-mouthed toad (S)
602 Eastern indigo snake (F)
603 American alligator (F)
604 Northern diamondback terrapin
605 Amphibians
606 Greater siren
607 Bog turtle (S)
608 Gopher tortoise (S)
609 Eastern tiger salamander (S)
610 Northern fence lizard
611 Five-lined skink
612 Map turtle
613 Plymouth red-bellied turtle (F)
614 Eastern diamondback rattlesnake
615 Carolina gopher frog
616 Florida gopher frog (S)
617 Atlantic salt marsh watersnake (F)
618 American crocodile (F)
619 Florida Keys mole skink (S)
620 Florida black-headed snake (S)
621 Pine barrens tree frog (S)
622 Northern pine snake (S)
623 Corn snake (S)
624 Timber rattlesnake (S)

AQUATIC ORGANISMS

Shown in BLUE: species with special status shown in RED (F) or (S) indicates species protected by Federal or State Legislation (see text)

SYMBOL



SPECIES

PLANTS (1-50)

- 1 Irish moss
2 Rockweed

INVERTEBRATES (51-100)

- 51 Crabs
52 Mussels
53 Oysters
54 Scallops
55 Clams
56 Worms
57 Shrimp
58 American lobster
59 Blue crab
60 Eastern oyster
61 European oyster
62 Bay scallop
63 Deep-sea scallop
64 Calico scallop
65 Surf clam
66 Hard clam
67 Soft shell clam
68 Brackish-water clam
69 Bloodworm
70 Sandworm
71 White shrimp
72 Brown shrimp
73 Northern shrimp
74 Rock crab
75 Jonah crab
76 Whelk
77 Ocean quahog
78 Pink shrimp
79 Stone crab
80 Spiny lobster

FISH (101-200)

- 101 Sharks, skates, rays
102 Herring
103 Salmon and trout
104 Catfish
105 Cod
106 Sunfish and bass
107 Drum
108 Flatfish
109 Longnose gar
110 Shortnose sturgeon (F)
111 Atlantic sturgeon (S)
112 American eel
113 Blueback herring
114 Hickory shad
115 Alewife
116 American shad (S)
117 Atlantic menhaden
118 Atlantic herring
119 Gizzard shad
120 Tarpon
121 Atlantic salmon
122 White catfish
123 Channel catfish
124 Yellow bullhead
125 Brown bullhead
126 Flat bullhead
127 Sea catfish
128 White perch
129 Striped bass
130 Black sea bass
131 Redbreast sunfish
132 Warmouth
133 Bluegill
134 Largemouth bass
135 Black crappie
136 Sneepshead
137 Spotted seatrout
138 Weakfish
139 Spot
140 Atlantic croaker
141 Southern kingfish
142 Northern kingfish
143 Gulf kingfish
144 Red drum
145 Star drum
146 Black drum
147 Summer flounder
148 Southern flounder
149 Winter flounder
150 Rainbow smelt
151 Atlantic tomcod
152 Threadfin shad
153 Carp
154 Atlantic mackerel
155 Chain pickerel
156 White bass
157 Northern puffer
158 Silver perch
159 Florida pompano
160 Bluefish
161 Spanish mackerel
162 Cobia
163 Mullet
164 White crappie
165 Redear sunfish
166 Smallmouth bass
167 Yellow perch
168 Pumpkinseed

66.4 \$ 15
4.95
MAY & TRAVEL CENTERS
GEOSTAT
00-908

- 543 Northern phalarope
544 Audubon's shearwater
545 Greater shearwater
546 Shearwaters
547 Petrels
548 Jaegers
549 White pelican

SONGBIRDS AND OTHERS (551-600)

- 551 Songbirds and others
552 Red-cockaded woodpecker (F)
553 Chachalaca
554 Bachman's warbler (F)
555 Wild turkey
556 American woodcock
557 Pileated woodpecker
558 Swainson's warbler
559 Ruffed grouse
560 Bobwhite
561 Mourning dove
562 Warblers
563 Ring-necked pheasant
564 Bank swallow
565 Dusky seaside sparrow (F)
566 White-crowned pigeon (S)

REPTILES AND AMPHIBIANS (601-700)

- 601 Eastern narrow-mouthed toad (S)
602 Eastern indigo snake (F)
603 American alligator (F)
604 Northern diamondback terrapin
605 Amphibians
606 Greater siren
607 Bog turtle (S)
608 Gopher tortoise (S)
609 Eastern tiger salamander (S)
610 Northern fence lizard
611 Five-lined skink
612 Map turtle
613 Plymouth red-bellied turtle (F)
614 Eastern diamondback rattlesnake
615 Carolina gopher frog
616 Florida gopher frog (S)
617 Atlantic salt marsh watersnake (F)
618 American crocodile (F)
619 Florida Keys mole skink (S)
620 Florida black-headed snake (S)
621 Pine barrens tree frog (S)
622 Northern pine snake (S)
623 Corn snake (S)
624 Timber rattlesnake (S)
625 Southern gray tree frog (S)

MAMMALS (701-800)

- 701 Beaver
702 Whitetail deer
703 European fallow deer
704 Blackbeard Island deer
705 Opossum
706 Marsh rabbit
707 Rice rat
708 Raccoon
709 St. Simon Island raccoon
710 Mink
711 River otter (F)
712 Feral hog
713 Feral cow
714 Cumberland Island pocket gopher
715 Anastasia Island cotton mouse
716 Aquatic furbearers
717 Black bear (S)
718 Bobcat
719 Eastern gray squirrel
720 Eastern fox squirrel
721 Eastern cottontail
722 Delmarva fox squirrel (F)
723 Muskrat
724 Red fox
725 Bats
726 Gray fox
727 Striped skunk
728 Nutria
729 Longtail weasel
730 Colonial pocket gopher (S)
731 Wild ponies
732 Sika deer
733 Beach meadow vole
734 Block Island meadow vole
735 Pallid beach mouse (S)
736 Sherman's fox squirrel (S)
737 Florida mouse (S)
738 Florida panther (F)
739 Goff's pocket gopher (S)
740 Key Largo wood rat (S)
741 Lower keys cotton rat (S)
742 Key Largo cotton mouse (S)

HABITAT USE

Shown in RED for species with special status, BLUE for aquatic organisms and BROWN for terrestrial organisms

- a Spawning ground
b Nursery
c Commercial harvesting area
d Adult concentration
e Overwintering area
f Sport fishing/hunting area
g Migratory area
h Nesting area
i Unusual distribution or specimen


- 119 Gizzard shad
120 Tarpon
121 Atlantic salmon
122 White catfish
123 Channel catfish
124 Yellow bullhead
125 Brown bullhead
126 Flat bullhead
127 Sea catfish
128 White perch
129 Striped bass
130 Black sea bass
131 Redbreast sunfish
132 Warmouth
133 Bluegill
134 Largemouth bass
135 Black crappie
136 Sheepshead
137 Spotted seatrout
138 Weakfish
139 Spot
140 Atlantic croaker
141 Southern kingfish
142 Northern kingfish
143 Gulf kingfish
144 Red drum
145 Star drum
146 Black drum
147 Summer flounder
148 Southern flounder
149 Winter flounder
150 Rainbow smelt
151 Atlantic tomcod
152 Threadfin shad
153 Carp
154 Atlantic mackerel
155 Chain pickerel
156 White bass
157 Northern puffer
158 Silver perch
159 Florida pompano
160 Bluefish
161 Spanish mackerel
162 Cobia
163 Mullet
164 White crappie
165 Redear sunfish
166 Smallmouth bass
167 Yellow perch
168 Pumpkinseed
169 Atlantic halibut
170 Atlantic cod
171 Pollock
172 Haddock
173 Hake
174 Bluefin tuna
175 Walleye
176 Northern pike
177 Scup
178 Tautog
179 Atlantic spadefish
180 Bay anchovy
181 Butterfish
182 Little tunny
183 Atlantic bonito
184 Brown trout
185 Cunner
186 Yellowtail flounder
187 Gulf flounder
188 Pinfish
189 King mackerel
190 Pigfish
191 White grunt
192 Tripletail
193 Ladyfish
194 Snook
195 Jack
196 Snapper
197 Grouper
198 Sailfish
199 Great barracuda
200 Maryland darter (F)


REPTILES AND AMPHIBIANS (201-250)



- 201 Green sea turtle (F)
202 Loggerhead sea turtle (F)
203 Hawksbill turtle (F)
204 Atlantic ridley turtle (F)
205 Leatherback turtle (F)

MAMMALS (251-300)

- 251 Florida manatee (F)
252 Atlantic bottlenose dolphin
253 Pigmy sperm whale
254 Short-finned pilot whale
255 Harbor seal
256 Gray seal
257 Right whale (F)
258 Atlantic spotted dolphin








TRANSVERSE MERCATOR PROJECTION

BLACK NUMBERED LINES INDICATE THE 10,000 METER UNIVERSAL TRANSVERSE MERCATOR GRID, ZONE 18

FOR SALE BY U. S. GEOLOGICAL SURVEY, RESTON, VIRGINIA 22092, OR DENVER, COLORADO 80225



T - Topographic map
 T/B - Topographic/Bathymetric map
 B - Bathymetric map
 E - Ecological inventory map
 E* - Includes portion of Albany

REFERENCE NO. 25

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO.: J004	DATE: November 18, 1991	TIME: 1615
DISTRIBUTION: Front Street Works file, J004		
BETWEEN: Mr. Robert Soldwedel	OF: NY Department of Environmental Protection and Energy - Fisheries Div.	PHONE: (609) 292-1599
AND: Claire Barupis		(NUS)
DISCUSSION: Mr. Soldwedel said that there is a statewide advisory on reducing consumer risk from fish contaminated with toxic chemicals, such as PCBs, dioxin, or chlordane. At the Newark Bay complex, there is a prohibition on the sale and consumption of all fish from the tidal Passaic River, and a prohibition on the sale or consumption of striped bass, blue claw crabs, and american eels, from the entire Newark Bay complex, which includes Newark Bay, Passaic River up to Hunter Dam, the Arthur Kill and the Kill van Kull, and also, the Hackensack River up to Oradell Dam.		
ACTION ITEMS:		

REFERENCE NO. 26

State circulates warnings on consuming certain fish

New Jersey state officials have issued some advisories and prohibitions regarding certain species of fish that may contain toxic chemicals and suggest methods of preparation to reduce exposure to contamination.

For the purposes of these alerts, the term "limited consumption" means not more than one meal per week of such fish, and persons of high risk — such as pregnant women, nursing mothers, women of child-bearing age, and young children — should not eat any such fish taken from designated regions. "Very limited consumption" restricts consumption to no more than one meal per month.


All sales of striped bass are prohibited. Limited consumption of all American eels is advised, especially in the Northeast region.

Otherwise, by region:

Newark Bay Complex (Newark Bay, Passaic River up to Dundee Dam, Hackensack River up to Oradell Dam, Arthur Kill, and Kill Van Kull and all tributaries) — sale or consumption of all fish from the tidal Passaic River, sale or consumption of striped bass and blue crabs, and sale of American eels from the entire complex are prohibited.

New Jersey waters of the Hudson River (up to the New Jersey-New York border, approximately four miles north of Alpine, and Upper New York Bay) — very limited consumption of striped bass, and limited consumption of white perch, white catfish, and bluefish is advised. The sale of American eels from these waters is prohibited.

Though the Lower New York



DON ECKER

OUTDOORS

Bay is not part of New Jersey waters, anglers fishing the lower bay, the upper part of New York Bay, and the Hudson River in New York waters are advised to follow New York state guidelines, which are similar to New Jersey's.

Raritan Bay Complex (New Jersey portion of Sandy Hook and Raritan bays and the tidal portion of the Raritan River upstream of the Route 1 bridge and New Brunswick) — limited consumption of striped bass, large bluefish (greater than 6 pounds or 24 inches), white catfish, and white perch.

Coastal New Jersey, including offshore state waters — limited consumption of striped bass and large bluefish.

Camden Area (including Strawbridge Lake, North and South branches of Pennsauken Creek, Cooper River and drainage, Cooper River Lake, Stewart Lake, Newton Lake) — sale and consumption of all fish prohibited.

Delaware River (between Interstate 276 bridge and tributary

Birch Creek, Logan Township, Gloucester County) — Advisory against consumption of channel catfish. Sale of this species is prohibited.

The following steps are strongly recommended to reduce exposure to contamination in fish: Remove belly-flaps, backstrap, and lateral-line tissue before cooking. Broil on a raised rack, boil in water, remove skin before cooking or canning. Discard all oils and fat, and liquids that contain them. Avoid coatings that hold oils and fats.

Blue crabs: Remove and discard hepatopancreas (tomalley, green gland, mustard) before cooking.

For more detailed information, write Bruce Ruppel, CN 409, Trenton, N.J. 08652.

• • •

The New Jersey Sportfishing Expo will be at the Morristown Armory, Western Avenue, Morristown, Feb. 15 and 16. Displays will include the newest fishing boats, accessories, and tackle. Seminar speakers include Al Ristori on salt water, Joe Humphreys on trout, Capt. Mike DiPalma on fishing Lake Ontario, and J.B. Kasper on fishing for Delaware River shad and bass.

There will be pro teams from Berkley/Trilene, Yankee Baits, and Zebco/Quantum to answer questions about bass fishing and tackle, and seminars for trout and bass beginners. Times are 9 a.m. to 8 p.m. Saturday and 10 a.m. to 6 p.m. Sunday. Admission is \$6. Children under 10 are admitted free. Door prizes will be awarded throughout the day. Phone (908) 876-5357 for more details.

REFERENCE NO. 27

TO: EL Beth Ltd file DATE: March 27, 1992
FROM: Claire Bumpis COPIES: —
SUBJECT: Lot and block number, and property acreage, EL Beth site,
REFERENCE: Perth Amboy, New Jersey.
cc


Reference: noted below

Per discussion with the Perth Amboy Tax Assessor's office, the property formerly E.L. Beth Ltd (now in the name of Jack and Robert Silverman) occupies Lot Nos. 4 and 4.18 of Block 238 in Perth Amboy. As the clerk recalls, EL Beth used "500 High Street" as a mailing address, although another property is listed in the tax book as 500 High Street. (During the Halliburton NUS on-site reconnaissance on March 4, 1992 this was clarified; the EL Beth site, set back off of the road, is reached through the gate entrance at 500 High Street).

The tax map^(Block 238) gives acreage values of 0.6610 acre for Lot 4, and 0.4062 acre for Lot 4.18.

SHEET No 44

Scale: 1" = 50'



REFERENCE NO. 28

CONTROL NO.:

J030

DATE:

March 24, 1992

TIME:

1320

DISTRIBUTION:

EL Beth file

Page 1 of 3

BETWEEN:

Tom Haborak, Sr.

OF:

Perth Amboy Fire
Department (Director)

PHONE:

(908) 826-1111

AND:

Claire Baupis

(NUS)

DISCUSSION:

I explained to Mr. Haborak that I was calling to inquire about the May, 1981 fire at E.L. Beth property and also about the July 1980 fire at Duane Marine property, in Perth Amboy. Mr. Haborak referred to his files as we spoke:

I asked about the cause of the May 1981 fire at E.L. Beth property; he said the fire at E.L. Beth occurred on Monday, May 18, 1981, and is recorded as a 'Structure fire'. Regarding the cause of the fire, he said "Ignition factor, combustibles too close to heat". I asked if any hazardous materials of concern were present - he said his file does not indicate any wastes; he said there are no special notes of any hazardous materials or quantities of materials. In regard to the cause of the fire, he said "kilns overheated and set pilings on fire". He said the fire was confined to 500 High Street; the fire did not extend to the General Cable Complex. I asked about the pier at E.L. Beth property; Mr. Haborak said it

ACTION ITEMS:

is not a pier, but rather, it is a building on pilings over the water; it had a concrete slab floor and the wood pilings beneath were set on fire, he said.

Mr. Haborak read the E.L. Beth file sheet to me:

May 18, 1981, Monday. Time of alarm 2:56 PM and fire was out on May 20 at 11:25 PM. E.L. Beth 500 High Street.

Alarm by telephone. Structure fire, had 4 engines and

CONTROL NO.: J030	DATE: March 24, 1992	TIME: 1320
DISTRIBUTION: EL Beth file Page 2 of 3		
BETWEEN: Tom Haborak, Sr.	OF: Beth Ambay Fire Department (Director)	PHONE: (908) 826-1111
AND: Claire Bumpis (NUS)		
DISCUSSION: (Continued)		
<p>one truck there; got mutual aid. About 100 firefighters.</p> <p>Area of origin: crawl space. Level of fire origin: below ground.</p> <p>Termination stage: flame (when broke out)</p> <p>Equipment involved in ignition: Kilns</p> <p>Form of heat ignition: Overheated Kilns</p> <p>Type of material ignited: wood pilings</p> <p>Ignition factor: Combustibles too close to heat.</p> <p>I asked Mr. Haborak if there are any statements in the file concerning amount of waste present, and he said 'no'.</p> <p>I asked about the 1980 'Duane Marine' fire. Mr. Haborak said he calls it the General Cable fire. He referred to the file and said: July 7, 1980, fire started at General Cable, at 42 Washington Street (which is at the corner of Washington and Rector Streets), and it spread to Duane Marine. He said it spread to the entire block. I asked if EL Beth was</p>		
<p><u>ACTION ITEMS:</u> possibly affected; he said it could have been, since they're all in the same area. He said the building at High and Buckingham Streets is General Cable - the building extended to the water; EL Beth is situated between Duane Marine and General Cable. He said the fire ran from Front Street, up Washington Street to High Street and halfway down High Street to the corner</p>		

CONTROL NO.: J030	DATE: March 24, 1992	TIME: 1320
DISTRIBUTION: EC Beth file Page 3 of 3		
BETWEEN: Tom Halorak, Sr.	OF: Ruth Cimbray fire Department (Director)	PHONE: (908) 826-1111
AND: Claire Bumpo (NUS)		
DISCUSSION: (continued) of High and Buckingham - the fire did not get into the building at High and Buckingham - it stopped there. The fire had started in the middle of the block and went west, east and north. He said that nothing is stated about chemicals at EC Beth property in the 1980 fire report. He said the General Cable (Duane Marine) fire was a week-long fire, lasting from Monday to Saturday. I asked if there is any file reference to chemicals present during the 1980 fire, and he said nothing is stated. Mr. Halorak said that the Middlesex County Prosecutor's Office, former arson task force, investigated the 1980 and 1981 fires, and that they might have information as well.		
ACTION ITEMS:		

CONTROL NO.: J030	DATE: March 25, 1992	TIME: 1250
DISTRIBUTION: EL Beth file		
BETWEEN: Investigator Ritz	OF: Middlesex County Prosecutor's Office	PHONE: 19081745-3300
AND: Claire Baranjo (NUS)		
DISCUSSION: Mr. Ritz returned my call. First, he said that according to his information, the EL Beth property is a church. (I then told him it was a foundry). He said that his reports are strictly first origin and cause reports, and that he wouldn't have hazardous materials information. He is referring to computer information as we speak, because the physical file is archived, he said. He said that the EL Beth fire is listed as an accidental fire. He read to me: "High and Washington Street, May 18, 1981, Victim listed as EL Beth". I also asked him about the July 1980 fire on the same block. He said that he doesn't know offhand if it entered the EL Beth property. He said it burned from High Street all the way to the river. I noted to him, however that reportedly, the fire didn't extend to the very northernmost part of the block, so maybe it did not enter the EL Beth property; also, since the pier was in use in 1981, it apparently wasn't affected by the 1980 fire - therefore, I did not ask him to check further on the extent of the 1980 fire.		

REFERENCE NO. 29

CONTROL NO.:

J030

DATE:

February 24, 1992

TIME:

~1355

DISTRIBUTION:

EL Beth file

Page 1 of 3

BETWEEN:

Carol Surgens, Esp

OF:

Jones and Day

PHONE:

(212) 326-8355

AND:

Claire Bampfis

(NUS)

DISCUSSION:

The address to which I can send letter to Mr. Robert Silverman and Mr. Jack Silverman regarding on-site reconnaissance is:
23 Audubon Court, Short Hills, New Jersey 07078.

Mrs. Surgens and I discussed the site. She said it's right on the edge of Arthur Kill. The manufacturing plant was on a wooden pier that extended over the Kill. She said about one acre of the property is on land. She said the owner said that most of the property is concrete paved. A garage is present. The manufacturing facility is about 11,000 to 12,000 sq. feet. They applied for and received Part A RCRA permit as a storage facility in the late 1970's, about 1979 she said. They bought the operating company that was present at the location. In 1979 to 1980 they stored certain hazardous wastes on site for more than 90 days, and so acquired a Part A RCRA permit. She said "the waste was listed as

ACTION ITEMS:

acid waste; it was ammonium chloride in solid form - she said it was molten when skimmed, and it solidified in drums. She said the solder manufacturing operated there. She said metals were molten in water for recovery. Ammonium chloride was skimmed off of the surface and was stored in 55 gallon drums, on the land portion of the property, on a concrete slab. Part of the storage area

CONTROL NO.:

J030

DATE:

February 24, 1992

TIME:

~ 1355

DISTRIBUTION:

EL Both file

Page 2 of 3

BETWEEN:

Carol Sengers, Esp

OF:

Jones and Day

PHONE:

(212) 326-8355

AND:

Chaine Baurio

(NUS)

DISCUSSION: (continued)

was in a garage, with a concrete floor. She said materials were stored 90 days or less. She said that after 1980, the site no longer stored ammonium chloride, because they no longer used the ammonium chloride process - it was just used in 1979 and 1980. She said that regarding other wastes, they'll explain further. May have had lube oil, classed as hazardous in New Jersey, but not by federal law. May have been drums of baghouse dust. No underground tanks are present at the site. To the extent of her client's knowledge, there are now no drums present. She said that they "ceased operations and moved, and then in 1981 the fire occurred and the facility burned down". She said that what's left are: concrete land surface, part of a pier, ruins of the building on pier. She said, regarding the pier and ruins, it is totally at our own risk to walk

ACTION ITEMS:

8 - there, as it's very, very unsafe. I told her we will not walk there. I asked if the pier is fenced off, and she said she's not sure. She said some fencing is present, but that she's not sure how much. She said the area is subject to vandalism. I asked if formerly there were underground tanks; she said she's not sure, but the owners can discuss it further. (continued)

CONTROL NO.:

J030

DATE:

February 24, 1992

TIME:

~1355

DISTRIBUTION:

EL Beth file

page 3 of 3

BETWEEN:

Carol Surgens, Esq

OF:

Jones and Day

PHONE:

(212) 326-8355

AND:

Claire Bumpo

(NUS)

DISCUSSION: (continued)

She said that one of the baghouses might still be present. She believes that only a residue of dust may remain, and possibly some scrap metal. Drums were removed.

Regarding planned HUS on-site reconnaissance, she said they prefer that decon water from recon be drummed and removed, rather than disposed of on site; they're concerned about environmental (legal) complications. But, she said, the site is mostly paved.

She said the site is adjacent to Duane Marine site, and N.J. DEP has been to Duane Marine, investigating; Duane Marine was a very large industrial operation, and had a fire.

Regarding EL Beth property, utilities had been in pipes, buried in the ground, and in some places, where utilities were removed, it is dug up, and looks like trenching.

we established that the on-site reconnaissance at the EL Beth property in Beth Amberg will be on March 4th, at 9:30 AM, and that we'll meet at the property entrance. She will inquire if the property owners have any documents to provide.

ACTION ITEMS:

8

REFERENCE NO. 30

toxicity (rat) of less than 50 milligrams per kilogram, an inhalation LC 50 toxicity (rat) of less than 2 milligrams per liter, or a dermal LD 50 toxicity (rabbit) of less than 200 milligrams per kilogram or is otherwise capable of causing or significantly contributing to an increase in serious irreversible, or incapacitating reversible, illness. (Waste listed in accordance with these criteria will be designated Acute Hazardous Waste.)

(3) It contains any of the toxic constituents listed in Appendix VIII unless, after considering any of the following factors, the Administrator concludes that the waste is not capable of posing a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported or disposed of, or otherwise managed:

(i) The nature of the toxicity presented by the constituent.

(ii) The concentration of the constituent in the waste.

(iii) The potential of the constituent or any toxic degradation product of the constituent to migrate from the waste into the environment under the types of improper management considered in paragraph (a)(3)(vii) of this section.

(iv) The persistence of the constituent or any toxic degradation product of the constituent.

(v) The potential for the constituent or any toxic degradation product of the constituent to degrade into non-harmful constituents and the rate of degradation.

(vi) The degree to which the constituent or any degradation product of the constituent bioaccumulates in ecosystems.

(vii) The plausible types of improper management to which the waste could be subjected.

(viii) The quantities of the waste generated at individual generation sites or on a regional or national basis.

(ix) The nature and severity of the human health and environmental damage that has occurred as a result of the improper management of wastes containing the constituent.

(x) Action taken by other governmental agencies or regulatory programs based on the health or environ-

mental hazard posed by the waste or waste constituent.

(xi) Such other factors as may be appropriate.

Substances will be listed on Appendix VIII only if they have been shown in scientific studies to have toxic, carcinogenic, mutagenic or teratogenic effects on humans or other life forms.

(Wastes listed in accordance with these criteria will be designated Toxic wastes.)

(b) The Administrator may list classes or types of solid waste as hazardous waste if he has reason to believe that individual wastes, within the class or type of waste, typically or frequently are hazardous under the definition of hazardous waste found in section 1004(5) of the Act.

(c) The Administrator will use the criteria for listing specified in this section to establish the exclusion limits referred to in § 261.5(c).

Subpart C—Characteristics of Hazardous Waste

§ 261.20 General.

(a) A solid waste, as defined in § 261.2, which is not excluded from regulation as a hazardous waste under § 261.4(b), is a hazardous waste if it exhibits any of the characteristics identified in this subpart.

[Comment: § 262.11 of this chapter sets forth the generator's responsibility to determine whether his waste exhibits one or more of the characteristics identified in this subpart.]

(b) A hazardous waste which is identified by a characteristic in this subpart, but is not listed as a hazardous waste in Subpart D, is assigned the EPA Hazardous Waste Number set forth in the respective characteristic in this subpart. This number must be used in complying with the notification requirements of section 3010 of the Act and certain recordkeeping and reporting requirements under Parts 262 through 265, 268, and Part 270 of this chapter.

(c) For purposes of this subpart, the Administrator will consider a sample obtained using any of the applicable sampling methods specified in Appen-

Environmental Protection Agency

dix I to be a representative sample within the meaning of Part 260 of this chapter.

[Comment: Since the Appendix I sampling methods are not being formally adopted by the Administrator, a person who desires to employ an alternative sampling method is not required to demonstrate the equivalency of his method under the procedures set forth in §§ 260.20 and 260.21.]

[45 FR 33119, May 19, 1980, as amended at 48 FR 14294, Apr. 1, 1983; 51 FR 40636, Nov. 7, 1986]

§ 261.21 Characteristic of ignitability.

(a) A solid waste exhibits the characteristic of ignitability if a representative sample of the waste has any of the following properties:

(1) It is a liquid, other than an aqueous solution containing less than 24 percent alcohol by volume and has flash point less than 60°C (140°F), as determined by a Pensky-Martens Closed Cup Tester, using the test method specified in ASTM Standard D-93-79 or D-93-80 (incorporated by reference, see § 260.11), or a Setaflash Closed Cup Tester, using the test method specified in ASTM Standard D-3278-78 (incorporated by reference, see § 260.11), or as determined by an equivalent test method approved by the Administrator under procedures set forth in §§ 260.20 and 260.21.

(2) It is not a liquid and is capable, under standard temperature and pressure, of causing fire through friction, absorption of moisture or spontaneous chemical changes and, when ignited, burns so vigorously and persistently that it creates a hazard.

(3) It is an ignitable compressed gas as defined in 49 CFR 173.300 and as determined by the test methods described in that regulation or equivalent test methods approved by the Administrator under §§ 260.20 and 260.21.

(4) It is an oxidizer as defined in 49 CFR 173.151.

(b) A solid waste that exhibits the characteristic of ignitability, but is not listed as a hazardous waste in Subpart D, has the EPA Hazardous Waste Number of D001.

[45 FR 33119, May 19, 1980, as amended at 48 FR 35247, July 7, 1983]

§ 261.22 Characteristic of corrosivity.

(a) A solid waste exhibits the characteristic of corrosivity if a representative sample of the waste has either of the following properties:

(1) It is aqueous and has a pH less than or equal to 2 or greater than or equal to 12.5, as determined by a pH meter using either an EPA test method or an equivalent test method approved by the Administrator under the procedures set forth in §§ 260.20 and 260.21. The EPA test method for pH is specified as Method 5.2 in "Test Methods for the Evaluation of Solid Waste, Physical/Chemical Methods" (incorporated by reference, see § 260.11).

(2) It is a liquid and corrodes steel (SAE 1020) at a rate greater than 6.35 mm (0.250 inch) per year at a test temperature of 55°C (130°F) as determined by the test method specified in NACE (National Association of Corrosion Engineers) Standard TM-01-69 as standardized in "Test Methods for the Evaluation of Solid Waste, Physical/Chemical Methods" (incorporated by reference, see § 260.11) or an equivalent test method approved by the Administrator under the procedures set forth in §§ 260.20 and 260.21.

(b) A solid waste that exhibits the characteristic of corrosivity, but is not listed as a hazardous waste in Subpart D, has the EPA Hazardous Waste Number of D002.

[45 FR 33119, May 19, 1980, as amended at 48 FR 35247, July 7, 1983]

§ 261.23 Characteristic of reactivity.

(a) A solid waste exhibits the characteristic of reactivity if a representative sample of the waste has any of the following properties:

(1) It is normally unstable and readily undergoes violent change without detonating.

(2) It reacts violently with water.

(3) It forms potentially explosive mixtures with water.

(4) When mixed with water, it generates toxic gases, vapors or fumes in a quantity sufficient to present a danger to human health or the environment.

(5) It is a cyanide or sulfide bearing waste which, when exposed to pH conditions between 2 and 12.5, can gener-

Industry and EPA hazardous waste No.	Hazardous waste	Hazard code
F024.....	Wastes, including but not limited to, distillation residues, heavy ends, tars, and reactor clean-out wastes from the production of chlorinated aliphatic hydrocarbons, having carbon content from one to five, utilizing free radical catalyzed processes. (This listing does not include light ends, spent filters and filter aids, spent desiccants, wastewater, wastewater treatment sludges, spent catalysts, and wastes listed in § 261.32.)	(T)
F020.....	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the production or manufacturing use (as a reactant, chemical intermediate, or component in a formulating process) of tri- or tetrachlorophenol, or of intermediates used to produce their pesticide derivatives. (This listing does not include wastes from the production of hexachlorophene from highly purified 2,4,5-trichlorophenol.)	(H)
F021.....	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the production or manufacturing use (as a reactant, chemical intermediate, or component in a formulating process) of pentachlorophenol, or of intermediates used to produce its derivatives.	(H)
F022.....	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the manufacturing use (as a reactant, chemical intermediate, or component in a formulating process) of tetra-, penta-, or hexachlorobenzenes under alkaline conditions.	(H)
F023.....	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the production of materials on equipment previously used for the production or manufacturing use (as a reactant, chemical intermediate, or component in a formulating process) of tri- and tetrachlorophenols. (This listing does not include wastes from equipment used only for the production or use of hexachlorophene from highly purified 2,4,5-trichlorophenol.)	(H)
F026.....	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the production of materials on equipment previously used for the manufacturing use (as a reactant, chemical intermediate, or component in a formulating process) of tetra-, penta-, or hexachlorobenzenes under alkaline conditions.	(H)
F027.....	Discarded unused formulations containing tri-, tetra-, or pentachlorophenol or discarded unused formulations containing compounds derived from these chlorophenols. (This listing does not include formulations containing hexachlorophene synthesized from prepurified 2,4,5-trichlorophenol as the sole component.)	(H)
F028.....	Residues resulting from the incineration or thermal treatment of soil contaminated with EPA Hazardous Waste Nos. F020, F021, F022, F023, F026, and F027.	(T)

* (R,T) should be used to specify mixtures containing ignitable and toxic constituents.

[46 FR 4617, Jan. 16, 1981, as amended at 46 FR 27477, May 20, 1981; 49 FR 5312, Feb. 10, 1984; 49 FR 37070, Sept. 21, 1984; 50 FR 645, Jan. 4, 1985; 50 FR 3000, Jan. 14, 1985; 50 FR 53319, Dec. 31, 1985; 51 FR 2702, Jan. 21, 1986; 51 FR 6541, Feb. 25, 1986]

§ 261.32 Hazardous wastes from specific sources.

The following solid wastes are listed hazardous wastes from specific sources unless they are excluded under §§ 260.20 and 260.22 and listed in Appendix IX.

Industry and EPA hazardous waste No.	Hazardous waste	Hazard code
Wood preservation: K001.....	Bottom sediment sludge from the treatment of wastewaters from wood preserving processes that use creosote and/or pentachlorophenol.	(T)
Inorganic pigments: K002.....	Wastewater treatment sludge from the production of chrome yellow and orange pigments.	(T)
K003.....	Wastewater treatment sludge from the production of molybdate orange pigments.	(T)
K004.....	Wastewater treatment sludge from the production of zinc yellow pigments.	(T)
K005.....	Wastewater treatment sludge from the production of chrome green pigments.	(T)
K006.....	Wastewater treatment sludge from the production of chrome oxide green pigments (anhydrous and hydrated).	(T)
K007.....	Wastewater treatment sludge from the production of iron blue pigments.	(T)
K008.....	Oven residue from the production of chrome oxide green pigments.	(T)
Organic chemicals: K009.....	Distillation bottoms from the production of acetaldehyde from ethylene.	(T)
K010.....	Distillation side cuts from the production of acetaldehyde from ethylene.	(T)
K011.....	Bottom stream from the wastewater stripper in the production of acrylonitrile.	(R, T)
K013.....	Bottom stream from the acetonitrile column in the production of acrylonitrile.	(R, T)
K014.....	Bottoms from the acetonitrile purification column in the production of acrylonitrile.	(T)
K015.....	Still bottoms from the distillation of benzyl chloride.	(T)

Industry and EPA hazardous waste No.	Hazardous waste	Hazard code
K016.....	Heavy ends or distillation residues from the production of carbon tetrachloride.	(T)
K017.....	Heavy ends (still bottoms) from the purification column in the production of epichlorohydrin.	(T)
K018.....	Heavy ends from the fractionation column in ethyl chloride production.	(T)
K019.....	Heavy ends from the distillation of ethylene dichloride in ethylene dichloride production.	(T)
K020.....	Heavy ends from the distillation of vinyl chloride in vinyl chloride monomer production.	(T)
K021.....	Aqueous spent antimony catalyst waste from fluoromethanes production.	(T)
K022.....	Distillation bottom tars from the production of phenol/acetone from cumene.	(T)
K023.....	Distillation light ends from the production of phthalic anhydride from naphthalene.	(T)
K024.....	Distillation bottoms from the production of phthalic anhydride from naphthalene.	(T)
K025.....	Distillation light ends from the production of phthalic anhydride from ortho-xylene.	(T)
K026.....	Distillation bottoms from the production of phthalic anhydride from ortho-xylene.	(T)
K027.....	Stripping still tails from the production of methyl ethyl pyridines.	(T)
K028.....	Centrifuge and distillation residues from toluene diisocyanate production.	(R, T)
K029.....	Spent catalyst from the hydrochlorinator reactor in the production of 1,1,1-trichloroethane.	(T)
K030.....	Waste from the product steam stripper in the production of 1,1,1-trichloroethane.	(T)
K031.....	Distillation bottoms from the production of 1,1,1-trichloroethane.	(T)
K032.....	Heavy ends from the heavy ends column from the production of 1,1,1-trichloroethane.	(T)
K033.....	Column bottoms or heavy ends from the combined production of trichloroethylene and perchloroethylene.	(T)
K034.....	Distillation bottoms from aniline production.	(T)
K035.....	Process residues from aniline extraction from the production of aniline.	(T)
K036.....	Combined wastewater streams generated from nitrobenzene/aniline production.	(T)
K037.....	Distillation or fractionation column bottoms from the production of chlorobenzenes.	(T)
K038.....	Separated aqueous stream from the reactor product washing step in the production of chlorobenzenes.	(T)
K111.....	Product washwaters from the production of dinitrotoluene via nitration of toluene.	(C, T)
K112.....	Reaction by-product water from the drying column in the production of toluenediamine via hydrogenation of dinitrotoluenes.	(T)
K113.....	Condensed liquid light ends from the purification of toluenediamine in the production of toluenediamine via hydrogenation of dinitrotoluenes.	(T)
K114.....	Vinels from the purification of toluenediamine in the production of toluenediamine via hydrogenation of dinitrotoluenes.	(T)
K115.....	Heavy ends from the purification of toluenediamine in the production of toluenediamine via hydrogenation of dinitrotoluenes.	(T)
K116.....	Organic condensate from the solvent recovery column in the production of toluene diisocyanate via phosgenation of toluenediamine.	(T)
K117.....	Wastewater from the reactor vent gas scrubber in the production of ethylene dibromide via bromination of ethene.	(T)
K118.....	Spent adsorbent solids from purification of ethylene dibromide in the production of ethylene dibromide via bromination of ethene.	(T)
K136.....	Still bottoms from the purification of ethylene dibromide in the production of ethylene dibromide via bromination of ethene.	(T)
Inorganic chemicals: K071.....	Brine purification mude from the mercury cell process in chlorine production, where separately prepurified brine is not used.	(T)
K073.....	Chlorinated hydrocarbon waste from the purification step of the diaphragm cell process using graphite anodes in chlorine production.	(T)
K108.....	Wastewater treatment sludge from the mercury cell process in chlorine production.	(T)
Pesticides: K031.....	By-product salts generated in the production of MSMA and cacodylic acid.	(T)
K032.....	Wastewater treatment sludge from the production of chlordane.	(T)
K033.....	Wastewater and scrub water from the chlorination of cyclopentadiene in the production of chlordane.	(T)
K034.....	Filter solids from the filtration of hexachlorocyclopentadiene in the production of chlordane.	(T)
K087.....	Vacuum stripper discharge from the chlordane chlorinator in the production of chlordane.	(T)
K035.....	Wastewater treatment sludges generated in the production of creosote.	(T)
K036.....	Still bottoms from toluene reclamation distillation in the production of disulfoton.	(T)
K037.....	Wastewater treatment sludges from the production of disulfoton.	(T)
K038.....	Wastewater from the washing and stripping of phosphate production.	(T)
K039.....	Filter cake from the filtration of diethylphosphorodithioic acid in the production of phosphate.	(T)
K040.....	Wastewater treatment sludge from the production of phosphate.	(T)
K041.....	Wastewater treatment sludge from the production of toxaphene.	(T)
K096.....	Untreated process wastewater from the production of toxaphene.	(T)

Industry and EPA hazardous waste No.	Hazardous waste	Hazard code
K042	Heavy ends or distillation residues from the distillation of tetrachlorobenzene in the production of 2,4,5-T.	(T)
K043	2,6-Dichlorophenol waste from the production of 2,4-D	(T)
K046	Unreated wastewater from the production of 2,4-D	(T)
K123	Process wastewater (including supernates, filtrates, and washwaters) from the production of ethylenedithiocarbamic acid and its salt.	(T)
K124	Reactor vent scrubber water from the production of ethylenedithiocarbamic acid and its salts.	(C, T)
K125	Filtration, evaporation, and centrifugation solids from the production of ethylenedithiocarbamic acid and its salts.	(T)
K126	Baghouse dust and floor sweepings in milling and packaging operations from the production or formulation of ethylenedithiocarbamic acid and its salts.	(T)
Explosives:		
K044	Wastewater treatment sludges from the manufacturing and processing of explosives	(R)
K045	Spent carbon from the treatment of wastewater containing explosives	(R)
K046	Wastewater treatment sludges from the manufacturing, formulation and loading of lead-based initiating compounds.	(R)
K047	Pink/red water from TNT operations	(T)
Petroleum refining:		
K048	Dissolved air flotation (DAF) float from the petroleum refining industry	(T)
K049	Slip oil emulsion solids from the petroleum refining industry	(T)
K050	Heat exchanger bundle cleaning sludge from the petroleum refining industry	(T)
K051	API separator sludge from the petroleum refining industry	(T)
K052	Tank bottoms (lead) from the petroleum refining industry	(T)
Iron and steel:		
K051	Emission control dust/sludge from the primary production of steel in electric furnaces.	(T)
K052	Spent pickle liquor generated by steel finishing operations of facilities within the iron and steel industry (SIC Codes 331 and 332).	(C, T)
Secondary lead:		
K099	Emission control dust/sludge from secondary lead smelting	(T)
K100	Waste leaching solution from acid leaching of emission control dust/sludge from secondary lead smelting.	(T)
Veterinary pharmaceuticals:		
K084	Wastewater treatment sludges generated during the production of veterinary pharmaceuticals from arsenic or organo-arsenic compounds.	(T)
K101	Distillation tar residues from the distillation of aniline-based compounds in the production of veterinary pharmaceuticals from arsenic or organo-arsenic compounds.	(T)
K102	Residue from the use of activated carbon for decolorization in the production of veterinary pharmaceuticals from arsenic or organo-arsenic compounds.	(T)
Ink formulation: K086	Solvent washes and sludges, caustic washes and sludges, or water washes and sludges from cleaning tube and equipment used in the formulation of ink from pigments, driers, soaps, and stabilizers containing chromium and lead.	(T)
Coking:		
K060	Ammonia still lime sludge from coking operations	(T)
K067	Decanter tank tar sludge from coking operations	(T)

(46 FR 4618, Jan. 16, 1981, as amended at 46 FR 27476-27477, May 20, 1981; 49 FR 37070, Sept. 21, 1984; 50 FR 42942, Oct. 23, 1985; 51 FR 5330, Feb. 13, 1986; 51 FR 19322, May 28, 1986; 51 FR 33612, Sept. 22, 1986; 51 FR 37729, Oct. 24, 1986; 52 FR 28698, Aug. 3, 1987)

§ 261.33 Discarded commercial chemical products, off-specification species, container residues, and spill residues thereof.

The following materials or items are hazardous wastes if and when they are discarded or intended to be discarded as described in § 261.2(a)(2)(i), when they are mixed with waste oil or used oil or other material and applied to the land for dust suppression or road treatment, when they are otherwise applied to the land in lieu of their

original intended use or when they are contained in products that are applied to the land in lieu of their original intended use, or when, in lieu of their original intended use, they are produced for use as (or as a component of) a fuel, distributed for use as a fuel, or burned as a fuel.

(a) Any commercial chemical product, or manufacturing chemical intermediate having the generic name listed in paragraph (e) or (f) of this section.

Environmental Protection Agency

(b) Any off-specification commercial chemical product or manufacturing chemical intermediate which, if it met specifications, would have the generic name listed in paragraph (e) or (f) of this section.

(c) Any residue remaining in a container or in an inner liner removed from a container that has held any commercial chemical product or manufacturing chemical intermediate having the generic name listed in paragraph (e) of this section, unless the container is empty as defined in § 261.7(b)(3) of the chapter.

(Comment: Unless the residue is being beneficially used or reused, or legitimately recycled or reclaimed; or being accumulated, stored, transported or treated prior to such use, re-use, recycling or reclamation, EPA considers the residue to be intended for discard, and thus, a hazardous waste. An example of a legitimate re-use of the residue would be where the residue remains in the container and the container is used to hold the same commercial chemical product or manufacturing chemical intermediate it previously held. An example of the discard of the residue would be where the drum is sent to a drum reconditioner who reconditions the drum but discards the residue.)

(d) Any residue or contaminated soil, water or other debris resulting from the cleanup of a spill into or on any land or water of any commercial chemical product or manufacturing chemical intermediate having the generic name listed in paragraph (e) or (f) of this section, or any residue or contaminated soil, water or other debris resulting from the cleanup of a spill, into or on any land or water, of any off-specification chemical product and manufacturing chemical intermediate

which, if it met specifications, would have the generic name listed in paragraph (e) or (f) of this section.

(Comment: The phrase "commercial chemical product or manufacturing chemical intermediate having the generic name listed in . . ." refers to a chemical substance which is manufactured or formulated for commercial or manufacturing use which consists of the commercially pure grade of the chemical, any technical grades of the chemical that are produced or marketed, and all formulations in which the chemical is the sole active ingredient. It does not refer to a material, such as a manufacturing process waste, that contains any of the substances listed in paragraph (e) or (f). Where a manufacturing process waste is deemed to be a hazardous waste because it contains a substance listed in paragraph (e) or (f), such waste will be listed in either § 261.31 or § 261.32 or will be identified as a hazardous waste by the characteristics set forth in Subpart C of this part.)

(e) The commercial chemical products, manufacturing chemical intermediates or off-specification commercial chemical products or manufacturing chemical intermediates referred to in paragraphs (a) through (d) of this section, are identified as acute hazardous wastes (H) and are subject to be the small quantity exclusion defined in § 261.5(e).

(Comment: For the convenience of the regulated community the primary hazardous properties of these materials have been indicated by the letters T (Toxicity), and R (Reactivity). Absence of a letter indicates that the compound only is listed for acute toxicity.)

These wastes and their corresponding EPA Hazardous Waste Numbers are:

Hazardous waste No.	Chemical abstracts No.	Substance
P023	107-20-0	Acetaldehyde, chloro-
P002	591-08-2	Acetamide, N-(aminothiomethyl)-
P067	640-19-7	Acetamide, 2-fluoro-
P068	62-74-8	Acetic acid, fluoro-, sodium salt
P002	591-08-2	1-Acetyl-2-thiourea
P003	107-02-6	Acrolein
P070	118-06-3	Aldicarb
P004	309-00-2	Aldrin
P005	107-18-6	Allyl alcohol
P006	20858-73-8	Aluminum phosphide (R,T)
P007	2763-98-4	5-(Aminomethyl)-3-isoxazolol
P008	504-24-5	4-Aminopyridine
P009	131-74-8	Ammonium picrate (R)

TABLE 3—SAMPLING AND ANALYSIS METHODS CONTAINED IN SW-846—Continued

Title	First edition		Second edition	
	Section No.	Method No.	Section No.	Method No.
Sample Analysis Request Sheet	2.0-9		1.3.5	
Sample Delivery to Laboratory	2.0-10		1.3.6	
Shipping of Samples	2.0-10		1.3.7	
Receipt and Logging of Sample	2.0-12		1.3.8	
Assignment of Sample for Analysis	2.0-13		1.3.9	
Sampling Methodology	3.0		1.4	
Containers	3.2-2		1.4.1	
Tanks	3.2-2		1.4.2	
Waste Piles	3.2-2		1.4.3	
Landfills and Lagoons	3.2-2		1.4.4	
Waste Evaluation Procedures			2.0	
Characteristics of Hazardous Waste			2.1	
Ignitability	4.0		2.1.1	
Pensky-Martens Closed-Cup Method	4.1		2.1.1	1010
Reflash Closed-Cup Method	4.1		2.1.1	1020
Corrosivity	5.0		2.1.2	
Corrosivity Toward Steel	5.3		2.1.2	1110
Reactivity	6.0		2.1.3	
Extraction Procedure Toxicity	7.0		2.1.4	
Extraction Procedure Toxicity Test	7.1, 7.2, 7.5			
Method and Structural Integrity Test	7.4		2.1.4	1310
Sample Workup Techniques			4.0	
Inorganic Techniques	8.49		4.1	
Acid Digestion for Flame AAS			4.1	3010
Acid Digestion for Furnace AAS			4.1	3020
Acid Digestion of Oil, Grease, or Wax	8.49-9		4.1	3030
Dissolution Procedure for Oil, Grease or Wax	8.49-9			
Alkaline Digestion	8.0	8.459	4.1	3080
Organic Techniques	9.0		4.2	
Separatory Funnel Liquid-Liquid Extraction	9.0	9.1	4.2	3510
Continuous Liquid-Liquid Extraction	9.0	9.01	4.2	3520
Acid-Base Cleanup Extraction	9.0	9.04	4.2	3530
Schmidt Extraction	9.0	9.05	4.2	3540
Sonication Extraction	9.0	9.06	4.2	3550
Sample Introduction Techniques			5.0	
Headspace	8.0	8.82	5.0	5020
Purge-and-Trap	8.0	8.83	5.0	5030
Inorganic Analytical Methods	8.0		7.0	
Antimony, Flame AAS	8.0	8.50	7.0	7470
Antimony, Furnace AAS	8.0	8.50	7.0	7471
Arsenic, Flame AAS	8.0	8.51	7.0	7080
Arsenic, Furnace AAS	8.0	8.51	7.0	7081
Barium, Flame AAS	8.0	8.52	7.0	7080
Barium, Furnace AAS	8.0	8.52	7.0	7081
Cadmium, Flame AAS	8.0	8.53	7.0	7130
Cadmium, Furnace AAS	8.0	8.53	7.0	7131
Chromium, Flame AAS	8.0	8.54	7.0	7080
Chromium, Furnace AAS	8.0	8.54	7.0	7191
Chromium, Hexavalent, Coprecipitation	8.0	8.545	7.0	7195
Chromium, Hexavalent, Colorimetric	8.0	8.546	7.0	7196
Chromium, Hexavalent, Chelation	8.0	8.547	7.0	7197
Lead, Flame AAS	8.0	8.56	7.0	7420
Lead, Furnace AAS	8.0	8.56	7.0	7421
Mercury, Cold Vapor, Liquid	8.0	8.57	7.0	7470
Mercury, Cold Vapor, Solid	8.0	8.57	7.0	7471
Nickel, Flame AAS	8.0	8.58	7.0	7520
Nickel, Furnace AAS	8.0	8.58	7.0	7521
Selenium, Flame AAS	8.0	8.59	7.0	7740
Selenium, Gaseous Hydride AAS	8.0	8.59	7.0	7741
Silver, Flame AAS	8.0	8.60	7.0	7780
Silver, Furnace AAS	8.0	8.60	7.0	7781
Organic Analytical Methods	8.0		8.0	
Gas Chromatographic Methods	8.0		8.1	
Halogenated Volatile Organics	8.0	8.01	8.1	8010
Nonhalogenated Volatile Organics	8.0	8.01	8.1	8015
Aromatic Volatile Organics	8.0	8.02	8.1	8020
Acrolein, Acrylonitrile, Acetonitrile	8.0	8.03	8.1	8030
Phenols	8.0	8.04	8.1	8040

TABLE 3—SAMPLING AND ANALYSIS METHODS CONTAINED IN SW-846—Continued

Title	First edition		Second edition	
	Section No.	Method No.	Section No.	Method No.
Phthalate Esters	8.0	8.06	8.1	8080
Organochlorine Pesticides and PCBs	8.0	8.06	8.1	8080
Nitroaromatics and Cyclic Ketones	8.0	8.09	8.1	8090
Polynuclear Aromatic Hydrocarbons	8.0	8.10	8.1	8100
Chlorinated Hydrocarbons	8.0	8.12	8.1	8120
Organophosphorus Pesticides	8.0	8.22	8.1	8140
Chlorinated Herbicides	8.0	8.40	8.1	8150
Gas Chromatographic/Mass Spectroscopy Methods (GC/MS)	8.0		8.2	
GC/MS Volatiles	8.0	8.24	8.2	8240
GC/MS Semi-Volatiles, Packed Column	8.0	8.25	8.2	8250
GC/MS Semi-Volatiles, Capillary	8.0	8.27	8.2	8270
Analysis of Chlorinated Dioxins and Dibenzofurans			8.2	8280
High Performance Liquid Chromatographic Methods (HPLC)	8.0		8.3	
Polynuclear Aromatic Hydrocarbons	8.0	8.10	8.3	8310
Miscellaneous Analytical Methods	8.0		9.0	
Cyanide, Total and Amenable to Chlorination	8.0	8.55	9.0	9010
Total Organic Halogen (TOX)	8.0	8.66	9.0	9020
Sulfides	8.0	8.67	9.0	9030
pH Measurement	8.0	8.2	9.0	9040
Quality Control/Quality Assurance	10.0		10.1	
Introduction	10.0		10.1	
Program Design	10.0		10.2	
Sampling	10.0		10.3	
Analysis	10.0		10.4	
Data Handling	10.0		10.5	

¹See specific metal.

[48 FR 15257, Apr. 8, 1983, as amended at 50 FR 3069, Jan. 14, 1985; 50 FR 42942, Oct. 23, 1985; 51 FR 5330, Feb. 13, 1986; 51 FR 6541, Feb. 25, 1986; 51 FR 37729, Oct. 24, 1986]

APPENDIX IV—[RESERVED FOR RADIOACTIVE WASTE TEST METHODS]

APPENDIX V—[RESERVED FOR INFECTIOUS WASTE TREATMENT SPECIFICATIONS]

APPENDIX VI—[RESERVED FOR ETIOLOGIC AGENTS]

APPENDIX VII—BASIS FOR LISTING HAZARDOUS WASTE

EPA hazardous waste No.	Hazardous constituents for which listed
F005	Toluene, methyl ethyl ketone, carbon disulfide, isobutanol, pyridine, 2-ethoxyethanol, benzene, 2-nitropropane.
F008	Cadmium, hexavalent chromium, nickel, cyanide (complexed).
F007	Cyanide (salts).
F008	Cyanide (salts).
F009	Cyanide (salts).
F010	Cyanide (salts).
F011	Cyanide (salts).
F012	Cyanide (complexed).
F019	Hexavalent chromium, cyanide (complexed).
F020	Tetra- and pentachlorodibenzo-p-dioxins; tetra- and pentachlorodibenzofurans; tri- and tetrachlorophenols and their chlorophenoxy derivative acids, esters, ethers, amine and other salts.
F021	Penta- and hexachlorodibenzo-p-dioxins; penta- and hexachlorodibenzofurans; pentachlorophenol and its derivatives.
F022	Tetra-, penta-, and hexachlorodibenzo-p-dioxins; tetra-, penta-, and hexachlorodibenzofurans.
F023	Tetra-, and pentachlorodibenzo-p-dioxins; tetra- and pentachlorodibenzofurans; tri- and tetrachlorophenols and their chlorophenoxy derivative acids, esters, ethers, amine and other salts.
F001	Tetrachloroethylene, methylene chloride trichloroethylene, 1,1,1-trichloroethane, carbon tetrachloride, chlorinated fluorocarbons.
F002	Tetrachloroethylene, methylene chloride, trichloroethylene, 1,1,1-trichloroethane, 1,1,2-trichloroethane, chlorobenzene, 1,1,2-trichloro-1,2,2-trichloroethane, ortho-dichlorobenzene, trichlorofluoromethane.
F003	N.A.
F004	Cresols and cresylic acid, nitrobenzene.

EPA hazard-ous waste No.	Hazardous constituents for which listed	EPA hazard-ous waste No.	Hazardous constituents for which listed
P008	Chloromethane, dichloromethane, trichloromethane, carbon tetrachloride, chloroethylene, 1,1-dichloroethane, 1,2-dichloroethane, trans-1,2-dichloroethylene, 1,1-dichloroethene, 1,1,1-trichloroethane, 1,1,2-trichloroethane, trichloroethylene, 1,1,2,2-tetrachloroethane, 1,1,2,2-tetrachloroethene, tetrachloroethylene, pentachloroethane, hexachloroethane, allyl chloride (3-chloropropene), dichloropropane, dichloropropane, 2-chloro-1,3-butadiene, hexachloro-1,3-butadiene, hexachlorocyclopentadiene, hexachlorocyclohexane, benzene, chlorobenzene, dichlorobenzenes, 1,2,4-trichlorobenzene, tetrachlorobenzene, pentachlorobenzene, hexachlorobenzene, toluene, naphthalene.	K020	Ethylene dichloride, 1,1,1-trichloroethane, 1,1,2-trichloroethane, tetrachloroethane (1,1,2,2-tetrachloroethane and 1,1,1,2-tetrachloroethane), trichloroethylene, tetrachloroethylene, carbon tetrachloride, chloroform, vinyl chloride, vinylidene chloride.
P009	Tetra-, penta-, and hexachlorodibenzo-p-dioxins; tetra-, penta-, and hexachlorodibenzofurans.	K021	Antimony, carbon tetrachloride, chloroform.
P027	Tetra-, penta-, and hexachlorodibenzo-p-dioxins; tetra-, penta-, and hexachlorodibenzofurans; tri-, tetra-, and pentachlorophenols and their chlorophenoxy derivative acids, esters, ethers, amine and other salts.	K022	Phenol, tars (polycyclic aromatic hydrocarbons).
P028	Tetra-, penta-, and hexachlorodibenzo-p-dioxins; tetra-, penta-, and hexachlorodibenzofurans; tri-, tetra-, and pentachlorophenols and their chlorophenoxy derivative acids, esters, ethers, amine and other salts.	K023	Phthalic anhydride, maleic anhydride.
K001	Pentachlorophenol, phenol, 2-chlorophenol, p-chloro-m-cresol, 2,4-dimethylphenyl, 2,4-dinitrophenol, trichlorophenols, tetrachlorophenols, 2,4-dinitrophenol, cresolates, chrysene, naphthalene, fluoranthene, benzo(b)fluoranthene, benzo(a)pyrene, indeno(1,2,3-cd)pyrene, benzo(a)anthracene, dibenz(a,h)anthracene, scorpaphthalene.	K024	Phthalic anhydride, 1,4-naphthoquinone.
K002	Hexavalent chromium, lead.	K025	Meta-dinitrobenzene, 2,4-dinitrotoluene.
K003	Hexavalent chromium, lead.	K026	Paraldehyde, pyridines, 2-picoline.
K004	Hexavalent chromium, lead.	K027	Toluene diisocyanate, toluene-2, 4-diamine.
K005	Hexavalent chromium, lead.	K028	1,1,1-trichloroethane, vinyl chloride.
K006	Hexavalent chromium, lead.	K029	1,2-dichloroethane, 1,1,1-trichloroethane, vinyl chloride, vinylidene chloride, chloroform.
K007	Cyanide (complexed), hexavalent chromium.	K030	Hexachlorobenzene, hexachlorobutadiene, hexachloroethane, 1,1,1,2-tetrachloroethane, 1,1,2,2-tetrachloroethane, ethylene dichloride.
K008	Hexavalent chromium.	K031	Arsenic.
K009	Chloroform, formaldehyde, methylene chloride, methyl chloride, paraldehyde, formic acid.	K032	Hexachlorocyclopentadiene.
K010	Chloroform, formaldehyde, methylene chloride, methyl chloride, paraldehyde, formic acid, chloroacetaldehyde.	K033	Hexachlorocyclopentadiene.
K011	Acrylonitrile, acetonitrile, hydrocyanic acid.	K034	Hexachlorocyclopentadiene.
K012	Hydrocyanic acid, acrylonitrile, acetonitrile.	K035	Cresolates, chrysene, naphthalene, fluoranthene, benzo(b)fluoranthene, benzo(a)pyrene, indeno(1,2,3-cd)pyrene, benzo(a)anthracene, scorpaphthalene.
K013	Acetonitrile, acrylonitrile.	K036	Toluene, phosphorodithiolo and phosphorothioic acid esters.
K014	Acetonitrile, acrylonitrile.	K037	Toluene, phosphorodithiolo and phosphorothioic acid esters.
K015	Benzyl chloride, chlorobenzene, toluene, benzotrithiolide.	K038	Phosgene, formaldehyde, phosphorodithiolo and phosphorothioic acid esters.
K016	Hexachlorobenzene, hexachlorobutadiene, carbon tetrachloride, hexachloroethane, perchloroethylene.	K039	Phosphorodithiolo and phosphorothioic acid esters.
K017	Epichlorohydrin, chloroethers (bis(chloromethyl) ether and bis (2-chloroethyl) ethers), trichloropropane, dichloropropanols.	K040	Phosgene, formaldehyde, phosphorodithiolo and phosphorothioic acid esters.
K018	1,2-dichloroethane, trichloroethylene, hexachlorobutadiene, hexachlorobenzene.	K041	Toxaphene.
K019	Ethylene dichloride, 1,1,1-trichloroethane, 1,1,2-trichloroethane, tetrachloroethane (1,1,2,2-tetrachloroethane and 1,1,1,2-tetrachloroethane), trichloroethylene, tetrachloroethylene, carbon tetrachloride, chloroform, vinyl chloride, vinylidene chloride.	K042	Hexachlorobenzene, ortho-dichlorobenzene.
		K043	2,4-dichlorophenol, 2,6-dichlorophenol, 2,4,6-trichlorophenol.
		K044	N.A.
		K045	N.A.
		K046	Lead.
		K047	N.A.
		K048	Hexavalent chromium, lead.
		K049	Hexavalent chromium, lead.
		K050	Hexavalent chromium, lead.
		K051	Hexavalent chromium, lead.
		K052	Lead.
		K053	Cyanide, naphthalene, phenolic compounds, arsenic.
		K054	Hexavalent chromium, lead, cadmium.
		K055	Hexavalent chromium, lead, cadmium.
		K056	Hexavalent chromium, lead, cadmium.
		K057	Mercury.
		K058	Chloroform, carbon tetrachloride, hexachloroethane, trichloroethane, tetrachloroethylene, dichloroethylene, 1,1,2,2-tetrachloroethane.
		K059	Aniline, diphenylamine, nitrobenzene, phenylenediamine.
		K060	Arsenic.
		K061	Benzene, dichlorobenzenes, trichlorobenzenes, tetrachlorobenzenes, pentachlorobenzene, hexachlorobenzene, benzyl chloride.
		K062	Lead, hexavalent chromium.
		K063	Phenol, naphthalene.
		K064	Phthalic anhydride, maleic anhydride.
		K065	Phthalic anhydride.

EPA hazard-ous waste No.	Hazardous constituents for which listed	EPA hazard-ous waste No.	Hazardous constituents for which listed
K066	1,1,2-trichloroethane, 1,1,1,2-tetrachloroethane, 1,1,2,2-tetrachloroethane.	K114	2,4-Toluenediamine, o-toluidine, p-toluidine.
K067	1,2-dichloroethane, 1,1,1-trichloroethane, 1,1,2-trichloroethane.	K115	2,4-Toluenediamine.
K068	Chloroform, heptachlor.	K116	Carbon tetrachloride, tetrachloroethylene, chloroform, phosgene.
K069	Toxaphene.	K117	Ethylene dibromide.
K070	2,4-dichlorophenol, 2,4,6-trichlorophenol.	K118	Ethylene dibromide.
K100	Hexavalent chromium, lead, cadmium.	K123	Ethylene thiourea.
K101	Arsenic.	K124	Ethylene thiourea.
K102	Arsenic.	K125	Ethylene thiourea.
K103	Aniline, nitrobenzene, phenylenediamine.	K126	Ethylene thiourea.
K104	Aniline, benzene, diphenylamine, nitrobenzene, phenylenediamine.	K130	Ethylene dibromide.
K105	Benzene, monochlorobenzene, dichlorobenzenes, 2,4,6-trichlorophenol.		
K106	Mercury.		
K111	2,4-Dinitrotoluene.		
K112	2,4-Toluenediamine, o-toluidine, p-toluidine, aniline.		
K113	2,4-Toluenediamine, o-toluidine, p-toluidine, aniline.		

N.A.—Waste is hazardous because it fails the test for the characteristic of ignitability, corrosivity, or reactivity.

[46 FR 4619, Jan. 16, 1981, as amended at 46 FR 27477, May 20, 1981; 49 FR 5312, Feb. 10, 1984; 50 FR 2000, Jan. 14, 1985; 50 FR 42942, Oct. 23, 1985; 51 FR 5330, Feb. 13, 1986; 51 FR 6541, Feb. 25, 1986; 51 FR 37729, Oct. 24, 1986]

APPENDIX VIII—HAZARDOUS CONSTITUENTS

Common name	Chemical abstracts name	Chemical abstracts No.	Hazardous waste No.
Acetonitrile	Same.	75-05-8	U003
Acetophenone	Ethanone, 1-phenyl-	98-06-2	U004
2-Acetylaminofluorene	Acetamide, N-9H-fluoren-2-yl-	53-06-3	U005
Acetyl chloride	Same.	75-36-5	U006
1-Acetyl-2-thiourea	Acetamide, N-(aminothioxomethyl)-	591-08-2	P002
Acrolein	2-Propenal	107-02-6	P003
Acrylamide	2-Propenamide	79-06-1	U007
Acrylonitrile	2-Propenenitrile	107-13-1	U008
Alfatidine	Same.	1402-68-2	
Aldicarb	Propanal, 2-methyl-2-(methylthio)-, O-[(methylamino)carbonyl]iodine.	116-06-3	P070
Aldrin	1,4,5,8-Dimethanonaphthalene, 1,2,3,4,10,10-10-hexachloro-1,4,4a,5,8,8a-hexahydro-(1alpha,4alpha,4beta,5alpha,8alpha,8beta)-.	308-00-2	P004
Allyl alcohol	2-Propen-1-ol	107-18-6	P005
Aluminum phosphide	Same.	20859-73-8	P006
4-Aminobiphenyl	[1,1'-Biphenyl]-4-amine	92-67-1	
5-(Aminomethyl)-3-isoxazolol	3(2H)-isoxazolone, 5-(aminomethyl)-	2763-86-4	P007
4-Aminopyridine	4-Pyridinamine	504-24-5	P008
Amtrite	1H-1,2,4-Triazol-3-amine	61-82-5	U011
Ammonium vanadate	Vanadic acid, ammonium salt	7803-55-6	P119
Aniline	Benzenamine	62-53-3	U012
Antimony	Same.	7440-38-0	
Antimony compounds, N.O.S. ¹	Sulfurous acid, 2-chloroethyl 2-[4-(1,1-dimethylethoxy)-1-methylethyl] ester.	140-57-8	
Arsenic	Same.	7440-38-2	
Arsenic compounds, N.O.S. ¹			
Arsenic acid	Arsenic acid H ₃ AsO ₄	7778-39-4	P010
Arsenic pentoxide	Arsenic oxide As ₂ O ₅	1303-28-2	P011
Arsenic trioxide	Arsenic oxide As ₂ O ₃	1327-53-3	P012
Auramine	Benzenamine, 4,4'-carbonimidoylbis[N,N-dimethyl-]	492-80-8	U014
Azaserine	L-Serine, diazoacetate (ester)	115-02-6	U015

REFERENCE NO. 31

GRAPHICAL EXPOSURE MODELING SYSTEM

(GEMS)

USER'S GUIDE

VOLUME 2. MODELING

Prepared for:

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF PESTICIDES AND TOXIC SUBSTANCES
EXPOSURE EVALUATION DIVISION

Task No. 3-2

Contract No. 68023970

Project Officer: Russell Kinerson

Task Manager: Loren Hall

Prepared by:

GENERAL SCIENCES CORPORATION
8401 Corporate Drive
Landover, Maryland 20785

Submitted: December 1, 1986

E.L. BETH LTD.

LATITUDE 40:30:46 LONGITUDE 74:15:34 1980 POPULATION

	<i>Mile</i> 0-0.25	0.25-0.5	0.5-1.0	1.0-2.0	2.0-3.0	3.0-4.0	SECTOR
KM	0.00- 0.4	0.4- 0.8	0.8- 1.6	1.6- 3.2	3.2- 4.8	4.8- 6.4	TOTALS
S 1	279	4567	19400	19821	25530	43847	113444
RING	279	4567	19400	19821	25530	43847	113444
TOTALS							

REFERENCE NO. 32

CERCLIS DATA BASE DATE: 02/28/92

CERCLIS DATA BASE TIME: 16:51:49

LEVEL: REG 02

SELECTION:

SEQUENCE: REGION, STATE, SITE NAME

** PROD VERSION **

U.S. EPA SUPERFUND PROGRAM

** CERCLIS **

LIST-8: SITE/EVENT LISTING

PAGE NO: 65

VERSION 2.00

RUN DATE: 03/02/92

RUN TIME: 14:10:07

EVENTS: ALL

EPA ID NO.	SITE NAME STREET CITY COUNTY CODE AND NAME	STATE ZIP CONG DIST.	OPRBL UNIT	EVENT TYPE	EVENT QUAL	ACTUAL START DATE	ACTUAL COMPL DATE	CURRENT EVENT LEAD
NJD067484923	E L BETH LTD 500 HIGH STREET PERTH AMBOY 023 MIDDLESEX	NJ 08861 NJ-06	00	DS1			11/01/91	EPA (FUND)
NJD980505077	E. RUTHERFORD JOINT SEWAGE T. P. FOOT OF BOROUGH AVENUE EAST RUTHERFORD 003 BERGEN	NJ 07073 NJ-09	00	DS1			05/31/85	STATE(FUND)
				PA1	LOWER PRIORITY	08/22/90	09/24/90	STATE(FUND)
				SI1	LOWER PRIORITY	02/05/87	03/31/87	STATE(FUND)
NJD930771604	E.I. DUPONT DE NEMOURS CANNONBALL RD POMPTON LAKES 031 PASSAIC	NJ 07442 NJ-08	00	DS1			05/01/85	STATE(FUND)
				PA1	LOWER PRIORITY	05/01/85	06/01/85	STATE(FUND)
				SI1	HIGHER PRIORITY	06/30/89	09/27/89	EPA (FUND)
NJD000420159	E.I. DUPONT DE NEMOURS WASHINGTON RD SAYREVILLE 023 MIDDLESEX	NJ 08859 NJ-15	00	DS1			06/01/81	EPA (FUND)
				PA1	LOWER PRIORITY	07/29/87	08/21/87	STATE(FUND)
				SI1	HIGHER PRIORITY	06/30/89	09/27/89	EPA (FUND)
NJD002185965	E.I. DUPONT DE NEMOURS SOUTH WOOD AVENUE LINDEN 039 UNION	NJ 07036 NJ-15	00	DS1			06/01/81	EPA (FUND)
				PA1	LOWER PRIORITY		09/01/84	STATE(FUND)
				SI1	NO FURTHER REMDL ACT PLND	08/15/85	09/13/85	EPA (FUND)
NJD002385490	E.I. DUPONT DE NEMOURS P.O. BOX 152 (DUPONT ROAD) CARNEYS POINT 033 SALEM	NJ 08069 NJ-02	00	DS1			04/01/79	OTHER
				PA1	NO FURTHER REMDL ACT PLND		09/01/84	STATE(FUND)
				PA2	NO FURTHER REMDL ACT PLND		03/08/89	STATE(FUND)
				SI1	HIGHER PRIORITY	10/01/90	12/17/90	EPA (FUND)
NJD002385730	E.I. DUPONT DE NEMOURS CHAMBERS WORKS /RTE 130 DEEPWATER 033 SALEM	NJ 08023 NJ-02	00	DS1			12/01/79	EPA (FUND)
				PA1	LOWER PRIORITY		03/01/80	EPA (FUND)
				SI1	DEFERRED TO RCRA OR NRC	12/01/79	05/01/80	EPA (FUND)
NJD002444024	E.I. DUPONT DE NEMOURS CHEESFUAKE RD SAYREVILLE 023 MIDDLESEX	NJ 08859 NJ-15	00	DS1			06/01/81	EPA (FUND)
				PA1	LOWER PRIORITY	07/29/87	08/06/87	STATE(FUND)
				SI1	HIGHER PRIORITY	11/01/89	12/31/89	EPA (FUND)

CERCLIS DATA BASE DATE: 02/28/92
CERCLIS DATA BASE TIME: 16:51:49
LEVEL: RFG 02

** PROD VERSION **
U.S. EPA SUPERFUND PROGRAM
** CERCLIS **
LIST-8: SITE/EVENT LISTING

PAGE NO: 63
VERSION 2.00
RUN DATE: 03/02/92
RUN TIME: 14:10:07

SELECTION:
SEQUENCE: REGION, STATE, SITE NAME

EVENTS: ALL

EPA ID NO.	SITE NAME STREET CITY COUNTY CODE AND NAME	STATE ZIP CONG DIST.	OPRBLE UNIT	EVENT TYPE	EVENT QUAL	ACTUAL START DATE	ACTUAL COMPL DATE	CURRENT EVENT LEAD
NJD080654131 (CONTINUED)	DOVER MUNICIPAL WELL 4		(00)	SI2	HIGHER PRIORITY	07/01/80	08/01/82	STATE(FUND)
			01	CO1		03/01/87		STATE ONLY
NJD080771570	DOVER TOWNSHIP LANDFILL BAY & CHURCH STREETS DOVER TWP 029 OCEAN	NJ 08753 NJ-02	00	DS1 PA1 SI1	LOWER PRIORITY HIGHER PRIORITY	10/01/84	04/10/84 09/01/84 11/01/84	STATE(FUND) STATE(FUND) STATE(FUND)
NJD085698686	DOWELL SCHLUMBERGER INCORPORATED MAPLE & JONES BLVD. MOUNT HOLLY 005 BURLINGTON	NJ 08060 NJ-06	00	DS1 PA1 SI1	LOWER PRIORITY NO FURTHER REMDL ACT PLND	05/01/85 09/22/87	04/10/84 06/01/85 09/22/87	STATE(FUND) STATE(FUND) EPA (FUND)
NJD053518536	DREW CHEM CORP 1106 HARRISON AVE KEARNY 017 HUDSON	NJ 07032 NJ-11	00	DS1			11/01/91	EPA (FUND)
NJD001217496	DREW CHEMICAL CORPORATION/PVO 1 DREW CHEMICAL PLAZA BOONTON 027 MORRIS	NJ 07005 NJ-13	00	DS1 PA1 SI1	LOWER PRIORITY NO FURTHER REMDL ACT PLND	05/01/85 10/01/90	04/10/84 05/31/85 12/31/90	STATE(FUND) STATE(FUND) STATE(FUND)
NJD081995508	DREW METALEX CORPORATION WATERWORKS ROAD OLD BRIDGE 023 MIDDLESEX	NJ 08857 NJ-03	00	DS1 PA1	DEFERRED TO RCRA OR NRC		06/06/89 09/27/89	EPA (FUND) EPA (FUND)
NJD054526553	DUANE MARINE 26 WASHINGTON ST PERTH AMBOY 023 MIDDLESEX	NJ 08861 NJ-15	00	RV1 IR2 RV3 DS1 PA1 SI1 OH1	STABILIZATION STABILIZATION HIGHER PRIORITY DEFERRED TO RCRA OR NRC	07/03/84 07/03/84 11/29/84 05/04/87 06/30/89	04/28/87 04/28/87 12/16/84 05/01/79 05/11/87 09/29/89 09/28/84	RESP. PARTY EPA (FUND) EPA (FUND) EPA (FUND) EPA (FUND) EPA (FUND) STATE(FUND) EPA (FUND)
NJD081898819	DUBOIS CHEMICALS UNION AVE & DUBOIS EAST RUTHERFORD 003 BERGEN	NJ 07073 NJ-09	00	DS1 PA1 SI1	LOWER PRIORITY NO FURTHER REMDL ACT PLND	12/01/79	01/01/80 02/01/80 02/01/80	EPA (FUND) EPA (FUND) EPA (FUND)

CERCLIS DATA BASE DATE: 02/28/92

** PROD VERSION **

PAGE NO: 82

CERCLIS DATA BASE TIME: 16:51:49

U.S. EPA SUPERFUND PROGRAM

VERSION 2.00

LEVEL: REGION 02

** C E R C L I S **

RUN DATE: 03/02/92

SELECTION: INTEGRATED

LIST-4: SITE ALIAS LOCATION LISTING

RUN TIME: 13:43:03

SEQUENCE: REG, ST, SITE NAME
REGION: 02

EPA ID	SITE/ALIAS NAME STREET CITY COUNTY NAME	STATE COUNTY CODE	ZIP COUNTY CODE	ALIAS SEQ. #	NAME SOURCE	FED FAC	CONG DIST.
NJ0002355774 (CONTINUED)	DYNASIL CORP OF AMERICA CAMDEN	NJ		01			
NJ0067484923	E L BETH LTD 500 HIGH STREET PERTH AMBOY MIDDLESEX	NJ	08861 023			N	NJ-06
NJ0980505077	E. RUTHERFORD JOINT SEWAGE T. P. FOOT OF BOROUGH AVENUE EAST RUTHERFORD BERGEN	NJ	07073 003		EPA	N	NJ-09
	EAST RUTHERFORD PLANT			01			
NJ0980771604	E.I. DUPONT DE NEMOURS CANNONBALL RD POMPTON LAKES PASSAIC	NJ	07442 031		EPA	N	NJ-08
NJ0000820159	E.I. DUPONT DE NEMOURS WASHINGTON RD SAYREVILLE MIDDLESEX	NJ	08859 023		EPA	N	NJ-15
	DUPONT			01			
	F & F PLANT BURNING GROUND			03			
	PARLIN F & F			04			

CERCLIS DATA BASE DATE: 02/28/92

** PROD VERSION **

PAGE NO: 80

CERCLIS DATA BASE TIME: 16:51:49

U.S. EPA SUPERFUND PROGRAM

VERSION 2.00

LEVEL: REGION 02

** CERCLIS **

RUN DATE: 03/02/92

SELECTION: INTEGRATED

LIST-4: SITE ALIAS LOCATION LISTING

RUN TIME: 13:43:03

SEQUENCE: REG, ST, SITE NAME

REGION: 02

EEA ID	SITE/ALIAS NAME STREET CITY COUNTY NAME	STATE	ZIP	ALIAS SEQ.	NAME	FED	CONG
		COUNTY CODE		7	SOURCE	EAC	DISL

NJD004525553	DUANE MARINE 26 WASHINGTON ST PERTH AMBOY MIDDLESEX	NJ	08861		STS	N	NJ-15
		023					

DUANE MARINE 01

MIDDLESEX NJ

NJD001493819	DUNN'S CHEMICALS UNION AVE & DUBOIS EAST RUTHERFORD BERGEN	NJ	07073		STS	N	NJ-09
		003					

NJD000505051	DUCK ISLAND SANITARY LF LAMPERTON RD HAMILTON TWP MERCER	NJ	08619		STS	N	NJ-04
		021					

DUCK ISLAND 01

RT. 29
TRENTON NJ 08611

INTERSTATE WASTE REMOVAL 02

NJD086574028	DUFFIELD AVENUE DUFFIELD AVENUE JERSEY CITY HUDSON	NJ	07306				NJ-14
		017					


DUFFIELD AVENUE 01

HUDSON NJ

NJD070202611	DURABOND PRODUCTS COMPANY 1000 NOTTINGHAM WAY					N	NJ-04
--------------	--	--	--	--	--	---	-------

REFERENCE NO. 33

CONGRESSIONAL DISTRICTS



Published by the
ELECTION DIVISION
New Jersey Department of State
CN 304
Trenton, New Jersey 08625



Thomas H. Kean
Governor

Jane Burgio
Secretary of State

CONGRESSIONAL DISTRICTS

DISTRICT ONE: Part of Burlington County (Bees River Borough, Beverly City, Cinnaminson Twp., Delanco Twp., Delran Twp., Edgewater Park Twp., Evernden Twp., Hainesport Twp., Lambert Twp., Medford Lakes Borough, Medford Twp., Moorestown Twp., Mount Holly Twp., Mount Laurel Twp., New Hanover Twp., North Hanover Twp., Pemberton Borough, Pemberton Twp., Riverside Twp., Shamong Twp., Southampton Twp., Tabernacle Twp., Washington Twp., Willingboro Twp., Woodland Twp., and Wrightstown Borough), Part of Camden County (Audubon Borough, Cherry Hill Twp., Haddonfield Borough, Beach Haven Borough, Beachwood Borough, Berkeley Twp., Eagleswood Twp., Harvey Cedars Borough, Lacey Twp., Lakehurst Borough, Little Egg Harbor Borough, Long Beach Twp., Manchester Twp., Ocean Gate Borough, Ocean Township, Pine Beach Borough, Plumstead Twp., Seaside Park Borough, Ship Bottom Borough, Stafford Twp., Surf City Borough and Tuckerton Borough),

DISTRICT TWO: Atlantic County, Cape May County, Cumberland County, Salem County and Part of Gloucester County (E. Twp., Franklin Twp., Glassboro Borough, Mantua Twp., Newfield Borough, Pitman Borough and South Harrison Twp.),

DISTRICT THREE: Part of Monmouth County (Allentown Borough, Asbury Park City, Atlantic Highlands Borough, Avon-by-the-Sea Borough, Belmar Borough, Bradley Beach Borough, Deal Borough, Eatontown Borough, Fair Haven Borough, Hazlet Twp., Highlands Borough, Interlaken Borough, Keansboro Borough, Keasport Borough, Little Silver Borough, Loch Arbut Village, Long Branch City, Manasquan Borough, Middletown Twp., Monmouth Beach Borough, Neptune City Borough, Neptune Twp., Oceanport Borough, Ocean Twp., Red Bank Borough, Rumson Borough, Sea Bright Borough, Sea Jett Borough, Shrewsbury Borough, Shrewsbury Twp., Spring Lake Borough, Spring Lake Heights Borough, South Belmar Borough, Union Falls Borough, Union Beach Borough and West Long Branch Borough and Part of Ocean County (Bay Head Borough, Brick Twp., Dover Twp., Island Heights Borough, Lakewood Twp., Lavelle Borough, Mantoloking Borough, Point Pleasant Beach Borough, Point Pleasant Borough, Seaside Heights Borough and South Twp. River Borough),

DISTRICT FOUR: Part of Burlington County (Bordentown City, Bordentown Twp., Burlington City, Burlington Twp., Chesterfield Twp., Eastampton Twp., Fieldsboro Borough, Florence Twp., Mansfield Twp., Springfield Twp., and Westampton Twp., Part of Mercer County (East Windsor Twp., Ewing Twp., Hamilton Twp., Hightstown Borough, Hopewell Borough, Hopewell Twp., Lawrence Twp., Pennington Borough, Trenton City and Washington Twp., Part of Middlesex County (Jamesburg Borough, Monroe Twp., and Plainsboro Twp.), Part of Monmouth County (Allentown Borough, Bristol Borough, Colts Neck Twp., Englishtown Borough, Farmingdale Borough, Freehold Borough, Freehold Twp., Holmdel Twp., Howell Twp., Manalapan Twp., Marlboro Twp., Millstone Twp., Roosevelt Borough, Upper Freehold Twp., and Wall Twp.), and Part of Ocean County (Jackson Twp.),

DISTRICT FIVE: Part of Bergen County (Allendale Borough, Alpine Borough, Bergenfield Borough, Closter Borough, Emerson Borough, Emerson Twp., Glen Rock Borough, Harrington Park Borough, Hawthorth Borough, Hillsdale Borough, Mahwah Borough, Manasquan Borough, Montvale Borough, Northvale Borough, Norwood Borough, Oakland Borough, Old Tappan Borough, Oradell Borough, Paramus Borough, Park Ridge Borough, Ramapo Borough, Ridgewood Village, River Vale Twp., Rochelle Park Twp., Rockleigh Borough, Saddle River Borough, Tenafly Borough, Upper Saddle River Borough, Weehawken Borough, Weehawken Twp., Westwood Borough, Woodcliff Lake Borough and Wyckoff Twp.), Part of Passaic County (Bloomfield Borough, Mahwah Borough, Hawthorne Borough, North Mahwah Borough, Ringwood Borough, Ringwood Twp., and West Milford Twp.), and Part of Sussex County (Andover Borough, Andover Twp., Branchville Borough, Frankford Twp., Franklin Borough, Freedom Twp., Hamburg Borough, Hardiston Twp., Hopatcong Borough, Lafayette Twp., Montague Twp., Newton Town, Odessa Borough, Sandvick Twp., Sparta Twp., Stanhope Borough, Sussex Borough, Vernon Twp., Walpack Twp., and Wantage Twp.),

DISTRICT SIX: Part of Middlesex County (Carteret Borough, Edison Twp., Highland Park Borough, Metuchen Borough, New Brunswick City, North Brunswick Twp., Old Bridge Twp., Perth Amboy City, Sayreville Borough, South Amboy City, South River Borough and Woodbridge Twp.), Part of Monmouth County (Aberdeen Twp., and Matawan Borough), and Part of Union County (Linden City, Rahway City and Roselle Borough),

DISTRICT SEVEN: Part of Essex County (Millburn Twp.), Part of Middlesex County (Dunellen Borough and Middlesex Borough), Part of Somerset County (Bound Brook Borough, Bridgewater Twp., Green Brook Twp., Manville Borough, North Plainfield Borough, Warren Twp., and Watchung Borough), and Part of Union County (Berkeley Heights Twp., Clark Twp., Cranford Twp., Elizabeth City, Farwood Borough, Garwood Borough, Kenilworth Borough, Mountainside Borough, New Providence Borough, Plainfield City, Roselle Park Borough, Scotch Plains Twp., Springfield Twp., Summit City, Union Twp., Westfield Town and Winfield Twp.),

DISTRICT EIGHT: Part of Bergen County (Franklin Lakes Borough), Part of Essex County (Part of Belleville Town, Bloomfield Town, Glen Ridge Borough, Montclair Town and Nutley Town), Part of Morris County (Riverdale Borough) and Part of Passaic County (Clifton City, Little Falls Twp., Passaic City, Paterson City, Pompton Lakes Borough, Prospect Park Borough, Totowa Borough, Wayne Twp., and West Paterson Borough),

DISTRICT NINE: Part of Bergen County (Bohota Borough, Carlstadt Borough, Cliffside Park Borough, East Rutherford Borough, Edgewater Borough, Englewood Park Borough, Englewood City, Englewood Cliffs Borough, Fair Lawn Borough, Fairview Borough, Fort Lee Borough, Garfield City, Hackensack City, Hackensack Heights Borough, Leonia Borough, Little Ferry Borough, Lodi Borough, Lyndhurst Twp., Maywood Borough, Moonachie Borough, New Milford Borough, North Arlington Borough, Palisades Park Borough, Ridgefield Borough, Ridgefield Park Village, River Edge Borough, Rutherford Borough, Saddle Brook Twp., South Hackensack Twp., Teaneck Twp., Totterdore Borough, Wallington Borough and Wood-Ridge Borough, and Part of Hudson County (East Newark Borough, Part of Kearny Town, and Secaucus Town),

DISTRICT TEN: Part of Essex County (Part of Belleville Town, East Orange City, Irvington Town, Newark City and Orange City), and Part of Union County (Millside Township),

DISTRICT ELEVEN: Part of Essex County (Caldwell Borough, Cedar Grove Twp., Essex Falls Borough, Fairfield Borough, Livingston Twp., Maplewood Twp., North Caldwell Borough, Roseland Borough, South Orange Village, Verona Borough, West Caldwell Borough and West Orange Town), Part of Morris County (Boonton Town, Boonton Twp., Butler Borough, Chatham Borough, Chester Borough, Chester Twp., Danville Twp., Dover Town, East Hanover Twp., Glenburn Park Borough, Hanover Twp., Jaffrey Twp., Kinnelon Borough, Lincoln Park Borough, Madison Borough, Mendham Borough, Mendham Twp., Mine Hill Twp., Montville Twp., Mountain Lakes Borough, Mount Arlington Borough, Mount Olive Twp., Netcong Borough, Parsippany-Troy Hills Twp., Pequannock Twp., Randolph Twp., Rockaway Borough, Rockaway Twp., Roxbury Twp., Victory Gardens Borough and Sharon Borough), Part of Sussex County (Byram Twp., and Green Twp.) and Part of Warren County (Allamuchy Twp., Frelinghuysen Twp., Independence Twp., and Liberty Twp.),

DISTRICT TWELVE: Hunterdon County, Part of Mercer County (Princeton Borough, Princeton Twp., and West Windsor Twp.), Part of Middlesex County (Cranbury Twp., East Brunswick Twp., Helmette Borough, Milltown Borough, Morristown Twp., Piscataway Twp., South Brunswick Twp., South Plainfield Borough and Southwood Borough), Part of Morris County (Chatham Twp., Harding Twp., Morris Plains Borough, Morristown Town, Morris Twp., Passaic Twp., and Washington Twp.), Part of Somerset County (Barnegat Twp., Bernards Twp., Bernardsville Borough, Branchburg Twp., Far Hills Borough, Franklin Twp., Hillsborough Twp., Millstone Borough, Montgomery Twp., Peapack-Gladstone Borough, Reiten Borough, Rocky Hill Borough, Somerville Borough, and South Bound Brook Borough), Part of Sussex County (Hampton Twp., and Skillwater Twp.), and Part of Warren County (Alpine Borough, Belvidere Town, Blairstown Twp., Franklin Twp., Greenwich Twp., Hackettstown Town, Hardwick Twp., Harmony Twp., Hope Twp., Knowlton Twp., Lopatcong Twp., Mansfield Twp., Oxford Twp., Panamint Twp., Phillipsburg Town, Pohatcong Twp., Washington Borough, Washington Twp., and White Twp.),

DISTRICT THIRTEEN: Part of Burlington County (Bees River Twp., Beverly City, Cinnaminson Twp., Delanco Twp., Delran Twp., Edgewater Park Twp., Evernden Twp., Hainesport Twp., Lambert Twp., Medford Lakes Borough, Medford Twp., Moorestown Twp., Mount Holly Twp., Mount Laurel Twp., New Hanover Twp., North Hanover Twp., Pemberton Borough, Pemberton Twp., Riverside Twp., Shamong Twp., Southampton Twp., Tabernacle Twp., Washington Twp., Willingboro Twp., Woodland Twp., and Wrightstown Borough), Part of Camden County (Audubon Borough, Cherry Hill Twp., Haddonfield Borough, Beach Haven Borough, Beachwood Borough, Berkeley Twp., Eagleswood Twp., Harvey Cedars Borough, Lacey Twp., Lakehurst Borough, Little Egg Harbor Borough, Long Beach Twp., Manchester Twp., Ocean Gate Borough, Ocean Township, Pine Beach Borough, Plumstead Twp., Seaside Park Borough, Ship Bottom Borough, Stafford Twp., Surf City Borough and Tuckerton Borough),

DISTRICT FOURTEEN: Part of Hudson County (Bayonne City, Guttenberg Town, Harrison Town, Hoboken City, Jersey City, Part of Kearny Town, North Bergen Twp., Union City, Weehawken Twp., and West New York Town),

ATTACHMENT 3

SITE ASSESSMENT PHASES

1. PRELIMINARY ASSESSMENT/RCRA PRELIMINARY ASSESSMENT

- * Quick, Low Cost Review of Readily Accessible Records and Reports
- * Undertaken to Determine the Existence of a Problem and the Need for Further Action at a Site by Characterizing:
 - Magnitude of the Hazard
 - Source and Nature of the Release or Potential Release
 - Identity of Potentially Responsible Party(s) (PRP)
- * Does Not Include On-Site Visits or Sample Collection

2. SITE INSPECTION

- * The Purpose of the Site Inspection is to:
 - Determine the Necessity of Further Action
 - Further Define and Characterize the Problem
 - Provide Data for the Hazard Ranking System (HRS) Scoring and Compute Initial Score
- * The Site Inspection Involves an On-Site Visit and Sampling (10+/- Samples)
- * A Site Inspection is not an Extent of Contamination Study
- * A Site Inspection Avoids Use of More Sophisticated Analysis
 - Geophysical Survey

3. SITE INSPECTION PRIORITIZATION


- * Quick, Low Cost Review of Readily Accessible Records and Reports
- * Undertaken to Determine the Validity and Update Background Conditions Under the New HRS Model, and the Need for Further Action at a Site by Characterizing:
 - Magnitude of the Hazard
 - Source and Nature of the Release or Potential Release
- * Included On-Site Visits or Sample Collection
 - Analyze Samples/Limited Analytical Resources
 - Account for Significant Safety Hazards On-Site

4. EXPANDED SITE INSPECTION

A Follow-Up Inspection May Be Recommended After the SI To:

- * Gather Additional Data Necessary to Strengthen or Substantiate the Initial HRS Score
 - Geophysical Surveys
 - Installation of Groundwater Monitoring Wells
 - Additional Sampling

SITE ASSESSMENT PHASES



Review of Analytical Data

If previous analytical data are available, they should be reviewed for information which supports the design of the sampling and analysis program, tests site hypotheses, and documents the site score. The SI investigator should review all previous analytical data. While analytical data collected for other purposes may not meet SI objectives, site-specific analytical data are generally helpful in better understanding the nature of the problem at the site, regardless of data sources or data quality. The depth of the review depends on the overall quality and quantity of data, the intended use of the data, and whether they are representative of current site conditions and comparable to SI data. Determining whether available data can be applied as SI-generated data requires the professional judgement of an experienced reviewer. Both validated and non-validated analytical data may be available. Previous SI data will be validated and of CLP-quality. Non-validated data may contain false positives and false negatives, as well as quantitation, transcription, and calculation errors. If data of unknown or questionable quality are used for decision-making, the investigator should review all available information to assess the level of certainty associated with the data. If these data are used for HRS documentation, data validation may be necessary. The investigator may be able to determine the general quality of the data set by reviewing QC data. False positives can occur when blanks are contaminated or spike recoveries are very high. False negatives can occur if spike recoveries are very low. If hazardous substances are found in one duplicate but not the other, results may be false positive or negative.